

**PRICE BID - SBI RBO - III JAMNAGAR - INTERIOR FURNISHING WORK**

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	<b>GENERAL NOTES FOR : For FOR ALL ITEMS</b>				
	<b>Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIS, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED</b>				
<b>I</b>	<b>WORK STATION / COUNTER</b>				
	<b>GENERAL NOTES FOR : For all work stations</b>				
	The W.S. should have <b>READY MADE leg rest</b> , HIGH IMPACT POLYSTYRENE WITH CHROME PLATED METAL STRUCTURE				
	There should be provision for <b>cable manager</b> system with necessary cutouts in top surface				
	<b>C.P.U. trolley</b> from Steel with lockable roller supports/ Nylon castors.				
	<b>Key board tray</b> made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it.				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) Table Top : 1 mm thick thick laminate & Burma Teak beading on Edges with lacquer polish				
	2) <b>Front Apron &amp; Sides: 1 mm thick thick laminate &amp; Burma Teak beading on Edges with lacquerpolish</b>				
	3) <b>Facing of Drawers: 1 mm thick thick laminate &amp; Burma Teak beading on Edges with lacquerpolish</b>				
	4) <b>All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate</b>				
	5) All the wooden surface : polished of approved shade				
	As per drawing and instruction of Architect/Bank Complete.				
1	<b>ASSISTANT GENERAL MANAGER TABLE SIZE : 8'-0" X 3'-6" X 2'-6"+ SIDE RACK - SIZE: 4'0" X 1'6" X 2'6"</b> with 1 mm thick LAMINATE finish on Table Top, sides & Edges and all other visible surfaces etc complete as follows	1.00	NO		
	<b>TABLE</b>				
	Supplying and installation of Table as per the following description : Size 8'0" x 3'-9". Table top shall be made from 18 mm thick commercial ply wood with 1 mm thick laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. . Computer Key board of metal of approved make shall be provided. Exposed surfaces of the unit shall have 1 mm th laminate finish <b>ready made Foot rest</b> shall be provided. All internal surface will have 0.60 mm thick balacing laminate				
	Apron (Modesty Panel) & Table sidemade from 18 mm thick ply wood finished 1 mm laminate Finish All visible area should be in 1 mm laminate finish.The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood drawer unit of 1'-4" x 2'-0" x 2'-0" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make, grouplock, S.S. Handle				
	<b>SIDE RACK - SIZE: 4'0"X1'6"X 2'6"</b>				
	Supplying and providing side cabinet : Having openable shutters as directed. Cabinet shall be made from 18mm thick commercial ply wood with 1.00mm thick thick laminate. back shall be made from 6mm th commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with veneer finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers.				
	<b>As per drawing and instruction of Architect/Bank Complete</b>				
	<b>FINISHING DETAILS IN NUTSHELL:</b>				
	1) <b>Table Top</b> : Teak Veneer with PU Coating & Burma Teak beading on Edges with PU Coating				
	2) <b>Front Apron &amp; Sides:</b> Teak Veneer with PU Coating				
	3) <b>Facing of Drawers:</b> Teak Veneer with PU Coating				

**PRICE BID - SBI RBO - III JAMNAGAR - INTERIOR FURNISHING WORK**

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	<b>GENERAL NOTES FOR : For FOR ALL ITEMS</b>				
	<b>Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIS, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED</b>				
2	<b>CM W.S. - SIZE : 6'-0"X 2'-9"X 2'-6"</b> + SIDE RACK - SIZE : 3'-3"X1'-4"X2'-6" As / item no. 1 / 01 but with different in size Other specifications remains the same.	4.00	NO		
3a	<b>MGR W.S. - SIZE : 5'-3"X 2'-6"X 2'-6"</b> + SIDE RACK - SIZE : 2'-6"X1'-4"X2'-6" As / item no. 1 / 01 but with different in size & without pencil drawer. Other specifications remains the same.	3.00	NO		
3b	<b>MGR W.S. - SIZE : 5'-3"X 2'-6"X 2'-6"</b> + SIDE RACK - SIZE : 3'-3"X1'-4"X2'-6" As / item no. 1 / 01 but with different in size & without pencil drawer. Other specifications remains the same.	1.00	NO		
4a	<b>OFFICER'S W.S. - SIZE : 5'-0"X 2'-6"X 2'-6"</b> + SIDE RACK - SIZE : 3'-3"X1'-4"X2'-6" As / item no. 1 / 01 but with different in size & without pencil drawer. Other specifications remains the same.	7.00	NO		
4b	<b>OFFICER'S W.S. - SIZE : 5'-0"X 2'-6"X 2'-6"</b> + SIDE RACK - SIZE : 2'-6"X1'-4"X2'-6" As / item no. 1 / 01 but with different in size & without pencil drawer. Other specifications remains the same.	2.00	NO		
5a	<b>CLERK'S W.S. - SIZE : 4'-3"X 2'-6"X 2'-6" - without side rack</b> As / item no. 1 / 01 but with different in size & without pencil drawer & side rack. other specifications remains the same.	2.00	NO		
6	<b>CLERK'S W.S. ( cluster ) - to the shape I type - SIZE : 5'-0"X 5'-0"X 2'-6"</b> as per above but will be fixed to the low hight partition there will be no front apron	20.00	NO		
7	<b>CONFERENCE TABLE</b> The basic structure of the Conference table shall be made out of 18 mm ply with all open edges covered with wooden beading of req. size. The top shall be of 18 mm th. ply + additional 18 mm th. ply patta with T.W. besding of 1 1/2"x 1/2" on external sides & 3" box made out of 18 mm ply. on internal sides, <u>can be made openable to operate from the bottom for cabelling purpose</u> . The middle vertical supports shall be of 18 mm ply with 1 mm laminate on both side & T.W. beading. The front apron will have grooves pattern in laminate. The W.S. should have 3" X 1 1/2" T.W. leg rest .There should be provision for cable manager system with necessary cutouts in top surface. The horizontal TOP shall be in 6 mm th. SOLID SURFACE( curian) finish & ON vertical surfaces on all open external sides WILL HAVE LAMINATE. It will be in balancing laminate( matching to veenear) on internal surfaces. All the wooden borders / members / veenear shall be in a melamine finish	16.00	RMT		
8a	<b>DINNING TABLE: 6' 0"x 3'0"x 2'6"</b> Supplying and installation of Dining Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.	1.00	NO		

**PRICE BID - SBI RBO - III JAMNAGAR - INTERIOR FURNISHING WORK**

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	<b>GENERAL NOTES FOR : For FOR ALL ITEMS</b>				
	<b>Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIS, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED</b>				
8b	<b>DINNING TABLE: 4' 0"x 2'3"x 2'6"</b> <b>as per above but different in size</b>	1.00	NO		
9	<b>LUNCH counter (2' 0" WIDE) IN JET BLACK</b> Providing and laying platform of 1'9" width (clear width) and at 2'6" height (finished top level) from floor . BWR ply wood 19mm thick supported on Steel L angle bracket. The plat form should be cantilevered from the wall as shown in the drawing. 9" wide 19mm thick BWR ply wood to be provided below the entire lunch counter for Tiffin and kitchen items. The ply surface to be covered with 1 m m laminate as per required shape and size	3.50	RMT		
10	<b>SORTING / MASSANGER COUNTER- Linear Table with Drawer - 2'0" WIDE</b> Providing and fixing Linear Table having width of 2'-0" using 18 mm thick Commercial plywood for Top and verticle support at 4'-0" c/c, Providing storage cabinet Two drawer and One shutter Unit at Every 4'-0" c/c,Group lock, SS handle in counter as directed complete. 1.0 mm thick Laminate finish on table Top and front side of shutter. Providing Foot rest of 3" x 1.5" in C.P. Teak wood with lacquered polish. All internal surfaces shall have 0.60 mm thick balacing laminate as directed.	2.50	RMT		
11	<b>WOODEN PLANTER : 1'6"x 1'6"x 1'6"- to the shape between the curved sofa</b> <b>P/F planter box with using 18 mm thick MR Grade plywood</b> on all sides with 1.00 mm Thick Laminate as per requirement and drawing etc complete as directed.	3.00	NO		
<b>II</b>	<b>PARTITIONS / GLAZING</b>				
<b>1</b>	<b>FULL HEIGHT PARTITITONS</b>				
<b>a</b>	<b>P &amp; F FULL HEIGHT PARTITIONS - PARTLY PANELLED / PARTLY GLAZED including door</b>	156.00	SMT		
	<b><u>BASIC STRUCTURE:</u></b>				
	P & F full height partitions made from internal frame work of size 2"x1" x min. 1.5 mm th. Alu. sections, fixed by means of al. angle of 1"x1"x1" size for proper fixity. The entire Alu. frame work shall be covered with <b>12 mm th.MDF</b> on both the sides. All open sides of the framework shall be covered with the <b>12 mm th.MDF</b> to cover the entire thickness of the partition. The upper portion rom 3' to 7' of the partitions will have 6 / 8 mm th. clear glass required as per size of glass, fixed with 2 1/2"x1/2" (F.S.) wooden molding with suggested grooves to cover the full thickness of the partition.The hinge side aluminum frame shall be in filled with wooden section. The same shall be than covered by 12 mm th. MDF panels to get the flush type partitions.				
	<b><u>GENERAL:</u></b>				
	All the gaps either vertical or horizontal shall be filled properly with ideal material. All the vertical members of the partitions shall be carefully inserted / fixed in the floor (without damaging the floor) & also shall be fixed to the structural ceiling for proper strength.Necessary provision shall be made in the partition for ele. Conduits, switch boards,a.c. drain lines & ac's. etc.as req. The door shutters are included in this item. The common member of partition and frame of door will be considered in the item of partitions). Only below ceiling area will be considered for measurement purpose, however the partition shall be raised atleast by 3" above the false ceiling level for having fixity for the ceiling & also all vertical member shall be taken up to the slab / beam bottom.				
	<b>P &amp; f of internal door shutters made out of 30 mm th flush door</b> with suggested grooves with 6/8 mm th. clear glass fixed with 10 mm th. wooden molding to cover full th. of the shutter. including 3 Nos 5" long SS hinges with countersunk SS screws, Godrej Mortice lock, S.S Handles,Door stoppers, doorstop of approved make etc. complete as per drawing & instructions				

**PRICE BID - SBI RBO - III JAMNAGAR - INTERIOR FURNISHING WORK**

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	<b>GENERAL NOTES FOR : For FOR ALL ITEMS</b>				
	<b>Plywood (IS 303 BWP) ANTI TERMITE PROPERTIS, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED</b>				
	<b>FINISHES:</b>				
	All the external plywood components shall be finished with 1 mm th. laminate in on both the sides & also in the thickness of the partition. All external wooden members shall be in melamine matt polish finish.				
	<b>THE PPPG FHP SHALL BE FIXED IN POSITION AS / INST.</b>				
2	<b>P &amp; F LOW HEIGHT PARTITIONS – 4'-0"HT</b>	45.00	SMT		
	<i>As / item no. II / 01a but with different in ht &amp; REGULAR glass. Other specifications remains the same.</i>				
	<b>WICKET GATE</b>				
	P/F one no of 30 mm thick flush shutter( 2 NOS ) with both side laminate including 5" SS hinges with countersunk SS screws, Approved make Night latch Lock, S.S Handles,Door stoppers,150 mm long Door stoppers, doorstop of approved make etc.				
3	<b>Providing and fixing "Dorma/Ozone/Godrej " or equivalent make door closure.</b>	17.00	NO		
	<b>III PANELLING &amp; BOXING</b>				
1	<b>P/F Wall panelling with framing laminate finishing for wall and Pillar etc</b>	21.60	SMT		
	Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. .				
2	<b>Providing and fixing 18 mm thick plywood of 4" height skirting with 1.0 mm thick laminate finish runner patta on Storage Top / Table Top if required.etc complete as directed.</b>	16.00	RMT		
3	<b>P/F Wall panelling without framing laminate finishing for wall and Pillar etc /Creating Box for fixing AC machine and concealing of copper and drain pipe and around front side main entrance door top, jambs using 18 mm thick MR Grade plywood with 1.00 mm Thick Laminate as per requirement and drawing etc complete as directed.</b>	50.00	SMT		
4	<b>Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing &amp; direction with all labour &amp; materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will be made for any cutting in the film.</b>	27.00	SMT		
	<b>IV STORAGE CABINETS</b>				
1	<b>GENERAL PURPOSE STORAGE CABINETS – OF VARIOUS SIZES &amp; VARIOUS HEIGHTS</b>				
	<b>NOTE : FINISHES for all storage</b>				
	The entire unit shall be in 1 mm laminate finish on external vertical sides and in balancing laminate finish on internal surface. The wooden borders shall be in melamine matt polish finish.				
1[A]	<b>GENERAL PURPOSE</b>	65.00	SMT		
	<b>BASIC STRUCTURE:</b>				
	P & F 1'-4" deep storage cabinet. The basic structure of the cabinet including shelves shall be made of 18 mm ply. It will 6 mm th. plywood puthi. For low height storage the top shall be like additional ¼" ply patta to get 1" thickness . The storage unit should have 18 mm th. ply openable shutters. It should with all S.S hinges, towers bolts, powder coated handle, ball catches, S.S approved make (group lock) multi purpose lock complte. Edges to be finished with teak wood lipping etc have 18 mm th. ply vertical & horizontal fixed shelves. The top will have 1"x1" wooden beading on 1 longer side.				

**PRICE BID - SBI RBO - III JAMNAGAR - INTERIOR FURNISHING WORK**

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
<b>GENERAL NOTES FOR : For FOR ALL ITEMS</b>					
<b>Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIS, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED</b>					
<b>2</b>	<b><u>ELECTRIC PANEL CABINET</u></b>	<b>4.50</b>	<b>SMT</b>		
	P & F 1'-4" deep storage cabinet as shown. The basic structure of the cabinet including dividers & shelves shall be made of 18 mm Bison panel sheet. It would not have any puthi but shall have req. additional supports to fix the same to the wall. It will have openable shutters as required & shall be made with 2"x1"x min. 1.2 mm th. Alu. Section framework covered with 6 mm bison panel sheet on all sides with 16. Gu. powder coated perforated S.S sheet as infill material.shutter with approved make handle, hinges,ball catches				
<b>3</b>	<b><u>P/F PANTRY PLATFORM CUPBOARD SHUTTER / drawer unit</u></b>	<b>2.60</b>	<b>SMT</b>		
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiate for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed.				
	<b>IT WILL HAVE 1 DRAWER UNIT OF 3 NOS OF DRWERS /AS / DRAWING</b>				
<b>V</b>	<b><u>MIS. FURNISHING ITEMS</u></b>				
<b>1</b>	<b><u>PINUP BOARD</u></b>	<b>6.00</b>	<b>SMT</b>		
	P & F pinup boards. It consist 12 mm th. soft boards of good density to be mounted over 12 mm ply. & covered with 3/4" x 1/4" beading before putting the fabric. The soft board will be covered with a plain (Basic rate Rs. 240 /- per mtr.) from front and edges. Molding of size: 3/4"x1/4" will be fixed on all four sides & will be finished in melamine polish. (Only soft boards provided other than the partitions will be measured and soft board made in the partitions will be the part of the partition)fabric				
<b>2</b>	<b><u>Supplying and installation 1'-9" x 1'-9" x 1'-3" height for Corner Tepoy</u></b>	<b>6.00</b>	<b>NO</b>		
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed. [REFER DRG NO-5]				
<b>3</b>	<b><u>Supplying and installation 2'0"dia x 1'6" height for Center Tepoy</u></b>	<b>1.00</b>	<b>NO</b>		
<b>4</b>	<b><u>visitors sofa</u></b>	<b>20.50</b>	<b>RMT</b>		
	The seat shall be made out of 19 mm BB in a box form. The back shall be made out using internal wooden frame work of size 2"x1 1/2" covered with 6 mm ply. It shall be covered with 100 mm & 50 mm th. 40 density u foam in seat & back respectively. This should be again covered with 14 mm th. 40 density u foam with madarpat cover on it & upholstered of				
	suggested shade & finish in seat & back on all open visible sides with basic rate of Rs.900/- per meter. It will have wooden handlesas / drawing. outer length with armrest will be considered for measurement purpose. [REFER DRG NO-5]				
<b>5</b>	<b><u>ROLLER BLIND</u></b>	<b>72.00</b>	<b>SMT</b>		
	Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Including GST)				
<b>6</b>	<b><u>P/A WALL PAPERS on Digital wall</u></b>	<b>24.00</b>	<b>SMT</b>		
	Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft				

**PRICE BID - SBI RBO - III JAMNAGAR - INTERIOR FURNISHING WORK**

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : For FOR ALL ITEMS				
	<i>Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIS, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED</i>				
<b>VI</b>	<b><u>FALSE CEILING WORK</u></b>				
<b>1</b>	<b><u>P/F GYPSUM BOARD FALSE CEILING</u></b>	<b>321.00</b>	<b>SMT</b>		
<b>1[A]</b>	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section <b>of Gypsteel ULTRA ( Gypsteel Ultra shall be used)</b> supporting system in line and level. Finishing the surface and <b>applying 3 coats of Plastic emulsion paint</b> as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.				
	Note : (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMT and paid in SqM (3) Only finished visible surface area shall be measured for payment.				
<b>2</b>	<b><u>Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid</u></b>	<b>192.00</b>	<b>SMT</b>		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. <b>Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose</b>				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				
<b>3</b>	<b><u>P &amp; F WOODEN CEILING WITH -GROOVES AS PER DESIGN</u></b>	<b>7.00</b>	<b>SMT</b>		
	Same as above but providing and fixing of 8 mm thick MDF + 1 MM LAMINATE instead of Gypsum Board etc complete as per design and instruction. Only finished surface area shall be measured for payment.				
	<b>TOTAL QUOTED AMOUNT (Rs.)</b>			<b>Rs.</b>	