

PRICE BID FOR THE INTERIOR FURNISHING WORKS AT SBI RASMAC - CHANGANASSERY, AS PER UNIFORM INTERNAL LAYOUT (NEW BRANCH PREMISES)

SI.N o	DESCRIPTION OF WORK	Quantity	Unit	Rate	Amount
1	<p>LOW HEIGHT PARTITION : For Open seats : Providing and fixing of Low height partitions for work stations of 1200 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1200 mm level fixed in position. 8 mm plywood both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Clear float glass of 12 mm thick and of approved band with etching shall be fixed with SS D Brackets for a height of 500 mm above the solid partition.</p>	94	Sq.M		
2	<p>Custom Made Full Height Solid Partition : Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves . Measurement for the partition area shall be considered from floor level to false ceiling level only.</p>	81	Sq.M		
3	<p>Partly solid and partly glazed partition :- Supply and set in position of custom made partly solid and partly glazed full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. 8 mm plywood on both sides of frame work from the floor level to false ceiling level finished with 1 mm laminate on both sides including necessary grooves . 12 mm thick toughened glass of good quality to be provided at a height of 90cm from FFL to 210 cm from FFL, including 3M Vinyl sticker / etching as per approved colour design / patterns etc complete.. Measurement for the partition area shall be considered from floor level to false ceiling level only.</p>	74	Sq.M		
4	<p>Fixed glass partitions : Supply and installation of Full height straight glass partition 12mm thick toughened glass and proprietary anodized aluminium sections of the SLIM LINE series of approved make 80x18mm thick. providing widline section (105x25mm) at around the door two vertical upto false ceiling and horizontal at door top The sections shall be matt natural anodized and shall be a combination of SAP 004 and 005 on all four sides as per the manufacturers specification and shall be inclusive of all accessories like stake1, stake3 and wedge 3G/B from FFL to the bottom of false ceiling height. The glass joints shall be filled with silicon sealant on both side. Rate shall include for providing transport charges, handling, loading and unloading & installation of all necessary hardware's, scaffolding,wastage, Structural supports if any, etc. complete and all as per manufacturers specifications as directed. Etching stickers are to be provided as per design. Fixing flush stop of size 20mmx15mm for door frame visible joint, grooves of size 12 mm etc complete.</p>	108	Sq.M		
5	<p>Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make.</p>	15	Sq.M		

PRICE BID FOR THE INTERIOR FURNISHING WORKS AT SBI RASMAC - CHANGANASSERY, AS PER UNIFORM INTERNAL LAYOUT (NEW BRANCH PREMISES)

SI.No	DESCRIPTION OF WORK	Quantity	Unit	Rate	Amount
6	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	17	Sq.M		
7	Gypsum Board False Ceiling : Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough . Frame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls around perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete.	588	Sq.M		
8	AGM Table : Providing and fixing AGM's table of size 2400mm x 800mm X 750 mm high to detail as shown in drg. Comprising table top out of 25mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip.12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood finished with 1 mm laminate. All the internal and external exposed face of plywood to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete.Aqua blue shade of saint Gobain (or) equivalent toughened glass panel to be fixed on the 18mm thick ply on front vertical laminated Plywood Board with SS studs. Additional horizontal support to be provided below the table top in order to avoid sagging.	1	No.		
9	Side Tables For AGM : Providing and fixing side unit for AGM table to detail as per drg. of size 1200mm x 600 mm made of 25 mm Plywood finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc.,complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	1	No.		
10	Table for Officers 150cm : Providing and fixing Officer's table of size 1500mm x 750mm X 750 mm high to detail as shown in drg. as per specification in item no.9 above. 12 mm thick glass with polished edges to be provided on table top.	24	No.		

PRICE BID FOR THE INTERIOR FURNISHING WORKS AT SBI RASMAC - CHANGANASSERY, AS PER UNIFORM INTERNAL LAYOUT (NEW BRANCH PREMISES)

Sl.No	DESCRIPTION OF WORK	Quantity	Unit	Rate	Amount
11	Table for Clerk 120cm : Providing and fixing Officer's table of size 1200mm x 750mm X 750 mm high to detail as shown in drg. as per specification in item no.9 above. 12 mm thick glass with polished edges to be provided on table top.	26	No.		
12	Table of size 100cm : Providing and fixing table of size 1000mm x 600mm X 750 mm high to detail as shown in drg. as per specification in item no.9 above. 12 mm thick glass with polished edges to be provided on table top.	2	No.		
13	Side Table of size 120cm : Providing and fixing side unit for Officer table to detail as per drg. of size 120cm x 45 cm as per specification in item no.10 above. 12 mm thick glass with polished edges to be provided on table top.	20	No.		
14	Side Table of size 100cm : Providing and fixing side unit for Officer table to detail as per drg. of size 100cm x 45 cm as per specification in item no.10 above. 12 mm thick glass with polished edges to be provided on table top.	7	No.		
15	Discussion table : Providing & fixing Oval shaped discussion table of size 150cm X 80cm, made of 25mm thick Plywood finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip of required width. 4 legs of Stainless steel with 40mm X 25mm section size to be provided. 45 cm flip-top to be given for cable entry of electrical / network ports.	2	No.		
16	Low Level Storage :Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm to 1200 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 25 mm Plywood for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exposed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	100	Sq.M		
17	Column / Wall Panelling : Providing and fixing columns/ wall panelling to detail as shown in the drawing with 18 mm thick plywood finished with 1 mm thick laminate.	197	Sq.M		
18	Providing and Fixing zebra roller Blinds of approved make and colour.	20	Sq.M		
19	ACP- Panelling with 3 mm thick aluminium composite panel of approved make and shade, cut and bind using router machine and curved using rol over aluminium frame work with 50 x 25 x 1 mm sections as per site condition; at front portion of Bank & ATM room, at the exterior columns, with white coloured panels and blue colour panel at 40cm height from finished floor level.Approved brand : Alstone, Alstrong or equivalent	20	Sq.m		
20	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade including scrubbing & cleaning the surface.Approved make of paint: Asian, Berger, Nerolac or equivalent	63	Sq.M		
21	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shade over a coat of putty including scrubbing & cleaning the surface.Approved make of paint: Asian, Berger, Nerolac or equivalent	73	Sq.M		
22	Enamel painting : Painting with 2 coats of synthetic enamel paint over a coat of wood primer after cleaning the surface.Approved make : Asian, Berger, Nerolaco or equalant	25	Sq.M		
	TOTAL FOR INTERIOR WORKS				
	GST Extra				