

TENDER FOR DISMANTLING WORK AND BUY BACK OF DISMANTLED MATERIALS AT STATE BANK OF INDIA, FLATS ANTYODAYA NAGAR BHOPAL (M.P.)					
PRICE BID					
S.NO	ITEM	QUANTITY	UNIT	RATE	AMOUNT
1	DISMANTLING WORK				
	Demolishing of existing 250MM Brick work in walls, parapets, plinth, Boundary walls etc, manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material at site or as per direction of Engineer - in- charge. (approximate quantity)	742.000	CUM		
2	DISMANTLING 125 MM TK BRICK WORK				
	Demolishing of existing Brick work in walls, parapets, plinth, Boundary walls etc, manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material at site or a per direction of Engineer - in- charge. (approximate quantity)	2642.00	SQM		
3	Dismantling of existing doors, door frames, windows (steel or wood) shutter including chowkhats, M.s Grill, architrave, holdfasts etc. complete and stacking within 50 metres lead or as per direction of Engineer - in-charge.				
a	DOORS (approximate quantity)	288.00	each		
b.	WINDOWS (approximate quantity)	160.00	EACH		
4	Demolishing R.C.C. work manually/ by mechanical means including stacking, cutting of steel bars and disposal of unserviceable material outside the site or as per direction including loading unloading, transportation and as per direction of Engineer - in-charge. (approximate quantity)	840.00	CUM		
	<u>TOTAL COST FOR DISMANTLING WORK</u>				

S.NO	ITEM	QUANTITY	UNIT	RATE	AMOUNT
5	BUY BACK ITEMS-				
a	All type malba (including loading, unloading, transportation etc complete) (approximate quantity 1926.0 Cum)	1.00	JOB		
b.	Steel OF Column, Beam, Slab etc (including loading, unloading, Cutting transportation etc complete) (approximate quantity 75560 KGS)	1.0	JOB		
c	M.S Window Grill & OTHER Scrapped items (including loading, unloading, transportation etc complete) (approximate quantity 11442) KGS	1.00	JOB		
TOTAL BUY BACK AMOUNT					
<p>** Note: The Quantites shown in the above BOQ is Approximate Quantites (to give an assesement of quantum of work involved) and accordingly the Rates may be quoted, Contractor has to quote the overall work after visiting the site and no deviation afterwards will be allowed</p>					
ABSTRACT SHEET					
S.NO	ITEMS				AMOUNT
1	Buy Back Amount of Dismantled Materials (A)				
2	Less cost of dismantling works			(-)	
TOTAL BALANCE AMOUNT TO BE REIMBURSED TO BANK (AFTER DEDUCTION OF BUY BACK)					
Add 18% GST					
Total Reimbursement amount including GST					
Reimbursement amount in words including					
<p>Note: Total estimated cost is approx 20.00 Lacs after deducting of buy back value excluding GST</p>					
Signature of the Contractor					