

**BOQ FOR INTERIOR AND FURNISHING WORKS OF LCPC AT FIFTH FLOOR OF ADMINISTRATIVE OFFICE BUILDING JABALPUR**

S No	Item Description	UoM	Qty	Rate	Amount
1	Providing and fixing gypsum false ceiling. in 12.5mm thick Gypboard (POP) plain false ceiling with corner POP molding & GI suspended from RCC slab/ Beam as approved by Bank/ Architect including G.I. Parameter Channels of size 0.55 mm thick having one flange of 20mm and another flange of 30mm and web of 27mm along with parameter of ceiling,screw fixed, to the brick wall / partition with the help of nylon sleeves and screws at 600mm C/C. The suspended G.I. Intermediate channels of size 45 x 0.9 mm thick with two flanges of 15mm each from the soffit at 1200mm C/C with GI cleats and steel expansion fasteners.	SqM	164.00		
2	Providing and fixing of false ceiling at all heights of 600mmx600mmx12mm Armstrong mineral fiber ceiling tiles of type IBIZA RH-90 laid on Armstrong prelude XL exposed grid systems with 9mm wide T Section flanges colour white. The frame work comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit approved hangers at 1200mm maximum centers. Hangers (GI wire) to be fixed by approved roof plug and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. flush fitting 1200mm along cross tees (with double stitching) to be interlocked between main runners at 600mm c/ c to form 1200x600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mmx600mm modules to be formed by fittings 600mm long flush fitting cross tees centrally between the 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to walls at 450mm maximum centers.	SqM	332.00		
3	Providing and fixing low height double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways including sand wiced with 8.0mm HDF Board / MR plywood from both the sides & finished with 1.0mm thick approved shades of laminate.	SqM	29.00		
4	Providing and fixing full height double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways including sand wiced with 8.0mm HDF Board / MR plywood from both the sides & finished with 1.0mm thick approved shades of laminate.	SqM	26.00		

5	Providing and fixing single shutter flush doors of approx size 2.10 m x 0.75 - 0.9 m as instructed, hinged type door openable one side as instructed, made up of superior quality waterproof flush door partially glazed (cost of glass included). The door shall be flush door of approx. 32-38 mm thickness, both sides 1 mm thk laminate as per design. Cost shall be inclusive of beadings, all accessories like SS hinges, medium quality mortise handles/locks, baby latches, stopper, etc. Fittings shall be in SS finish as per approval, the cost shall include p/f of door closers of reputed brand as per approval with all doors.	SqM	6.00		
6	Providing, supplying and laying of approved make and brand (ISI make) scratch proof, flexible and homogeneous PVC flooring of 1.5 mm thickness conforming to IS 3462-1982 in required finish, fixed with synthetic acrylic adhesive after preapring the floor, levelling and smoothening as directed.	SqM	500.00		
7	Providing and supplying Officer's table of size of 2100 x 900 x 750 mm height, with edges been double thick having one side drawer Unit, 350 mm wide (clear internal size) one M S powder coated keyboard tray with mouse tray (measured separately) as manufactured by ebco ( KBTM 45) or EGL (KBT-M-001) including sliding channel as directed.	Nos	1.00		
8	Providing and supplying Officer's table of size of 1500 x 750 x 750 mm height, with edges been double thick having one side drawer Unit, 350 mm wide (clear internal size) one M S powder coated keyboard tray with mouse tray (measured separately) as manufactured by ebco ( KBTM 45) or EGL (KBT-M-001) including sliding channel as directed.	Nos	12.00		
9	Providing, making and placing in position low height storage cabinets as storage & or runners from 350mm to 500 mm depth, height of 750 to 900 and length as per site requirement, and in 18 mm MR grade plywood construction with 6mm thk. MR grade plywood backing complete.	SqM	13.50		
10	Modification to existing full height partitions by fixing 4 mm thick MDF board finished with 1 mm thick laminated of approved shade to match the pattern as directed.	SqM	24.00		
11	Repair to existing drawer unit of length 450mm, width 350mm and height 750 mm including replacement of heavy duty telescopic drawer slides (EBCO make) and multidrawer Godrej or Ebco single lock along with brass handle for each unit as directed.	Nos	25.00		
12	Providing and fixing drawer unit of length 450mm, width 350mm and height 750 mm made of exterior grade of 18 mm thick MR commercial ply wood for the front and rear 12 mm MR Plywood for sides and 6mm thick MR ply for the bottom sliding finished with 1 mm thick laminate including provision of heavy duty telescopic drawer slides (EBCO make) and multidrawer Godrej or Ebco single lock along with brass handle for each unit as directed.	Nos	5.00		
13	Providing and fixing 12 mm thick clear float glass partition of size 1600X450-600 mm high fixed in 'D' bracked with SS fittings as directed.	Nos	5.00		
14	Fixing 12 mm thick clear float glass partition of size 1600X450-600 mm high fixed in 'D' bracked with SS fittings as directed.	Nos	10.00		

15	Repairs to existing tables including cutting and positioning, replacement of lamination, ply wood and finished in complete as directed.	Nos	5.00		
16	Repairs to existing partitions including replacement of channel section and refixing of plyboard finished with 1 mm thick laminated of approved shade to match the pattern as directed.	Sqft	150.00		
17	Providing & applying two or more coats of plastic emulsion paint on walls, ceiling, etc. over the coats of putty and primer including removing, scrapping & cleaning the existing color wash/ distemper/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing .	SqM	550.00		
18	Mexhanized cleaning of existing flooring using rotary floor machine and abrasive pads using non-acidic, pH-neutralk cleaners cleaning agents to prevent damage or discolouration. Mirror polishing to the satisfation of Bank.	1000	1000.00		
<b>Amount (in Rs.) excluding GST</b>					