

S.No	Description	Total Qty	Unit	Rate	Amount
1.00	<p>Please Note : Below mentioned items shall be applicable to all item specifications</p> <p>A) The quoted rate should include cost of necessary scaffolding, staging, centring, shuttering etc. as required for execution of the job at any height and location including removal of same. The scaffolding should be erected and anchored into the concrete members with help of expandable bolts, which are to be cut as the scaffolding is removed, no wall is to be punctured, at no extra cost to the Bank.</p> <p>B) Contractor has to make arrangements at his own cost to tie a safety net around the work so that loose plaster/ concrete does not cause damage to the property or any human being, if necessary.</p> <p>C) Contractor shall arrange for temporary shifting of the existing counters to desired orientation/position/place within the Bank premises for smooth Banking operations.</p> <p>D) Necessary temporary partitions as per the site requirement shall be erected at contractors cost to segregate the Banking operations area and work area.</p> <p>E) Contractors shall arrange to clear the debris from the site and shift to local governing body approved dumping grounds at no extra cost to the Bank.</p> <p>FULL HEIGHT PARTITIONS - PARTLY GLAZED</p> <p>(i) Framing- Made out of 50mm x 50mm, 2 mm thick hollow aluminum square sections at spacing not exceeding 600 mm both-ways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling.</p> <p>(ii) 11 mm thick EG MDF fixed on both sides with 25mm dry wall screws for the entire height of the partition.</p> <p>(iii) From 1070 mm level to 2135 mm level to have 8mm clear float glass fixed with 85mm x 15mm around jamb and 12mm x 12mm button beading on both sides of the glass, to a neat finish as per drawings and directions etc., complete. The glass sizes subject to design drawing etc.</p> <p>(iv) Finishing- with 1.00mm thick laminate of approved quality and shade to be finished as per design & pattern shown in Architectural drawing or as directed by the Engineer.</p> <p>The rate shall include all necessary hardware, making necessary cutouts for electrical conduits / cables & switchboards, AC ducts etc., including necessary support for doors as per drawings/ directed by Engineer..</p> <p>All beech wood members to have minimum two coats of LOW VOC or NO VOC white duco paint finish.</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or approved equivalent</p> <p>(b) EG MDF- Greenply, Century,VIR or approved equivalent.</p> <p>(c) Laminte- Greenlam/ Aica/ Archidiam or equivalent</p> <p>(d) Glass: Saint Gobain, Asahi Float, Modi Guard.B50</p> <p>Mode of measurement:- Though aluminum frame shall extend up to RCC slab bottom level above false ceiling, partition area below false ceiling shall be measured.</p>	59.80	Sq.M.		-
2.00	<p>FULL HEIGHT PARTITIONS - SOLID</p> <p>Providing & fixing full height solid wooden partition finished with both sides laminate:-</p> <p>(i) Framing- Made out of 50mm x 50mm, 2 mm thick hollow aluminum square sections at spacing not exceeding 600 mm both-ways (horizontal and vertical) fixed rigidly on floor, wall / column & ceiling.</p> <p>(ii) Skin:- Providing & fixing 11 mm thick EG MDF on both sides of the framework.</p> <p>(iii) Finishing:- with 1.00mm thick laminate of approved quality and shade to be finished as per design & pattern shown in Architectural drawing or as directed by the Engineer.</p> <p>The rate shall include all necessary hardware, making necessary cutouts for electrical conduits / cables & switchboards, AC ducts etc., including necessary support for doors as per drawings/ directed by Engineer..</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or approved equivalent</p> <p>(b) EG MDF- Greenply, Century,VIR or approved equivalent.</p> <p>(c) Laminte- Greenlam/ Aica/ Archidiam or equivalent</p> <p>Mode of measurement:- Though aluminum frame shall extend up to RCC slab bottom level above false ceiling, partition area below false ceiling shall be measured.</p>	40.10	Sq.M.		-
3.00	<p>LOW HEIGHT PARTITIONS</p> <p>Providing & fixing low height wooden partition finished with both sides laminate and glass:- Height of the partition will be max 1,500 mm (Solid portion of 900mm height and top portion with 10mm toughened glass of 600mm height).</p> <p>(i) Framing- Made out of 50mm x 50mm, 2 mm thick hollow aluminum square sections at spacing not exceeding 600 mm both-ways (horizontal and vertical) fixed rigidly on floor, wall / column. The end vertical frames shall be extended up to 1,500mm.</p> <p>(ii) Skin- Providing & fixing 11mm thick EG MDF on both sides of the framework, on both sides of the framework and around vertical posts extended upto 1500 mm height.</p> <p>(iii) Finishing:- With 1.00mm thick laminates of approved quality and shade to be finished over EG MDF as per design & pattern shown in Architectural drawing or as directed by the Engineer.</p> <p>(iv) Provision for Glazing:- Provision for fixing 12 mm thick toughened glass with polished edges as partitions and fixing the same with 'SS Satin Finish' 'D- clamps' horizontally & vertically the edges should be smooth complete. (Glass will be measured separately)</p> <p>(v) 6mm thick beechwood molding to be provided on top and side edges of partition. complete with Duco paint including proper base & primer etc.</p> <p>The rate shall include all necessary hardware, making necessary cutouts for electrical conduits / cables & switchboards, AC ducts etc., including necessary support for doors as per drawings/ directed by Engineer.</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or approved equivalent</p> <p>(b) EG MDF- Greenply, Century,VIR or approved equivalent.</p> <p>(c) Laminte- Greenlam/ Aica/ Merino or equivalent</p> <p>(d) Glass: Saint Gobain, Asahi Float, Modi Guard.</p>	37.00	Sq.M.		-
4.00	<p>Same as above but 1200 mm ht. Partitions including 300 mm glass top etc., complete as directed. (Glass will be measured separately)</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or approved equivalent</p> <p>(b) EG MDF- Greenply, Century,VIR or approved equivalent.</p> <p>(c) Laminte- Greenlam/ Aica/ Merino or equivalent</p> <p>(d) Glass: Saint Gobain, Asahi Float, Modi Guard.</p>	3.50	Sq.M.		-
5.00	<p>32MM DOORS IN PARTITIONS - with glass panel:</p> <p>Flush Door with Laminate finish:- Providing & fixing 32 mm Flush doors with 1.0mm laminate on both sides as per design.</p> <p>Door frame:- Providing and fixing door frames using beechwood members of size 85 mm x 35mm and finished with duco paint.</p> <p>Shutter:- Providing and fixing block board shutters of 32mm thick, with view panel of 160cmx30cm. View panel to have 8mm thick clear float glass and 1.9x1.9cm beechwood beading on both sides and glass pasted with 3M privacy film as per design.</p> <p>Skin:- The shutters shall be finished with 1mm thick laminate of approved quality and make.</p> <p>The Doors to have all hardware such as 125mm SS hinges, 450 m long SS handles, SS tower bolts, Mortice Locks (Dorma/ Godrej/Ozone or approved equivalent), door stopper, door closure (Dorma/godrej/Ozone or approved equivalent). Exposed edges of shutter shall be provided with beechwood beading of 32mm width and finished with 2 coats duco paint.</p>	7.90	Sq.M.		-
6.00	<p>32MM DOORS IN PARTITIONS : solid</p> <p>Flush Door with Laminate finish:- Providing & fixing 32 mm Flush doors with 1.0mm laminate on both sides as per design.</p> <p>Door frame:- Providing and fixing door frames using beechwood members of size 85mm x 35mm and finished with duco paint.</p> <p>Shutter:- Providing and fixing block board shutters of 32mm thick.</p> <p>Skin:- The shutters shall be finished with 1mm thick laminate of approved quality and make.</p> <p>The Doors to have all hardware such as 125mm SS hinges, 450 m long SS handles, SS tower bolts, Mortice Locks (Dorma/ Godrej/ Ozone or approved equivalent), door stopper, door closure (Dorma/godrej/Ozone or approved equivalent). Exposed edges of shutter shall be provided with beechwood beading of 32mm width and finished with 2 coats duco paint.</p>	9.10	Sq.M.		-
7.00	<p>Fire Door for UPS Room 900mm-1200mm x 2100mm</p> <p>Providing and fixing in position 120 minutes fire rated 46mm thick Galvanized steel single leaf doors with door frame for opening of size 1000mm x 2100mm with vision panel having test certificate (covering glass and fittings) of reputed makes. The rate to include labour, conveyance, necessary hardware viz., pair of SS 304 D handles, lock and key, SS 2 ball-bearing hinges - (127mm x 76mm x 2.5mm), concealed door closer (all of approved make and quality) SS 304 kick plate etc. complete as directed.</p>	4.00	Sq.M.		-
8.00	<p>WICKET GATE - for SWO Counters</p> <p>Providing wicket gate made of 32mm solid flush door with around beechwood beading of 32mm width and finished with 2 coats duco paint and height to match low height partitions. Wicket gate shall be finished with 1.0mm laminate sheet on both faces and shall fixed to partition with 85mm x 35mm beech wood frame on sides with SS hinges as required with handles, stoppers, self lock (Godrej Kinght gate) etc complete. Wicket gate shall have self lock from inside fixed at lower height as per instructions and Bank requirement.</p> <p>Wicket gate specified below may also be used with other low height partitions elsewhere in the branch if required, with height of wicket gate modified suitably.</p>	11.70	Sq.M.		-
9.00	<p>FIXED GLASS WORKS FOR PARTITIONS : (12MM TOUGHENED GLASS)</p> <p>Providing, making and fixing in position Fixed 12mm toughened glass as fixed glass from Skirting/ Floor level upto available Ceiling / beam / lintel level and inline with wooden partitions / doors etc as per layout plan. The glass is to be fixed onto the ply base with patch fittings and all the edges of the glass to be machine polished for a smooth finish. The work includes cost of all materials, approved hardware, making necessary template before toughening of glass and fixing the same as per site conditions to a neat finished work as per drawings and directions including silicon sealant between glass panels etc., complete.</p> <p>Approved make:-</p> <p>(a) Hardware: Ozone, Dorma, Godrej or approved equivalent</p> <p>(b) Glass: Saint Gobain, Asahi Float, Modi Guard.B50</p>	17.40	Sq.M.		-
10.00	<p>12MM TOUGHENED GLASS MAIN ENTRANCE DOOR AND PARTITION DOORS:</p> <p>Providing, making and fixing in position Fixed 12mm toughened glass openable shutters work as per specifications given below and for the openings mentioned. Main Entrance Glass Work comprising of Door opening of approximate size 1830mm x 2135mm ; 2490mm in two leaves, and Partition Doors of approximate size 900 : 1065mm x 2135mm ; 2490mm. The entire work to be done as per site conditions with following specifications etc., complete as directed.</p> <p>Providing and fixing frameless fully glazed 12mm thick toughened glass door fixed with necessary patch fittings (Dorma/ Godrej/Ozone or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items (Top Pivot, Top Patch Fittings, Bottom Patch fittings, Floor Spring, Corner lock with strike plate and Euro Profile Cylinder, Handle - 600mm length). Measurement will be taken only upto solid partition level.</p> <p>Approved make:-</p> <p>(a) Hardware: Ozone, Dorma, Godrej or approved equivalent</p> <p>(b) Glass: Saint Gobain, Asahi Float, Modi Guard.B50</p>	7.90	Sq.M.		-
11.00	<p>PANELING IN WALLS & COLUMN BANKING HALL</p> <p>Providing and fixing in position wooden paneling to column / walls with laminate finish:-</p> <p>(i) Framework:- made of Aluminum frame 50 mm x 25mm, 2mm thick hollow aluminum square sections at spacing not exceeding 600 mm both-ways (horizontal and vertical) fixed rigidly on wall / column</p> <p>(ii) Plywood skin:- Providing & fixing 11 mm thick EG MDF on both sides of the framework.</p> <p>(iii) Finishing:- with 1.00mm thick laminate of approved quality and shade to be finished as per design & pattern shown in Architectural drawing or as directed by the Engineer.</p> <p>The rate shall include all necessary hardware, making necessary cutouts for electrical conduits / cables & switchboards, AC ducts etc., including necessary support for doors as per drawings/ directed by Engineer..</p> <p>Approved make:-</p> <p>(a) Aluminum extruded sections: Jindal, Hindalco or approved equivalent</p> <p>(b) EG MDF- Greenply, Century,VIR or approved equivalent.</p> <p>(c) Laminte- Greenlam/ Aica/ Archidiam or equivalent</p> <p>Mode of measurement:- Though aluminum frame shall extend up to RCC slab bottom level above false ceiling, partition area below false ceiling shall be measured.</p>	55.00	Sq.M.		-
12.00	<p>WALL PAPER PANELING ON WALLS/ COLUMNS</p> <p>Providing and fixing gypsum board paneling to column / wall partitions:- made of Aluminum frame 50 mm x 25mm x 2mm at 600mm centre to centre both-ways (Horizontal and vertical) with necessary packing of gypsum board to achieve the size of column/ wall including fixing of 12mm gypsum board on Aluminum frame using fully threaded screws of 25mm on frame. Providing and fixing wall paper of approved shade and design fixed with adhesive (Fevicol SR or approved equivalent) over the gypsum board as per the company's specifications.</p> <p>(Basic rate of wall paper:970/-per sqm)</p> <p>Make:- Marshalls / Ddecor / Marie / Claire / Nilava -Asian Paints or approved equivalent make</p>	0.00	Sq.M.		-

Sl.No	Description	Total Qty	Unit	Rate	Amount
13.00	<p>PLAIN GYPSUM FALSE CEILING @ HEIGHTS UPTO 2.75 Mts LEVELS</p> <p>Providing and fixing Concealed Grid suspended ceiling system of 12.5mm Gypsum Boards / Standard Plaster Boards fixed to ceiling Frame Work as per manufacturers instructions and details for a concealed grid key lock suspended ceiling system consisting of following:</p> <p>27 x 37 x 1.6mm Soffit Clip, 5mm suspension rod / 25 x 10 x 0.5mm Ceiling Angle, adjustable spring loaded suspension clip / 2.64mm dia Connecting Clip, 20 x 28 x 30 x 0.5mm Perimeter Channel, Top Cross Rail of 3000mm long of 0.55BMT Furring Channel / 15 x 45 x 15 x 0.9mm Intermediate Channel and 4000mm long made of 0.5mm BMT the Top Cross Rail / 80 x 26 x 0.5mm Ceiling Section to be suspended from ceiling at every 1200mm and Furring / Intermediate Channel to be fixed to Top Cross Rail / Ceiling Section at every 600mm to make a grid of 1200 x 600mm.</p> <p>All sections used should adhere to the manufacturers guidelines and the contractor has to submit certificate from the manufacturer on usage of their specified sections.</p> <p>Further the rates to include vertical faces upto 150mm as per drawings at exposed edges, cutouts for lighting fixtures / AC grilles / Fire Alarm Detectors etc., along with necessary strengthening and supports for fixing of these. The board joints are to be flush finished with jointing compound and paper tape etc., complete as directed.</p> <p>The ceiling shall be finished with 2 coats of premium emulsion paint over primer putty etc complete</p>	83.00	Sq.M.		-
14.00	<p>GRID FALSE CEILING : MINERAL FIBER TILE @ HEIGHTS UPTO 2.75 Mts LEVELS</p> <p>Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance >87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 & 7) in module size of 600 x 600 x 16mm, suitable for Green Building application, with Recycled content of 30% - 45%</p> <p>The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.</p> <p>The Installation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.</p> <p>Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.</p>	192.00	Sq.M.		-

Sl.No	Description	Total Qty	Unit	Rate	Amount
15.00	<p>LOW HEIGHT STORAGE UNITS 750 - 1200 mm ht.</p> <p>Low Height Cupboard with Laminate Finish: Providing & fixing Low Height Storage Cupboard of 750-1200 mm height and 450mm deep.</p> <p>Top to be made with 25mm thick Block Board shelves to be made 19mm thick Block board, Outer exposed structure to be made with 18mm EG MDF and back side using 8mm EG MDF.</p> <p>All shutters to be made with 18 mm thk. EG MDF.</p> <p>All internal surfaces to be finished with 0.8mm laminate and external surfaces to be finished with 1mm laminate of approved shade and make.</p> <p>All edges of the cupboard should be edgebanded using PVC edgebanding tape of approved shade.</p> <p>Shutters to be provided with S.S. 200mm handles, magnetic catchers, self closing SS hinges, locks (Godrej/ Hettich/Hafele), SS towerbolts etc. All shutters to be made overlapping the frame</p> <p>Only front elevation will be considered for area calculation.</p> <p>Make: EG MDF/ Block board:- Greenply, Century,VIR or approved equivalent.</p> <p>Laminate:- Greenlam, Century or equivalent.</p>	28.00	Sq.M.		-
16.00	<p>FULL HEIGHT STORAGE UNITS 2100 mm ht</p> <p>Full Height Cupboard with Laminate Finish: Providing & fixing Full Height Storage Cupboard of 2100mm height and 450mm deep</p> <p>Outer exposed structure with to be made with 18mm EG MDF and back side using 8mm EG MDF</p> <p>All shutters and shelves to be made with 19 mm thk. block board</p> <p>All internal surfaces to have 0.8mm thk laminate and external surfaces to be finished with 1mm laminate of approved shade and make.</p> <p>All edges of the cupboard should be edgebanded using PVC edgebanding tape of approved shade.</p> <p>Shutters to be provided with S.S. 200mm handles, magnetic catchers, self closing SS hinges, locks (Godrej/ Hettich/Hafele), SS towerbolts etc. All shutters to be made overlapping the frame</p> <p>Only front elevation will be considered for area calculation.</p> <p>Make: EG MDF/ Block board:- Greenply, Century,VIR or approved equivalent.</p> <p>Laminate:- Greenlam, Century or equivalent</p> <p>(Only front elevation will be considered for area calculation)</p>	21.00	Sq.M		-
17.00	<p>CHIEF MANAGER TABLE:</p> <p>Chief Manager tables size 2130mm x 900mm x 760mm and Side Table 1200 mm x 450 mm x 750mm</p> <p>Providing, making and placing in position CHIEF MANAGER Table and Side Table with following specifications.</p> <p>Main Table and side Table top to be made in 25mm block board and side supports to be made 18mm BWR Ply as per IS 303 with 1mm Thk. Laminate, top to shape 1 1/2" hole cut for wire manager, cables etc. The front side of the table to have a inverted " C " made with 2 x 18mm thick EG MDF finished with 1mm Thk. Laminate on the front and the verticals. The modesty panel to have 18mm EG MDF with 6mm thk toughened lacquered glass in blue colour as specified.</p> <p>The " L " shaped table top on the back side to have 50mm edge around finished with 1mm Thk laminate.</p> <p>All other members to be with 18mm EG MDF and all exposed faces of the table to have 1mm Thk. Laminate as specified.</p> <p>All the exposed edges of 18mm EG MDF to have PVC edge banding.</p> <p>One readymade CPU mobile pedestal.</p> <p>One Molded Key Board Tray (550 x 375 mm) with channels etc.,</p> <p>One Three Drawer Unit of 400mm wide made with 18mm EG MDF and 12mm EG MDF. The unit to have 3nos equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and edges finished with PVC edge banding.</p> <p>Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1no internal shelf made with 18mm EG MDF all laminated and with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc., and PVC edge banding / 20mm x 6mm beech wood edge lipping etc.</p> <p>All the unexposed faces to have 0.8mm Laminate and exposed faces to have 1.00 mm Laminate</p> <p>Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.</p>	1.00	Each.		-

Sl.No	Description	Total Qty	Unit	Rate	Amount
18.00	<p>Officer Tables</p> <p>Supplying and installation of Table as per the following description : Table top shall be made from 25 mm thick Block Board with 1mm thick with necessary intermediate support. Table top shall be supported by 18 mm thick EG MDF. The top of the table shall be provided with equal sized 8 mm thick float glass with necessary cutting for wire manager. Apron (Modesty Panel) made from 18 mm thick EG MDF with 1mm laminate & groove pattern as per drawing. Table sides & intermediate panels (at 50cm from each sides) made from 18 mm thk EG MDF finished with 1mm thick laminate for all surfaces shall be provided as per drawing.</p> <p>One Three Drawer Unit of 400mm wide made with 18mm EG MDF and 11mm EG MDF. The unit to have 3nos equal drawers. The rate to include all necessary hardware viz., telescopic drawer channels, handles, locks, etc., and edges finished with PVC edge banding.</p> <p>Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1no internal shelf made with 18mm EG MDF and 18mm EG MDF all laminated and with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts,telescopic channels etc., and PVC edge banding etc.</p> <p>Side Table having one pedestal unit with 450mm wide having one drawer & one shutter with 1no internal shelf made with 18mm EG MDF and 18mm EG MDF all laminated and with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts,telescopic channels etc., and PVC edge banding etc.</p> <p>All edges to be provided & fixed with PVC Edge banding of approved shade.</p> <p>All the unexposed faces to have 0.8mm Laminate and exposed faces to have 1.00 mm Laminate</p> <p>Each table to have 1 no. CPU metal mobile stand, 1 no. metal Key board tray (550 x 375 mm) with mouse pad extensions,modular footrest, wire manager of make ebco/ Godrej or approved equivalent.</p> <p>As per drawing and instruction of Architect/Bank work to be Completed</p> <p>Table size. : 1530 mm x 770 mm x 760 mm & Side Table 910 mm x 450 mm x 760 mm</p>	7.00	Each.		-
19.00	<p>SINGLE WINDOW COUNTERS:</p> <p>Counter : 1530mm x 900mm x 760mm</p> <p>Side Runner : 1070 mm x 450mm x 760mm.</p> <p>Providing, making and placing in position Single Window Counters along with necessary Half height partitions above (The partitions will be measured and paid as per Half Height Partitions) with following specifications and as per dimensions specified.</p> <p>Table top of main table and side table to be made in 25 mm thick Block board with 1mm thick laminate surface. 8mm glass top to shape 1 1/2" hole cut for wire manager, cables etc.. 1 mm Laminate surface to continue in the front side with curvature from the front table top to the modesty panel in front with cove lighting provision.(Glass for main table only)</p> <p>All other members to be with 18 mm thick EG MDF, 2 Nos. of 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and all exposed faces of the table to have 1mm thick Laminate as specified in the drawing to be used.</p> <p>Front of SWC Counter to have about 100mm high skirting made of 18 mm thick EG MDF fixed at floor level and finished with 1.0mm laminate of dark blue colour.</p> <p>All the edges of 18 mm thick EG MDF to have PVC edge banding.</p> <p>One readymade CPU mobile pedestal.</p> <p>One Molded Key Board Tray with channels etc.,</p> <p>One Three Drawer Unit made with 18 mm thick and 11 mm thick EG MDF. The unit to have 3nos equal drawer and each drawer shall be fixed with auto self locks. Drawers shall have Cash Denomination Partitions made of 12mm ply laminated. The rate to include all necessary hardware viz., telescopic drawer channels, handles, hinges, etc., and PVC edge banding etc.,</p> <p>One Side Table with shutters made with 18 mm thick EG MDF with necessary hardware viz., ' W ' hinges, SS handles, locks, SS tower bolts, etc., and 20mm x 6mm beech wood /PVC edge banding etc and finished with 1.0mm laminate.</p> <p>All the unexposed faces to have 0.8mm Laminate and exposed faces to have 1.00 mm Laminate.</p> <p>Ready Made Modular Foot Rest - 400mm x 350mm x 65mm.</p> <p>All wooden members to have minimum two coats of NO VOC or LOW VOC white duco paint finish.</p> <p>Each Single Window Counter to have half height partitions on either sides as per item 1.20 above.(which will be measured as per respective item)</p> <p>Each Single Window Counter to have provision for 12mm thick toughned glass in the front and sides as per relevant item measured separately.</p> <p>The cost to include the " L " shaped Single Window Counter and to include all materials, hardware, labour for a neat and finish job as per drawings and directions etc., complete.</p> <p>NOTE</p> <p>Brief list of make are as under or any equivalent make will be permitted by the Engineer</p> <p>Block board/ EG MDF - Make: EG MDF/ Block board- Greenply, Century,VIR or approved equivalent.</p>	8.00	Each.		-
20.00	<p>LINEAR TABLE / WORKSTATION LAMINATE FINISH (CURVED SHAPE)</p> <p>Providing and fixing Linear Table having width of 610 mm using 25 mm thick Block board for table top and 18mm thk EG MDF vertical supports at 1200 mm c/c.</p> <p>Drawer / Storage cabinet of 350 X 630 X 720 mm shall be provided using 18 mm thick EG MDF. Each Drawer Fascia made out of 18 mm thick EG MDF and all sides of drawers be made of 11 mm thick EG MDF & bottom of drawers shall be of 8 mm thick EG MDF. The drawer unit box and individual drawers to be fixed with 1mm laminate on exposed sides and all the internal surfaces shall be 0.80 mm thick laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer.</p> <p>1.0 mm thick Laminate finish on table Top and bottom. 2 mm PVC edge banding on exposed edges.</p> <p>Providing Modular Foot rest, keyboard tray and metallic CPU stand.</p> <p>Brief list of make are as under or any equivalent make</p> <p>Block board/ EG MDF - Make: EG MDF/ Block board- Greenply, Century,VIR or approved equivalent.</p> <p>Laminte- Greenlam/ Aica/ Archidiam or equivalent</p> <p>Multipurpose group Lock - Ebco / EG / Godrej or approved equivalent.</p> <p>Telescopic channels - Ebco / Everite /Ozone or approved equivalent.</p> <p>Keyboard tray - Ebco / Hettich / Innofit/ Featherlite or approved equivalent.</p> <p>Cable Manager (60mm) - Metal- Ebco or equivalent or approved equivalent.</p> <p>Adhesive- Fevicol / Pedlite / Araldite / Royal Bond or approved equivalent.</p>	3.69	Rmt		-

Sl.No	Description	Total Qty	Unit	Rate	Amount
21.00	<p>12MM TOUGHENED GLASS DIVIDERS FOR SINGLE WINDOW COUNTERS (Tapered Shape) Providing, making and fixing in position 12mm thick toughened clear float glass dividers in the front side of half height partitions of Single Window Counters of approximate size 1650mm x 500mm - 100mm in tapered shape. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets from above skirting level. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete. Brief list of make are as under or any equivalent make will be permitted by the Engineer Glass- Asaahi/ Tata / Modi guard / Saint gobain Square / D bracket S.S finish of required size - Oswal / Riddhi / Swift or equivalent approved make.</p>	6.00	Each.		-
22.00	<p>12MM TOUGHENED GLASS FOR FRONT PORTION OF SINGLE WINDOW COUNTERS (TRANSACTION SIDE): Providing, making and fixing in position 12mm thick clear float glass in the front side and shall be in 2 nos of separate sizes. Lower part shall be fixed with a glass panel of size 1530 x 380mm with a central cut out of 200mm x 150mm. Upper part shall be fixed with a glass panel of size 1530 x 450mm. A gap of 50mm shall be maintained between the two glass panels. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " / " L " brackets as required. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete. Brief list of make are as under or any equivalent make will be permitted by the Engineer Glass- Asaahi/ Tata / Modi guard / Saint gobain Square bracket (50 mm x 12.5 mm) S S finish - Oswal / Riddhi / Swift or equivalent</p>	8.00	Each.		-
23.00	<p>12MM TOUGHENED GLASS ON LOW HEIGHT PARTITIONS BETWEEN SINGLE WINDOW COUNTERS & VOUCHER TRAY: Providing, making and fixing in position 12mm thick toughened clear float glass in sizes as per design with cut out of 200mm x 150mm at position to match Voucher tray. All the edges of the glass to be polished for a smooth finish and the glass is to be fixed with " D " brackets. The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete. Glass size shall be as per length of low height partition after leaving about 300mm solid portion at both ends. Item includes providing Voucher tray of size 200 x 200, made of 19mm BB-laminated with PVC edge banding etc and fixed onto the low partition with all hardware etc complete. Brief list of make are as under or any equivalent make will be permitted by the Engineer. Glass- Asaahi/ Tata / Modi guard / Saint gobain Square bracket (50 mm x 12.5 mm) S S finish - Oswal / Riddhi / Swift or equivalent</p>	9.00	Sq.M.		-
24.00	<p>WALL MOUNTED WRITING DESK: Writing Desk Size 900 mm (3'-0") L x 380 mm (1'-3") depth x (900 mm + 150 mm) (3' + 6") ht. Vertical Sides and bottom shall be made out of 36mm (2X18) thick EG MDF and back side 12 mm EG MDF with 1 mm Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12 mm thick toughened glass with polished edges, making different divisions by 12 mm thick glass and edges with 18 mm thick EG MDF with laminate on both side for slips or forms as per detail drawing and instruction complete. Laminate to be provided on all visible surface. Brief list of make are as under or any equivalent make will be permitted Make: EG MDF/Block board:- Greenply, Century,VIR or approved equivalent. Laminte:- Greenlam/ Aica/ Archidlam or equivalent Glass- Asaahi/ Tata / Modi guard / Saint gobain Adhesive- Fevicol / Pedlite / Araldite / Royal Bond</p>	1.00	Nos / each		-

Sl.No	Description	Total Qty	Unit	Rate	Amount
25.00	FLOOR MOUNTED WRITING DESK: A Octagonal support boxing is to be made 450mm at floor level tapering upwards to 600mm at 900mm from floor made in 11mm EG MDF Ply clad with 1mm Laminate. A top to be provided at 900mm level from floor to be made with 25 mm Block Board clad with 1mm Laminate which will have verticals made with 11mm EG MDF clad with 1mm Laminate upto the table top level of 1050mm from floor level. Providing, making and placing in position Wall Mounted Circular Writing Desk 900mm dia x 1050 mm with following specifications. The Writing Desk Circular Top to have 12mm thk toughened glass with 25mm chamfered bull nosing around. All exposed faces to have 1mm thk Laminate as specified. All the edges of 11mm / 18mm EG MDF to have PVC edge banding. All visible surfaces to be finished with 1.0mm thk laminate sheet and all internal and underside surfaces to be fixed with 0.8mm thick lamination sheet. The cost to include all materials, labour etc., for a finished item of work as per drawings and directions etc., complete.	1.00	Nos / each		-
26.00	COMPLAINT BOX Providing, supplying & fixing of Complaint box fixed to the wall / partition of size 375mm x 270mm x 450mm made out of 18mm EG MDF for the box, external finished with 1mm th. laminate of approved shade and colour, prior confirmation shall be taken from the architect / bank and before making of box internal surfaces providing all internal surfaces to be finished with 0.8mm laminate of approved color & design before making box including door shutter, necessary opening and all fixtures and fastenings, adhesives, nails screws etc., complete.	1.00	Nos / each		-
27.00	ROLLER BLINDS Supplying and fixing Roller Blinds of approved make with selected fabric of approved design and shade having powder coated rod and adjustable string, etc. complete. (Basic Price of Rs 80 Per Sq.Mtr excluding GST) Roller Blind- Vista wall fashion / Mac or equivalent	53.00	Sq.M.		-
28.00	Providing and fixing in position Designer Film on all glasses as per approved drawings. The Designer Film is of Harmony / 3M or equivalent approved make. The rate is for a finished item of work etc., complete as directed.	52.10	Sq.M.		-
29.00	SOFT BOARD Providing & fixing soft board for pin up using moulded Steam beach / Teak Wood frame of 25 x12.5 MM with 6 mm thick MR grade plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs.110 per Rmt. Steam beach member shall have lacquer polish as directed.)	1.20	Sqm		-
30.00	MAGNETIC WHITE BOARD Providing and fixing in position (900mmx1200mm) magnetic White Board of approved make as directed. The rate is for a finished item of work etc., complete as directed.	1.00	Nos / each		-
31.00	CENTRE TABLE - Laminate Manufacturing and supplying center tables as per the following specifications. Table top shall be made of 25mm BB finished with 1mm thk laminate and fixed with 8mm thk glass on top. Support structure with 4 nos legs of B.W 50 x 50 and horizontal ties around at top and bottom of B.W 37.5 x 37.5 All edges shall be finished with PVC edge bandings, nails, screws, adhesives etc. All wooden surfaces finished with melamine spray polish. Table top shall be provided with 8mm thk clear glass and cut to table top shape. All glass edges shall be machine polished. 0.90 x 0.60 x 0.45	1.00	No.		-
32.00	DINING TABLE (1800mm x 900mm) Providing and fixing Dining Table with Table top of 25mm thk BB of size 1.8m x 0.9m and fixed on the powder coated metal frame with screws, bolts etc and PVC edge banding / beading as required Supporting frame made of 4nos legs joined together around at top/ bottom with 50mmx50mmx2mm members for fixity. All visible surfaces to be finished with 1.0mm thk laminate sheet and all internal and underside surfaces to be fixed with 0.8mm thick lamination sheet with matching grains & edges shall be finished with PVC edge binding.	1.00	No.		-
33.00	ROUND GLASS TABLE FOR MEETING ROOM Supplying and fixing 900mm dia 12mm thk. toughened glass top table with S.S legs as approved by the Bank. Height of the table shall be 760mm.	1.00	No.		-
34.00	ENTRANCE-VINYL SCRAPER MATTING: Providing, fixing in position 3M™ Nomad™ or approved equivalent Scraper Matting 7150, Gray / Red. Entrance coiled vinyl scraper matting designed for heavy traffic applications over the existing flooring to a neat finished job as per drawings and directions etc., complete. Size - 1800 x 600.	1.00	Nos / each		-
35.00	BACK PAINTED GLASS (LACQUERED GLASS) PANELING Providing and fixing Wooden Paneling to column / wall/ partitions; made of Aluminum frame 50 mm x 25mm x 1.2mm at 600mm center to center both-ways (Horizontal and vertical) with necessary packing of wood members to achieve the size of column/ wall including fixing of 11mm EG MDF on Aluminum frame. Providing & fixing 8mm thick back painted toughened glass to be fixed with 3M adhesive on wooden paneling as per Architectural drawing/design. Make: Saint Gobain, Asahi or approved equivalent.	12.00	Sq.m		-
29.00	ACP CLADDING WORKS Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x2mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour charges, scaffolding, tools and plants etc., complete for finished item of work. if any. ACP Cladding - 3 mm thick shall be of Eurobond/ Auldecor/ Alstone/ Viva or equivalent.	11.00	Sqm		-
TOTAL INTERIOR WORKS					-