

**PRICE BID FOR THE FURNISHING WORK OF SBI HLC KANGRA
AT DISTT. KANGRA H.P.**

PART -A (INTERIOR WORKS)					
S.No.	Item of Work	Qty	Unit	Rate	Total Amount
1	Toughened Glass 12.00mm thik with etching including all as per given below	480	Sqft.		
a)	12 MM thk. toughened glass for Banking SWO Counters with Etching. front & sides. Providing and fixing 12 mm thick. clear plain toughened glass fixed in vertical position at counter level & to side partitions as per drawing. the counter top glass fixed on both sides to toughened glass partitions & side partitions fixed to wooden partition with superior quality stainless steel L-shaped clamps / glass holders 2 no. on both sides. A 6" dia semi circular hole at the bottom for transaction shall be provided. All the edges of the glass shall be grinded polished and left free. Make - Saint Gobain TATA Asahi.				
b)	Main Entrance Door ,BI Cabin Door & Meeting Room Front Side. (Toughened Glas700 to 1200x 2400 2100 mm all sides edge grinded, polished to be fixed on patch fittings, the door to be to be fitted horizontally vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accommodate fitting etc. the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant where ever required and SS cover over patch fittings to accommodate toughened glass of above items - Hardware - Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete of Ebeo, Ozono/ godrej / dorma the rate shall be include frosted film / logo all inclusive, complete in all respect. (Note: In case of false ceiling, the vertical members to be fixed below R.C.C slab but the area of Glazing payable will be below the false ceiling only).	0	0		
c)	Fixed Glass Glazing Partition - Toughened Glass 12.0 mm thk. with etching. Providing & fixing frameless fully glazed 12.0 mm thk. toughened float glass of size as per site all sides edge grinded, polished to be fixed with necessary patch fittings (godrej/dorma) the glazing to be fitted horizontally vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accommodate fittings and fixing the fixtures, screws, sealant wherever required and SS cover over patch fittings, etc. the rate shall include necessary etching film / logo all inclusive, complete.				
d)	The modesty guard to officials Tables shall be finished with 12mm thk. Toughened glass in 3/4" wide S.S. Spacer				
2(a)	Hardware & Accessories for fixing Toughened Glass doors etc. Providing and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings to accommodate toughened glass of above items Hardware Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" S S door handle (both sides) in door - pair, etc. all complete. Make Godrej Ozone Dorset Donna.	3	Job		
b)	Hardware & Accessories for fixing Toughened Glass glazing etc. Superior quality stainless steel S.S. glass holders of required size & L shaped clamps with cover / cap 2 no. on both sides to holding the front glass partition to S.W Counter & fixed glazing including required glass holes to fix the clamps complete - ISI marked.	40	No.		
c)	Wall Connecting Profile in Floor / Bottom. Providing and fixing wall connecting profile in floor to hold 12mm thk. Toughened glass including gas gasket, Rubber & hardware as per manufacturer's specifications to complete the job Material & labour etc. make: Godrej Ozone Hyper Dorset Hettich / Dorma / Intek Hardwares / Imperia Innovations Dhariwal Industries D. I. Interior Ares Interior & Safety Solutions Inc	59	Sqft.		
3	WALL PANELLING :- Providing & fixing full height laminate finish wall panelling 60mm thick made out of all tublaur frame of 50mmx25mm 18 guage section anodized aluminum of jindal / Indal Make work properly fixed to wall at 600mm c/c horizontally & vertically anchored to the wall with skin over 9mm thick BWR grade IS303 plywood/ BISON Board and to be finished with 1mm thick laminate as per colour scheme of the bank 35 12 steam beach lipping to be providing to all the edges. Complete job including melamine polish on edge beading cornices etc. And painting of grooves in approved colours all job to be done as per architect satisfaction bank direction. (Note: the area under storage or table, side credenza shall not be counted in wall panelling. only visible area will be payable).	530	Sq.ft		
	Makes -				
	Commercial Ply - Century-Sainik, Greenply-eCOTEC, Archid ply				
	Laminate - AICA, Greenlam, Merima, Century				
4(a)	FULL HEIGHT PARTIAL GLAZED PARTITIONS:- Providing and fixing full height partitions with 8mm thick clear glass fixed on TW frame of size 65mmx38mm of height varying ht. from 900mm to 2100mm The cost includes that for TW verticals at maximum 900mm c/c and horizontal at about 1050mm c The glass is to be fixed TW beeding of size 12mmx12mm all exposed work to be finished in melamine polished og approved shade and colour.	140	Sq.ft		

b)	The frame work to be cladded with 8mm thick commercial ply and 1.0mm thick laminate APPROVED make in specified pattern as per interiors details on both sides up to 3'-1/2" (3'-6" teak wood beading shall be provided on both sides of 8mm thick glass with etching work, as per pattern directed by the architect). The rate shall also include for providing and fixing in laminate & wood. The doors shall be made of 38mm thick commercial board flush door with 1.0mm thick laminate on both sides, fixed in per pattern. All the exposed edges of door shall be provided with 6mm thick hardwood lipping with polish, complete in all respects. The rate shall include necessary hardware for the doors including SS hinges, tower bolts, handle lock etc.				
c)	Note -: All ply to be sprayed with anti termite and borer spray. (ii.) Rates to include all necessary supports and as per details. (iii) Measurements to be recorded up to finished false ceiling level.				
d)	Makes -				
e)	Commercial Ply - Century-Sainik, Greenply-I:COTEC, Archid ply				
f)	Laminate - AICA, Greenlam, Merina, Century				
5(a)	FULL HEIGHT SOLID PARTITIONS:- Providing and fixing full height partitions 65 mm thick with aluminum tabular frame 50x38x1.2mm at 600mm c/c horizontally & vertically. anchored to the floor and the slab on top with skin on both sides 9mm thick BWR IS 303grade plywood BISON Board partition to have 50mm thick glass wood insulation between and to be finished with 1mm thick laminate on both sides. The cost includes all necessary hardware, edhesive, fixture and fittings all exposed edges to be finished with wooden beedings 12mm thick of width matching thickness of partition. All exposed woodwork to be finished with melamine polished. The cost also include that for fixing the laminate in pattern with wire nail grooves as per design.	570	Sq.ft		
b)	Note -: All ply to be sprayed with anti termite and borer spray. (ii.) Rates to include all necessary supports and as per details. (iii) Measurements to be recorded up to finished false ceiling level.				
c)	Makes -				
d)	Commercial Ply - Century-Sainik, Greenply-ECOTEC, Archid ply				
e)	Laminate - AICA, Greenlam, Merina, Century				
6(a)	LOW HT. PARTITION FOR COUNTER SEPARATION:- Providing and fixed low height partitions made of 44 mm X 44 mm X 16 Gauge aluminum extruded sections @ 2'-0" to 2'-0" c/c vertically & horizontally. The bottom member shall be aluminum extruded sections of size 65 mm X 44 mm X 16 Gauge. The aluminum extruded sections frame shall be fixed rigidly at floor level as well as wall with rowel plugs steel plugs 8 mm thick ply of BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) and 1 mm Thick laminate shall be fixed on both sides as per color scheme of the bank. 12mm thick glass to be provided on the Top of Partition. Teak wood beading 1 1/2" X 3 1/2" (melamine polished) around partition edges complete in all respects. height : 4'-0"	150	Sq.ft		
b)	Note -: All ply to be sprayed with anti termite and borer spray. (ii.) Rates to include all necessary supports and as per details. (iii) Measurements to be recorded up to finished false ceiling level.				
c)	Makes -				
d)	Commercial Ply - Century-Sainik, Greenply-I:COTEC, Archid ply				
e)	Laminate - AICA, Greenlam, Merina, Century				
7	Hardware				
a)	Providing and fixing of Mortice locks of approved make (Godrej /Ozone/Hettichi/ Dorma) in UPS, Record Room, etc. as per the directions of the Bank.	5	Nos		
b)	Providing and fixing hydraulic door closures Silver colour of approved make(Godrej /Ozone/Hettich/ Dorma) & color.	5	Nos		
8(a)	Manager's/ Officer Table (5'x2'6"x2'6") Officer's Tables Supplying and installation of Table as per the following description: Manager's Officer Table (5'x2'6"x2'6"): Providing and fixing of table made of 19 mm thick Commercial ply (ISI marked - GREEN (Ecotec)/ CENTURY (Sainik) with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade), with 40 mm X 6 mm thick teak wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round : 3" square cable manager for computer electrical cables at appropriate places will be made. The top surface of the table shall have 01.00 mm thick laminate. All the edges of the table, including bottom touching the floor and the drawers. The table shall have a keyboard tray of size 600 X 270 fixed on channels. A full depth CPU shelf 15" wide shall be provided at left hand side of counter underneath the working top, which will be made of 19mm thick BWP commercial ply finished with laminate 1mm thk. Three lockable drawer running on side mounted double slides (channels) & made of 12 mm thick ply with 1.0mm laminate inside with 6 mm ply bottom, handle, knob shall be provided. The sides of the drawer shall be made of 12 mm thick plywood, bottom of 6 mm thick plywood. A full length foot rest made of hard wood 3" x 1 1/2" section shall be provided at 4" above floor level. Inside of drawers & Non-Visible/ inside surfaces i.e. inside/ leg-space of table, inside of cupboard wall shall have white coloured laminate. Teak wood edges/ lipping/ beading shall be Spirit polished. The table shall include 8mm thick clear glass on top with bevelling on all 4 sides, foam sheet as required, complete in all respects.	10	Nos.		
b)	CHIEF MANAGER TABLE:(7'X3'-0"X2'-6") As per above specification	1	No.		
	Makes -				

	Commercial Ply - Century-Sainik, Greenply-cCOTEC, Archid ply			
	Laminate - AICA, Greenlam, Merina, Century			
	Telescopis Channels - Godrej, Ozone, Hettich, Hafele, Harison			
	Drawer Loks - Godrej, Ozone, Hettich, Hafele			
	Autolock : Godrej, Ozone, Hettich, Hafele			
9	Side Credenza Providing & fixing Side credenza (18" deep) made of 19 mm thick commercial ply and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have three drawers, horizontally running on side mounting drawer slides (channels) of approved make. The remaining part of the credenza will have cupboard with shutters and one shelf. The shutters with handle knob and magnetic catcher shall be provided beneath the drawers all non visible inside surfaces shall be finished with white/off white laminate 1mm thk. and teak wood edges / lipping beading shall be Spirit polished with matching pigment. The work also includes dismantling/removal of any existing/old furniture and removal of same from site to contractor owns dump. a Officer's & Staff side credenzaas per Drawing & specification mention in item above. Size - 3'-0", 4'-0" X 1'-6" X 2'-6" (W X D X H) 2.05 Rmt Comm. Ply/ Board : (Make Century:Sainik/Green Feotech/Archidply) Laminate (Make: Greenlam,Merino,Century,AICA) Hardware: (Make Godrej/Ozone/Hettich/Hafele/Harison) Teak Veneer/Ply As per Selection @70/- Sq.ft	44	R.ft.	
10	Wooden boxing for electrical panel: Providing Cabinet unit of size 18"wide 18mm thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) with 1.0mm thick horizontal laminate, 8mm thick bison panel board back side alongwith wall. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partial wood beading / moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges (dadoo kabzaa) to be used for fixing storage unit shutters.	40	Sq.Ft	
11	Low height storage unit : Providing storage unit of size 18"x4'-0" (W x H) of 3/4" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate having shelves @1'-3" C/C. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partial wood beading / moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges (dadoo kabzaa) to be used for fixing storage unit shutters. All inside surfaces are finished with 0.7mm thick laminated and beading moulding shall be paint/polish. All work is done complete in all respects.	230	Sq.Ft	
12	Full height storage unit - Providing storage unit of size 18"x9'-0" (W x H) of 3/4" thick commercial ply BWR grade IS 303 (phenol bonded, B.W.P., borer proof, chemically treated) with 1.0mm thick horizontal laminate and 1.0mm thick vertical laminate having shelves @1'-3" C/C. The storage unit will have all necessary hardware, decorative jalli pattern laminate band and teakwood/ partial wood beading / moulding. Recessed skirting (3/4") finished with 1.0mm thick laminate is present. Clip hinges (dadoo kabzaa) to be used for fixing storage unit shutters. All inside surfaces are finished with 0.7mm thick laminated and beading moulding shall be paint/polish. All work is done complete in all respects.	828	Sq.Ft	
13	PIN UP BOARD :- Made of 12mm thick soft board covered by 25mm x 25mm teak wood beading painted polished to approved colour and soft board covered with blazer/ fabric cloth of approved colour. Texture and sample approved by architect. Notice Board to be fixed to wall space between storage unit (ground placed) and storage unit (wall hung) in manager's Cabin & on top of writing table & in Banking Hall. (basic rate of fabric shall not be less than Rs.65/- per mtr.)	100	Sq.Ft	
14	FALSE CEILING:-			
a	GYBOARD FALSE CEILING: Providing and fixing Gypsum board false ceiling in levels as per the detailed drawing - made up of G.I. frames as specified by Gypsum India limited and 12mm thick Gypsum board with suitable suspenders fixed to the ceiling. Ceiling section, perimeter channel, suspenders etc. shall be standard sections supplied by Gypsum India LTD. Spacing of intermediate channels shall be at 1200c.c. and ceiling section at 457mm c/c the work includes finishing of joints, applying primer, two or more coats of plastic emulsion paints (white colour) , making cut-out for light fixtures, etc. providing of perimeter channels / beading etc. complete in all respect	1500	Sq.ft	
b	Providing & fixing teak wood vinear false ceiling in levels as per detailed drawing made up of G.I frame as specified by gypsum india limited and frame work to be covered with 4mm thick vinear over 9mm thick ply wood of BWR grade IS 303(phenol bonded , BWP, borer proof chemically treated) of century green make and 1mm thick laminate as per colour scheme suitable suspenders fixed to the ceiling , ceiling section perimeter channel , suspenders etc. shall be standard saction supplied by gypsum india limited. spacing of intermediate channel shall be @ 1200mm c/c & ceiling saction at 457mm c/c. 35/12 steam beach kipping to be provided to all the edges complete job including melamine polish on edge beading , cornices etc. and painting of groov in approved colour. All job to be done as per architect satisfaction bank direction the work includes making cut out for light fixtures. complete in all respects. Note: provision of coves shall be givened as mantedion in drawing.	250	Sq.ft	

c)	<p>Providing and fixing of false ceilings at all heights of 600 mm x 600 mm x 16 mm ARMSTRONG Mineral Fibre ceiling tiles of type Prima Dune Premier-Beveled Tegular Edge RH-99 laid on 15mm exposed grid system. The suspension system shall be the Armstrong Trulok Silhouette revealed profile grid system with 15mm wide flanges incorporating a 3mm or 6mm central recess color, black or white revealed. Silhouette main runners and cross tees to have mitered ends with "birds mouth" notches to provide mitered cruciform junctions. The framework comprise of main runner spaced at 1200mm centers securely fixed to the structural soffit by approved hangers at 1200mm maximum centers. Hangers (GI wire of 4.0mm dia) to be fixed by approved roof plug, level adjusters and screws etc. The last hanger at the end of each main runner should not be greater than 450mm from the adjacent wall. Flush fitting 1200mm long cross tees (with double stitching) to be interlocked between main runners at 600mm centers to form 1200 x 600mm modules. Cut cross tees longer than 600mm to be supported independently. 600mm x 600mm modules to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200m cross tees and making arrangement for light fixtures, etc. complete in all respect.</p> <p style="text-align: right;">Make Armstrong/ Unidus/Diamond</p>	1200	Sq. ft		
15	<p>Meeting Room table of approx. size 2700x1200mm (size to be considered based on site conditions). Providing & Fixing Conference Table of shape as per design made from 50mm X 40mm T. W. Wood framework 450mm center to center both ways for tabletop covered with 12mm thick BWR ply for bottom, 19mm thick BWR ply for top, table stand and base with necessary 50mm X 40mm vertical supports. All exposed surfaces shall be finish with approved color 1.0 mm thk. laminate. All internal surfaces to be finished with 0.8mm thick laminate. All edges to be provide with TW lipping patti finished with melamine polish. Rate shall be inclusive of Brush Finish Stainless Steel Tray with POP UP Flap for electrical switches including necessary openings for wire manager, mikes carting away unserviceable materials out of the compound, cleaning the site etc. complete as per the detail drawing and instruction of Engineer. Plywood Make: Greenply, Century, Duro, ISI marked BMR - IS 303 or equivalent approved by the Bank</p>		Nos.		
16	<p>Centre TABLE :- Providing and placing centre table of size 3'-0" x 1'-9" x 1'-6" made with 2" x 2" teakwood frame melamine polished with decorative 2 1/2" x 1 1/2" beading along with 12mm thick Glass on the top. All inside surfaces are painted with 2 coats of synthetic enamel paint over coat of wood primer. All work is done complete in all respects to architects / bank managements satisfactory.</p>	5	Nos		
17	Planter:				
a	Providing planter of size 1'-6"x1'-6" for waiting area finished with 1mm th laminate as per drg	7	No's		
18	<p>Panelling With ACP / Aluminium Composite Panels (With Aluminium Frames) Supplying & fixing 4mm thick Aluminum component sheet of approved make and shade (as per bank design) including making of ground of (1"X2") aluminum hollow section as per design .with 6mm-19mm wide vertical or horizontal groove finished with Dow Cowing sealant (789) as per Architect's drawings & instructions aluminum componenet sheet should be of virgin grade and having aluminum profile thickness of 0.5 mm on both sides of core. The rate is inclusive of all fixtures and fittings (with sealent) for proper finish. The works includes front face shutter boxing complete. the rate includes all required shuttering,scaffolding, labour, material, complete. Makes:-Aluco bond/Alu Decor/Alstrong/Alstone/Alex.</p>	400	Sqft.		

19	<p>MDF Fluted Wooden Panelling Wall paneling made from framework of 50 x 25 x 1.20 mm thick hollow aluminum sections spaced 450mm c/c both way (Intermediate), Claded with 8.0 mm thk over which MDF fluted wooden panel of 19mm +/- 2mm shall be fixed as per the design in the drawing or as directed by Architect.</p> <p>(i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 450mm c/c both way (Intermediate) & as required in width of bands, centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb & claded with 8.0mm thk. over which MDF fluted wooden panel of 19mm +/- 2mm shall be fixed.</p> <p>(ii) Panel Finishing - Providing & fixing 19mm +/- 2mm thick approved MDF Wooden Panelling fixed on the aluminum sections claded with 8.0mm thk. with tongue and groove joints in line and level.</p> <p>(iii) The rate should include cost of necessary hardware, making cutouts openings for electrical conduits cables, Switch boards, AC ducts etc., including providing necessary wooden aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site.</p> <p>(iv) The Duco paint shall be of approved make and shade. The surface to be painted shall be first prepared smooth by applying proper grade of sand paper water-paper and then if any pores are noticed the same shall be filled with approved quality synthetic filler agent. The complete surface shall be then applied an even coat of sealer putty and permitted to dry. The surface shall be again grinded smooth and even using appropriate grade of water-paper. When the surface is properly smooth and leveled without any pores or cracks the same shall be spray painted with approved quality Duco paint. The adjoining surfaces which are not to be painted with this application shall be suitably masked using appropriate masking tape. The paint shall be permitted to dry at room temperature and attain smooth lustrous finish.</p>	50	sq ft.		
20	Painting Work –				
a)	Texture Paint: Providing and applying special / texture paint Asian royal matalic finish of approved shade & make as per manufacturers specification and architects instructions, payment shall be made only exposed surface of texture paint. No measurement shall be made for texture paint behind paneling, furniture such as tables, Credenza, storage etc.	1120	Sq.ft		
21 a)	Door to System room - Fire rated steel door including frame Door to System room - Fire rated steel door including frame - 2 (Two) Hrs Metal test certificate will be provided issued from GQMC. 1.95 Sq.mt a) Frame - Providing and fixing fire resistant door frame of section 100 x 50 mm having built in rebate out made up of 1.2 mm GPSP Sheet duly powder coated / 16 SWG G.I. sheet (zinc coating not less than 120 gm /sqm) duly filled with vermiculite based concrete mix, suitable for mounting 120 minutes fire rated door shutters. The frame is fitted with intumescent fire seal strip of size 10 x 4 mm (minimum) around the frame and fixing with dash fastener of approved size and make, including apply a coat of approved brand fire resistant primer etc. complete as per direction of Engineer in charge (including Dash fastners).Door Size 1000x2100mm approxitely or as per direction of engineer incharge.		No		
b	Shutter - Providing and fixing Metal Door Shutter 46 mm thk.made up of 0.8mm thick GPSP Sheet. Glazed fire resistant door shutters of 120 minutes fire rating conforming to IS : 3614 (Part – II), tested and certified as per laboratory approved by Engineer in charge.with suitable mounting on door frame. the entire shutter filled insulation material / Honeycomb craft paper of 160gsm (zinc coating not less than 120 gm/m2) and fixing with necessary stainless steel ball bearing hinges of approved make.provision of Fire Rated Wired Glass size of glass 300 X 200 including applying a coat of approved fire resistant primer etc. all complete as per direction of Engineer – in charge (paneling to be paid for separately)				
c	Hardware for fixing - Fire rated steel door including frame Providing and fixing following hardware for fixing fire rated steel door including frame, complete. Hinges 4X3X3 (Min. 3Nos), Pull Handle 19 X 250mm - Pair, Dead Lock, Fire Rated Wired Glass size - 300 X 200, Fastners Hilti 10 X 92mm - (Min - 10Nos.) Make:- GMC,Baddi/Kutti, Paonta,Guardwell				
	TOTAL OF INTERIOR WORKS(Total Items 1 to 21)				
	THESE RATES ARE EXCLUDING G.S.T. RATES				
	TOTAL FOR INTERIOR WORKS				
	DISCOUNTS IF ANY				
	GRAND TOTAL				
	IN WORDS (RS)				

SIGNATURE OF CONTRACTOR
NAME OF CONTRACTOR