

PRICE BID

NAME OF WORK: INTERIOR & FURNISHING WORKS OF E-LOBBY AT STATE BANK OF INDIA, MAIN					
S.NO.	SPECIFICATIONS	QNTY.	UNITS	RATE	AMOUNT
1	FIXED TOUGHENED GLASS IN PARTITIONS, WITH ETCHING:				
	Providing & Fixing 12mm thk. Toughened Glass Panels with SS glass connectors of 304 Grade, fixed in position, with etching / filming, as per interior details/instruction of the Achitect/Engineer in charge.	13.00	sq.m.		-
	<i>Make: Asahi India, St. Gobain, Modiguard</i>				
	<i>Glass Connectors: Godrej, Dorma, Ozone, Stanley</i>				
2	12MM THICK TOUGHENED GLASS DOORS WITH PATCH FITTINGS & ETCHING/LOGO:				
	Providing & fixing frameless fully glazed 12.0 mm thk. toughend float glass doors, single leaf glazed Toughned door of size approximately, 1800 to 700mm X 2100 mm all sides edge grainded, polished to be fixed on patch fittings, the door to be to be fitted horizontally / vertically as per instructions. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include necessary etching film / logo all inclusive, complete	3.00	sq.m.		-
	NOTE: Rates include Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" SS door handle (both sides) etc. all complete of Godrej / Dorma/ Ozone make.				
	<i>Make: GLASS Asahi India, St. Gobain, Modiguard</i>				
	<i>Hardware (patch fittings etc): Godrej, Ozone, Dorma, Stanley</i>				
3	LOW HEIGHT WOODEN PARTITION WITH LAMINATE				
	Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be cladded with 8mm thick commercial ply and 1.0mm thick laminate APPROVED make in specified pattern as per interiors details on both sides. Also 3"x5/8" teak wood section shall be provided on the exposed edges of the partitions, including provideing grove for 12mm thich glass wherever specified. The rate shall also include for providing grooves in laminate & wood.	13.00	sq.m.		-
	Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.				
	Makes:				
	<i>Commercial ply: Century-SAINIK, Greenply-ECOTEC, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Century</i>				
	<i>Autolock: Ozone, Godrej, Haffle, Hettich</i>				
4	PARTITION : 3" THICK FULL HEIGHT UPS/ LAN - ONE SIDE CALCIUM SILICATE SHEET/ OTHER SIDE PLY) FOR UPS/ SERVER ROOM				
	PARTITION : 3" THICK FULL HEIGHT UPS/ LAN - ONE SIDE CALCIUM SILICATE SHEET/ OTHER SIDE PLY) FOR UPS/ SERVER ROOM: P/ F full height partitions made out of 16 gauge Aluminium Framing of 50 mm X 50 mm at 600 mm Centre to Centre both ways (vertically & horizontally). The frames must be rigidly fixed to the floor / walls & ceiling slabs. The 16 gauge aluminium angle cleats shall be used for joinery with aluminium metal screws. The aluminium framing then shall be covered with 12 mm thk BWR ply of approved make finished in 1 mm thk laminate of approved make & shade on one side and 12mm thk calcium silicate board duly finished & painted (as per painting on wall specs) on the other side. Necessary cuttings for Electrical conduits & Electrical fittings as per the requirements shall be provided, as per design / drawings / instructions. The partition rate shall be inclusive of cost of the flush door size 3'0" x 7'0" with inner side 6mm calcium silicate and outside 1mm laminate including handle, door closure, Hinges and Tower bolts. The door will have peep window (1' x 1') at 5' level with 6mm thk glass. Note: For the measurements of Partitions, area up to the false ceiling height only shall be considered.	11	sq.m.		-

S.NO.	SPECIFICATIONS	QNTY.	UNITS	RATE	AMOUNT
	Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.				
	Makes:				
	<i>Commercial ply: Century-SAINIK, Greenply-ECOTEC, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Century</i>				
	<i>Autolock: Ozone, Godrej, Haffle, Hettich</i>				
5	FALSE CEILING - (MINERAL FIBRE TILE):				
	Providing & fixing Armstrong false ceiling RH-99 with 600x600x16 mm Fine Fissured Beveled Tegular Edge false ceiling laid in Armstrong silhouette grid system. The frame work comprises of main runner spaced at 1200 mm centres securely fixed to structural soffit by approved hangers at 1200 mm maximum centres. Hangers (G.I. wires 4.0 mm dia) to be fixed by approved roof plug, level adjuster, screws etc. The last runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200mm long cross tee(with double stitching) to be inter locked between main runners at 600mm centres to form 1200x600mm module. Cut cross tees longer than 600mm to be supported independently. 600x600mm module to be formed by fitting 600 mm long flush fitting cross tee centrally between 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to wall @ 450 mm maximum centres. The rates include making opening for electric fixtures, A.C units etc. Rates include dismantling existing false ceiling and removal of malba from site, complete in all respect.	14.00	sq.m.		-
	MAKE: Armstrong, St. Gobain (India Gypsum)				
6	GYPBOARD FALSE CEILING:				
	Providing and fixing suspended false ceiling including steps as per design with 12.5mm tapered edge Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level.The grid consists of a perimeter channel (MF6a of dimensions 20mm x 27mm x 37mm x 3.5M) fixed round the perimeter to receive and of the ceiling section (MFS) and the outer edges to gypboard. The intermediate channel (MF7) of dimensions 15mm x 45mm x 0.9mm x 3.6M) at 1200mm c/c in the one direction and the ceiling section (MFS of dimensions 80mm x 26mm x 0.5mm x 3.6M) at 450mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 2Smm x 0.5mm) at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together.	22.00	sq.m.		-
	The gypsum board layers are screwed to the M/F ceiling sections with gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. AIC ducting etc.The work includes painting with 2 coats of plastic emulsion to give an even & finished surface. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.				
	MAKE: St. Gobain (India Gypsum)				
7	DOOR CLOSER:				
	Providing and fixing silver colour (or matching with colour scheme as per site) hydraulic door closer complete in all respects.	1.00	no.		-
	Makes:				
	<i>Commercial ply: Century-SAINIK, Greenply-ECOTEC, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Century</i>				
	<i>Autolock: Ozone, Godrej, Haffle, Hettich</i>				
8	WRITING DESK/FORMS STAND				

S.NO.	SPECIFICATIONS	QNTY.	UNITS	RATE	AMOUNT
	Providing and fixing forms stand of size 4'-0" X 1'-6" X 3'-9" with 3 nos. storage units of forms with 12 mm glass top fixed with 3" SS spacer. Space for housing vouchers of size 1'6" W, 1'-0" D & 9" H is also provided on the top and on side (L-shaped, wall hung) as per drawings made of 19 mm thick commercial ply with 1.0 mm thick laminate to be fixed and ¾" x ¼" teak wood lipping on two visible sides on it All exposed Teak wood edges / teak wood lipping / beading shall be spirit polished with matching pigment. etc. & to be fixed on the wall.cost of spacers ect. all inclusive complete.	1	no.		-
	Makes:				
	<i>Commercial ply: Century-SAINIK, Greenply-ECOTEC, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Century</i>				
	<i>Telescopic Channels: Godrej, Ozone. Hettich, Haffele, Harison</i>				
	<i>Drawer Locks: Godrej, Ozone, Hettich, Hafele</i>				
	<i>Autolock: Ozone, Godrej, Haffle, Hettich</i>				
9	COVE IN CEILING				
	Providing and Fixing of Cove in Gypsum Board same as item No .17	16.00	MTR		-
	<i>MAKE: St. Gobain(Gyproc), Lafarge</i>				
10	ACP CLADDING				
	Providing cutting, bending and fixing of aluminium Composite Panel cladding of approved make / manufacture on external façade of size as shown in drawings at all heights and elevation including necessary frame work, either curved or straight or circular in plan. The aluminium composite panel should consist of 3 mm thick thermoplastic core of anti - oxident LDPE + HDPE (Virgin Core) sandwiched between two layers 0.5 mm thick aluminium alloy sheet (alloy grade 3003 of ASTM B-209) making a total panel thickness of 4 mm.The surface finish shall be PVDFcoat of 30 micron over a base polyester coat on top and service coat on the reverse with chrome /alkyd of 6 - 7 microns coating shall confirm to ASTM D 2244-93 and ASTM D 523 - 89 for color retention and chalk resistance.ACP shall be fixed on especially designed aluminium frame work with horizontal and vertical members of extruded aluminium made out of AA 6063 T, 6 - 20 microns anodizing shall be done on the aluminium section. The aluminium frame wotk shall be of 50 x 25 x 1.6 Sheet to be supplied in width of 1220 mm. The color shade and texture of the ACP to be as per the approved Bank color design and pattern.	64.00	sq.m.		-
	TOTAL (ITEMS 1-10)				-
	Add GST on Grand Total @ 18%				