

PRICE BID FOR COMPOUND WALL REPAIRS OF OLD COCHIN BRANCH BUILDING, CALVATHY, FORT KOCHI					
SI No	Particulars	Quantity	Unit	Rate	Amount
1	Site clearance work including removal debris, existing trees and bushes etc	1	Ls		
2	Earth work in excavation including including stacking at suitable place within the complex and backfilling and disposal of surplus excavated earth away from the site without any risk and cost to the Bank.All kinds of soil.	40	Rm		
3	Plain cement concrete 1:4:8 below the RCC plinth using 40 mm metal,M sand including materials, labour charges, etc complete for foundation (10 cm thick)	3	CuM		
4	RCC 1:1.5:3 using 20 mm broken stones for belt, column, including all form work, watering, curing etc complete for compound wall complete but excluding cost of reinforcement for Lintels and plinth beams	12	CuM		
5	Providing and laying steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete for Lintels and plinth beams. Thermo-Mechanically Treated Bars	1200	Kg		
6	Providing and laying 20 cm thick solid cement concrete block masonry in CM 1:6 (1 Cement, 6 Sand) including all scaffolding, labour, coveyance, lead, lift,curing etc. complete.	25	CuM		
7	Plastering with CM 1:4, 12mm thick (1 cement & 4 sand) 12mm thick one coat floated hard and traveled smooth to walls including all staging work watering, curing etc complete.	230	SqM		
8	Supplying and erection of G.I barbed wire fencing above compound wall , three lines and column post 60cm heigh and column disatnce 3m.	45	Rm		
	TOTAL				0
					GST extra