

BOQ FOR CONSTRUCTION OF PATHWAY / WALKING TRACK AT SBI GUEST HOUSE LONAVALA

Sr No	Item	Unit	Qty	Rate	Amount
1	Paver Block (60-65 mm thick) Providing and laying approved quality chamfered edge factory made, rubber moulded, M-30 grade cement concrete interlocking paver block manufactured through block making machine with strong vibratory compaction, of approved size, design and shape, laid in required colour and pattern including laying 50 mm thick compacted bed of coarse sand, filling the joints with fine sand, finishing and sweeping extra sand etc. in footpath, compound area, driveway etc. complete as per the direction of Engineer-in-charge. The rates to inclusive of cutting of paver blocks as per required size and pattern. Alcock, Vyara, Pavit, Kaptim or equivalent approved by the Bank	Sqft	5200.00		
2	Kerb stone Providing and laying approved quality, factory made M-25 grade cement concrete Kerb Stone of size 450 X 300X 150mm fixed in proper line, level and curvature, jointed with cement mortar 1:2 (1 cement : 2 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage openings, wherever required, including painting with 2 coats of exterior grade weather proof paint in desired shade complete etc. as per direction of Engineer-in-charge. (Precast C.C. kerb stone shall be approved by Engineer-in-charge). Note : Length of finished kerb edging shall be measured for payment. Alcock, Vyara, Pavit, Kaptim or equivalent approved by the Bank	Rft	2600.00		
3	P and Filling of boulder for soling appx. 8"-9" depth below PCC for path ways, compacting, etc as per requirement of bank..... complete job	Sqft	5200.00		
4	Providing and laying in position machine mix PCC (plain cement concrete) 1:2:4, under foundation, plinth protection, floor slabs, grade slabs, coping, sill concrete etc. including transporting, laying, compacting, finishing the surface in line, level and plumb as per requirement and curing etc. complete. The Rate to include necessary formwork, centring, shuttering, complete in all respects and execution of work at all heights and location with required leads and lifts complete as directed by Engineer in charge.	Cft	2600.00		
			Sub Total		
			Discount if any		
			GRAND TOTAL		
				plus GST	

THE QUANTITIES CONSIDERED IN THE ESTIMATE ARE AN APPROXIMATE BASIS WHICH MAY VARY BOTH WAYS. THE CONTRACTOR SHALL HAVE NO CLAIM REGARDING THIS. BILL WILL BE PAID AS PER ACTUAL MEASUREMENT AFTER COMPLETION OF WORK SATISFACTORY.

THE CONTRACTOR MUST VISIT THE SITE BEFORE QUOTING RATES. SO THAT THEY MAY FAMILIAR WITH THE WORKS AND MATERIAL USED AT SITE. SIMILAR TYPE OF WORK HAD ALREADY BEEN DONE AT SBI GUEST HOUSE AT LONAVALA. NOTHING EXTRA SHALL BE PAID AGAINST ANY WORK/ITEM. THE CONTRACTOR IF REQUIRED MAY PLEASE BE DISCUSS WITH THE ENGINEER INCHARGE OF THE PROJECT BEFORE SUBMITTING THEIR TENDER.

--	--	--	--	--	--

FOR DETAILED SPECIFICATIONS AND MAKE OF MATERIAL, THE CONTRACTOR MUST SEE THE TECHNICAL BID BEFORE QUOTING RATES.