

PRICE BID - SBI RBO GANDHIDHAM - INTERIOR FURNISHING WORK

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : ALL ITEMS				
	Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIES, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED				
I	WORK STATION / COUNTER				
	GENERAL NOTES FOR : For all work stations				
	The W.S. should have <u>READY MADE leg rest</u> HIGH IMPACT POLYSTYRENE WITH CHROME PLATED METAL STRUCTURE				
	There should be provision for <u>cable manager</u> system with necessary cutouts in top surface				
	<u>C.P.U. trolley</u> from Steel with lockable roller supports/ Nylon castors.				
	<u>key board tray</u> made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it.				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 1 mm thick thick laminate & Burma Teak beading on Edges with lacquer polish				
	2) Front Apron & Sides: 1 mm thick thick laminate & Burma Teak beading on Edges with lacquerpolish				
	3) Facing of Drawers: 1 mm thick thick laminate & Burma Teak beading on Edges with lacquerpolish				
	4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
	5) All the wooden surface : polished of approved shade				
	As per drawing and instruction of Architect/Bank Complete				
1	ASSISTANT GENERAL MANAGER TABLE SIZE : 7'-6" X 3'-6" X 2'-6"+ SIDE RACK - SIZE:3'9"X1'6"X 2'6" with 1 mm thick LAMINATE finish on Table Top , sides & Edges and all other visible surfaces etc complete as follows	1.00	No.		
	TABLE				
	Supplying and installation of Table as per the following description : Size 7'6" x 2'-9". Table top shall be made from 18 mm thick commercial ply wood with 1 mm thick laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. . Computer Key board of metal of approved make shall be provided. Exposed surfaces of the unit shall have 1 mm th laminate finish <u>ready made Foot rest</u> shall be provided. All internal surface will have 0.60 mm thick balacing laminate				
	Apron (Modesty Panel) & Table sidemade from 18 mm thick ply wood finished 1 mm laminate Finish All visible area should be in 1 mm laminate finish. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood drawer unit of 1'-4" x 2'-0" x 2'-0" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle				
	SIDE RACK - SIZE: 3'9"X1'6"X 2'6"				
	Supplying and providing side cabinet : Having openable shutters as directed. Cabinet shall be made from 18mm thick commercial ply wood with 1.00mm thick thick laminate. back shall be made from 6mm th commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with veneer finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers.				
	As per drawing and instruction of Architect/Bank Complete				

PRICE BID - SBI RBO GANDHIDHAM - INTERIOR FURNISHING WORK

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : ALL ITEMS				
	Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIES, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : Teak Veneer with PU Coating & Burma Teak beading on Edges with PU Coating				
	2) Front Apron & Sides: Teak Veneer with PU Coating				
	3) Facing of Drawers: Teak Veneer with PU Coating				
2	CM W.S. - SIZE : 6'-0"X 2'-6"X 2'-6" + SIDE RACK - SIZE : 3'-3"X1'-4"X2'-6" As / item no. I / 01 but with different in size Other specifications remains the same.	4.00	No.		
3	MGR W.S. - SIZE : 5'-6"X 2'-6"X 2'-6" + SIDE RACK - SIZE : 3'-3"X1'-4"X2'-6" As / item no. I / 01 but with different in size & without pencil drawer. Other specifications remains the same.	4.00	No.		
4	OFFICER'S W.S. - SIZE : 5'-0"X 2'-6"X 2'-6" + SIDE RACK - SIZE : 3'-3"X1'-4"X2'-6" As / item no. I / 01 but with different in size & without pencil drawer. Other specifications remains the same.	2.00	No.		
5	CLERK'S W.S. - SIZE : 4'-6"X 2'-3"X 2'-6" - without side rack As / item no. I / 01 but with different in size & without pencil drawer & side rack. other specifications remains the same.	1.00	No.		
6A	CLERK'S W.S. (cluster) - to the shape I type - SIZE : 5'-0"X 5'-0"X 2'-6" as per above but will be fixed to the low high partition there will be no front apron	16.00	No.		
6B	CLERK'S W.S. (cluster) -4'6"X 2'-6" as per above but will be CHANGE IN SIZE & SHAPE	6.00	No.		
7	CONFERENCE TABLE The basic structure of the Conference table shall be made out of 18 mm ply with all open edges covered with wooden beading of req. size. The top shall be of 18 mm th. ply + additional 18 mm th. ply patta with T.W. besding of 1 1/2"x 1/2" on external sides & 3" box made out of 18 mm ply. on internal sides, <u>can be made operable to operate from the bottom for cabelling purpose</u> . The middle vertical supports shall be of 18 mm ply with 1 mm laminate on both side & T.W. beading. The front apron will have grooves pattern in laminate. The W.S. should have 3" X 1 1/2" T.W. leg rest .There should be provision for cable manager system with necessary cutouts in top surface. The horizontal TOP shall be in 6 mm th. SOLID SURFACE(curian) finish & ON vertical surfaces on all open external sides WILL HAVE LAMINATE . It will be in balancing laminate(matching to veneer) on internal surfaces. All the wooden borders / members / veneer shall be in a melamine finish	14.10	RMT		

PRICE BID - SBI RBO GANDHIDHAM - INTERIOR FURNISHING WORK

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : ALL ITEMS				
	Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIES, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED				
8	DINNING TABLE: 5' 0"x 2'6"x 2'6" Supplying and installation of Dining Table of 2'-6" height, 1" x 1.5" ht. T.W beading shall be fixed on border. Top shall be made of 18 mm thick commercial plywood with additional 18 mm thick Ply wood patta of required width on edges with 1.0 mm thick laminate on top of approved shade and supports of the Table shall be made of 2" x 2" T.W. members in a Design as directed. All surfaces not laminated shall be lacquer polished.Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.	2.00	No.		
II	<u>PARTITIONS / GLAZING</u>				
9	P & F LOW HEIGHT PARTITIONS – 4'-0"HT <i>As / item no. II / 02a but with different in ht & REGULAR glass. Other specifications remains the same.</i> WICKET GATE P/F one no of 30 mm thick flush shutter (2 NOS) with both side laminate including 5" SS hinges with countersunk SS screws, Approved make Night latch Lock, S.S Handles,Door stoppers,150 mm long Door stoppers, doorstop of approved make etc.	74.00	SQMT		
V	<u>MIS. FURNISHING ITEMS</u>				
10	PINUP BOARD P & F pinup boards. It consist 12 mm th. soft boards of good density to be mounted over 12 mm ply. & covered with 3/4" x 1/4" beading before putting the fabric. The soft board will be covered with a plain (Basic rate Rs. 240 /- per mtr.) from front and edges. Molding of size: 3/4"x1/4" will be fixed on all four sides & will be finished in melamine polish. (Only soft boards provided other than the partitions will be measured and soft board made in the partitions will be the part of the partition)fabric	6.00	SQMT		
11	Supplying and installation 1'-9" x 1'-9" x 1'-3" height for Corner Tepoy Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.	2.00	No.		
12	Supplying and installation 3' x 2' height	1.00	No.		
13	visitors sofa The seat shall be made out of 19 mm BB in a box form. The back shall be made out using internal wooden frame work of size 2"x1 1/2" covered with 6 mm ply. It shall be covered with 100 mm & 50 mm th. 40 density u foam in seat & back respectively. This should be again covered with 14 mm th. 40 density u foam with madarpat cover on it & upholstered of suggested shade & finish in seat & back on all open visible sides with basic rate of Rs.900/- per meter. It will have wooden handlesas / drawing. outer length with armrest will be considered for measurement purpose. [REFER DRG NO-5]	6.30	RMT		
14	ROLLER BLIND Supplying and fixing Roller Blind Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Including GST)	45.00	SQMT		

PRICE BID - SBI RBO GANDHIDHAM - INTERIOR FURNISHING WORK

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : ALL ITEMS				
	Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIES, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED				
15	LUNCH counter(1' 6" WIDE) IN JET BLACK Providing and laying platform of 1'6" width (clear width) and at 2'6" height (finished top level) from floor . BWR ply wood 19mm thick supported on Steel L angle bracket. The plat form should be cantilevered from the wall as shown in the drawing. 9" wide 19mm thick BWR ply wood to be provided below the entire lunch counter for Tiffin and kitchen items. The ply surface to be covered with 1 m m laminate as per required shape and size	4.60	RMT		
16	WOODEN PLANTER : 2'3"x 1'6"x 1'6"- to the shape between the curved sofa P/F planter box with using 18 mm thick MR Grade plywood on all sides with 1.00 mm Thick Laminate as per requirement and drawing etc complete as directed. this box to be fixed on adjoining column , free from the floor level	3.00	No.		
II	PARTITIONS / GLAZING				
17	FULL HEIGHT PARTITITONS				
17a	P & F FULL HEIGHT PARTITIONS - PARTLY PANELLED / PARTLY GLAZED including door	87.70	SQMT		
	BASIC STRUCTURE: P & F full height partitions made from internal frame work of size 2"x1" x min. 1.5 mm th. Alu. sections, fixed by means of al. angle of 1"x1"x1" size for proper fixity. The entire Alu. frame work shall be covered with 12 mm th.MDF on both the sides. All open sides of the framework shall be covered with the 12 mm th.MDF to cover the entire thickness of the partition. The upper portion rom 3' to 7' of the partitions will have 6 / 8 mm th. clear glass required as per size of glass, fixed with 2 1/2"x1/2" (F.S.) wooden molding with suggested grooves to cover the full thickness of the partition.The hinge side aluminum frame shall be in filled with wooden section. The same shall be than covered by 12 mm th. MDF panels to get the flush type partitions.				
	GENERAL: All the gaps either vertical or horizontal shall be filled properly with ideal material. All the vertical members of the partitions shall be carefully inserted / fixed in the floor (without damaging the floor) & also shall be fixed to the structural ceiling for proper strength.Necessary provision shall be made in the partition for ele. Conduits, switch boards,a.c. drain lines & ac's. etc.as req. The door shutters are included in this item. The common member of partition and frame of door will be considered in the item of partitions). Only below ceiling area will be considered for measurement purpose, however the partition shall be raised atleast by 3" above the false ceiling level for having fixity for the ceiling & also all vertical member shall be taken up to the slab / beam bottom.				
	P & f of internal door shutters made out of 30 mm th flush door with suggested grooves with 6/8 mm th. clear glass fixed with 10 mm th. wooden molding to cover full th. of the shutter. including 3 Nos 5" long SS hinges with countersunk SS screws, Godrej Mortice lock, S.S Handles,Door stoppers, doorstop of approved make etc. complete as per drawing & instructions				
	FINISHES: All the external plywood components shall be finished with 1 mm th. laminate in on both the sides & also in the thickness of the partition. All external wooden members shall be in melamine matt polish finish.				
	THE PPPG FHP SHALL BE FIXED IN POSITION AS / INST.				

PRICE BID - SBI RBO GANDHIDHAM - INTERIOR FURNISHING WORK

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : ALL ITEMS				
	Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIES, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED				
17b	P & F FULL HT SOLID PARTITION	38.00	SQMT		
	as per above but without glass				
17c	P & F FULL HT SOLID PARTITION - HULUX	44.60	SQMT		
	as per above but without glass				
	shall be covered with 6 MM HYLUX BOARD, INSTEAD OF 12 mm th.MDF on both the sides. All open sides of the framework shall be covered with the 12 mm th.MDF to cover the entire thickness of the partition.				
	there will be one side laminate & inside should be in paint finish				
17d	PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS PARTITION	10.60	SQMT		
	Providing & Fixing fully glazed panels in front. The item shall be executed by fixing 15 mm x 15 mm, 1 mm th. S.S. 304 "c" shape chanel fixed in the floor in consealed manner & 15 mm x 25 mm, 1 mm th. S.S. 304 "c" shape chanel, fixed in the ceiling / fixed solid partition in consealed manner with necessary supports inside for proper strength / support. The glass shall of 12 mm th. Clear toughned glass with all edges machine cut, fixed with clear silicon sealent from both inside & outside & shall be provided with sufficient drying period. The entire glazing shall be erected in complete line & level. Clear visible area will be considered for measurment purpose.				
	The item includes the cutting of floor carefully to accodmodate the chanel & refinishing the same. All glasses shall be in full length only unless otherwise specified. IT WILL ALSO HAVE FROSTED FILM 3' IN HT FROM 1'6" TO 4'6" RUNNING LENTH				
	FINISHES:				
	All the joints between wall / columns / ceilings / floors & glass shall be finished with clear silicon silent from out side & inside.				
	The entire glazing, complete in all respect should be installed in position in complete line & level as instructed.				
18	Providing and fixing "Dorma/Ozone/Godrej " or equivalent make door closure.	13.00	No.		
19	Providing and fixing TOUGHTEN GLASS DOOR	12.30	SQMT		
	Providing & Fixing fully glazed panels in front. The item shall be executed by fixing 15 mm x 15 mm, 1 mm th. S.S. 304 "c" shape chanel fixed in the floor in consealed manner & 15 mm x 25 mm, 1 mm th. S.S. 304 "c" shape chanel, fixed in the ceiling / fixed solid partition in consealed manner with necessary supports inside for proper strength / support. The glass shall of 12 mm th. Clear toughned glass with all edges machine cut, fixed with clear silicon sealent from both inside & outside & shall be provided with sufficient drying period. The entire glazing shall be erected in complete line & level. Clear visible area will be considered for measurment purpose.				
	The item includes the cutting of floor carefully to accodmodate the chanel & refinishing the same. All glasses shall be in full length only unless otherwise specified. IT WILL ALSO HAVE FROSTED FILM 3' IN HT FROM 1'6" TO 4'6" RUNNING LENTH				
	FINISHES:				
	All the joints between wall / columns / ceilings / floors & glass shall be finished with clear silicon silent from out side & inside.				
	The entire glazing, complete in all respect should be installed in position in complete line & level as instructed.				

PRICE BID - SBI RBO GANDHIDHAM - INTERIOR FURNISHING WORK

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : ALL ITEMS				
	Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIES, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED				
III	PANELLING & BOXING				
20	P/F Wall panelling with framing laminate finishing for wall and Pillar etc	47.00	SQMT		
	Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. .				
21	Providing and fixing 18 mm thick plywood of 4" height skirting with 1.0 mm thick laminate finish runner patta on Storage Top / Table Top if required.etc complete as directed.	9.50	RMT		
22	P/F Wall panelling with out framing laminate finishing for wall and Pillar etc / Creating Box for fixing AC machine and concealing of copper and drain pipe and around front side main entrance door top, jams using 18 mm thick MR Grade plywood with 1.00 mm Thick Laminate as per requirement and drawing etc complete as directed.	72.30	SQMT		
23	ALUMINUM COMPOSITE PANEL	8.00	SQMT		
	Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or equivalent				
24	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will be made for any cutting in the film.	16.00	SQMT		
IV	STORAGE CABINETS				
25	GENERAL PURPOSE STORAGE CABINETS – OF VARIOUS SIZES & VARIOUS HEIGHTS (DRG. NO. 09)				
	NOTE : FINISHES for all storage				
	The entire unit shall be in 1 mm laminate finish on external vertical sides and in balancing laminate finish on internal surface. The wooden borders shall be in melamine matt polish finish.				
25a	GENERAL PURPOSE	51.00	SQMT		
	BASIC STRUCTURE:				
	P & F 1'-4" deep storage cabinet. The basic structure of the cabinet including shelves shall be made of 18 mm ply. It will 6 mm th. plywood puthi. For low height storage the top shall be like additional ¼" ply patta to get 1" thickness . The storage unit should have 18 mm th. ply openable shutters. It should with all S.S hinges, towers bolts, powder coated handle, ball catches, S.S approved make (group lock) multi purpose lock complte. Edges to be finished with teak wood lipping etc have 18 mm th. ply vertical & horizontal fixed shelves. The top will have 1"x1" wooden beading on 1 longer side.				

PRICE BID - SBI RBO GANDHIDHAM - INTERIOR FURNISHING WORK

NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : ALL ITEMS				
	Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIES, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED				
26	<u>ELECTRIC PANEL CABINET</u>	5.30	SQMT		
	P & F 1'- 4" deep storage cabinet as shown. The basic structure of the cabinet including dividers & shelves shall be made of 18 mm Bison panel sheet. It would not have any puthi but shall have req. additional supports to fix the same to the wall. It will have openable shutters as required & shall be made with 2"x1"x min. 1.2 mm th. Alu. Section framework covered with 6 mm bison panel sheet on all sides with 16. Gu. powder coated perforated S.S sheet as infill material.shutter with approved make handle, hinges,ball catches				
27	<u>P/F PANTRY PLATFORM CUPBOARD SHUTTER / drawer unit</u>	2.70	SQMT		
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiate for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed.				
	IT WILL HAVE 1 DRAWER UNIT OF 3 NOS OF DRWERS /AS / DRAWING				
V	<u>MIS. FURNISHING ITEMS</u>				
28	<u>P/A WALL PAPERS on Digital wall</u>	12.00	SQMT		
	Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft				
VI	<u>FALSE CEILING WORK</u>				
29	<u>P/F GYPSUM BOARD FALSE CEILING</u>	278.00	SQMT		
29a	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.				
	Note : (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment.				

PRICE BID - SBI RBO GANDHIDHAM - INTERIOR FURNISHING WORK					
NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
	GENERAL NOTES FOR : ALL ITEMS				
	Plywood (ISI 303 BWP) ANTI TERMITE PROPERTIES, Block Board IS 1659 / Flush Door IS 2202 , BIFMA APPROVED				
30	<u>Providing and Fixing of Armstrong Mineral Fibre Accoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid</u>	126.00	SQMT		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				
31	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)	120.00	SQMT		
	Providing and applying (with rollers only) Acrylic emulsion paint of required shed and approved make on new/old work in two or more coats to give an even shed including the preparation of surface for painting, applying primer and putty, at all heights complete as per manufacturer's specification and as directed.				
32	P/ F COLLAPSIBLE GRILL	12.00	SQMT		
	Supplying providing & fixing collapsible gate in M.S channel section complete with bottom and top guiding rails locking arrangement and painted with synthetic enamel paint over a coat of primer etc. complete as directed.				
	TOTAL QUOTED PRICE			Rs.	