

BILL OF QUANTITY FOR ELECTRICAL AND ALLIED WORKS OF SBI CHANDRAPURI BRANCH, RUDRAPRAYAG					
S. No.	Description	Unit	Qty.	Rate (in Rs.)	Amount (in Rs.)
	SPLIT/ CASSETTE TYPE AIR CONDITIONERS Hot & Cold				
1	Supplying, erection, testing and commissioning following wall mounted Split/ Root mounted cassette units of (Toshiba/ Mitsubishi/ Hitachi/ O-General/ Bluestar /Voltas/ Carrier) with cordless remote complete with all necessary fittings duly insulated with 9 mm thick nitrile rubber pipe insulation with (All coils – copper only), fan and fan motor, machine control panel improved Refrigerant Joints, .Air conditioners shall be fitted with hermetically sealed type suction cooled reciprocating or discharge cooled rotary compressor or scroll compressor. Compressor unit operating on R32/ R-410. All complete as per drawing, approval and instructions of the Architect/ Employer. Item to include powder coated outdoor stands as per the manufacturer specifications.(Rates to be inclusive of Copper refrigerant pipe with insulation up to 3 Mtr length only for Each split AC Unit)				
a	1.0 TR split AC minimum 3 star rating inverter type including all necessary fittings and mountings as specified by the manufacturer (For ATM & Meeting Room)	Nos.	3.00		
b	1.5 TR split AC minimum 3 star rating inverter type including all necessary fittings and mountings as specified by the manufacturer (For BM's cabin & Banking Hall)	Nos.	3.00		
c	2.0 TR split AC minimum 3 star rating inverter type including all necessary fittings and mountings as specified by the manufacturer (For Banking Hall)	Nos.	1.00		
2	EXTRA REFRIGERANT PIPING				
	Supplying and laying of Extra copper refrigerant piping with O class nitrile rubber insulation with pipe , both of size as specified by the manufacturer suitable for 1.0/1.5/ 2.0 TR Split type AC and 2.0 TR/ 3.0 TR/4.0 TR Cassette AC - From Indoor to outdoor Units (make as approved by Architect/ Bank)				
a	For 1.0 TR/ 1.5 TR/ 2.0 TR Split AC as specified by the manufacturer	Mtr.	45.00		
3	DRAIN PIPING				

BILL OF QUANTITY FOR ELECTRICAL AND ALLIED WORKS OF SBI CHANDRAPURI BRANCH, RUDRAPRAYAG					
S. No.	Description	Unit	Qty.	Rate (in Rs.)	Amount (in Rs.)
	Providing and fixing drain piping up to drain as directed by the engineer incharge with all accessories e.g. elbows, unions, sockets, reducers, reducing tees, nipples etc. Complete job including cutting chiseling in walls, floor and making good of all chases/ cuts etc. and discharging the drain into a floor trap/ gully as per site conditions with insulation, both as specified by the manufacturer (make as approved by Architect/ Bank).				
a	25 mm dia PVC drain pipe for Split AC	Mtr.	80.00		
4	Providing and fixing of lockable caging for outdoor unit grouted on wall or on roof with open able shutter made of 10 X 10 mm MS square bars placed vertically @ 6" c/c welded with 40 X 3 mm MS flat all- round. Item includes all necessary hardware, priming coat, synthetic enamel paint, hanger, clamps other accessories etc. All complete as per approval and instructions of the Architect/ employer.				
a	1/1.5/2 TR split/cassette unit	Nos.	7.00		
5	Supplying and laying of Extra Electrical interconnecting control cable from indoor to outdoor of size as specified by the manufacturer suitable for 1.0/1.5/2.0 TR Split type AC with 2mm thick FRLS Conduit and all other accessories etc. All complete as per approval and instructions of the Architect/ employer. (make as approved by Architect/ Bank).				
a	For 1.0/1.5/2.0 TR ACs	Mtr.	95.00		
6	Supplying, installation and commissioning of automatic 24HRS. programmable timer of required capacity to run A.C. alternately (MDS / L&T / Other reputed make).	Nos.	1.00		
TOTAL FOR AIR CONDITIONING WORKS					
Note:- The rates quoted includes all other taxes , duties , loading, unloading , transportation and other expenses etc to site. Only GST will be paid Extra					