

| PRICE BID                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |       |      |        |
|------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-------|------|--------|
| ESTIMATE FOR ADDITIONAL CIVIL WORKS FOR LIFT FAÇADE AT STATE BANK OF INDIA , ADMIN. OFFICE, LUDHIANA |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |       |      |        |
| S.No.                                                                                                | Specifications                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Qty.  | Units | Rate | Amount |
| <b>VITRIFIED TILE FLOORING:</b>                                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |       |      |        |
| 1                                                                                                    | Providing and laying 1st quality vitrified tiles (Marble series Double charged- JOHNSON/ KAJARIA/ RAK- as approved by Bank's Engineer/Architect) of following sizes, as per design pattern on floor & skirting with chemical or adhesive/ cement as directed and joints to be filled with grout of approved colour, including dismantling existing floor tiles and disposal of malba from site, cutting wooden/ aluminum doors to match new floor level, preparing of surface & disposal of malba from site. The work shall include the skirting , complete in all respects.                                                                                                                                                            |       |       |      |        |
| a                                                                                                    | 96"X48" Vitrified tiles Double Charged- marble series. The tiles shall be laid with 3mm wide spacers. Grooves shall be filled with epoxy grout of matching color.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 50.00 | sqm   |      | -      |
|                                                                                                      | <i>NOTE: Skirting shall be measured as per actual size &amp; paid in sqm. Only</i>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |       |       |      |        |
| <b>GRANITE FLOORING (LEATHER/ LAPPATO FINISH)</b>                                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |       |      |        |
| 2                                                                                                    | Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for flooring and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.                                                                                                                                                                                                                                                              |       |       |      |        |
|                                                                                                      | Granite stone flooring leather finished/lapato, colour black, Cherry/Ruby red                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | 25.00 | sqm   |      | -      |
| <b>CNC CUT JAALI WITH BACKLIGHTING</b>                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |       |      |        |
| 3                                                                                                    | Providing & fixing CNC Cut jaali cut out of pu duco paint finished hdhmr sheet 12mm thick with a back layer of frosted polycarbonate sheet, fixed over a wooden box, above the lift area, including framework as required, complete in all respects                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 11.00 | sqm   |      | -      |
| <b>UPVC WINDOWS /GLAZING</b>                                                                         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |       |       |      |        |
| 4                                                                                                    | Providing and fixing factory made uPVC white colour casement/ casement cum fixed glazed windows (of Fenesta /Fenstersol India / Kommerling make ) comprising of uPVC multi- chambered frame, sash and mullion (where ever required) extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), uPVC extruded glazing beads of appropriate dimension, EPDM gasket, stainless steel (SS 304 grade) friction hinges, zinc alloy (white powder coated) casement handles, G.I fasteners 100 x 8 mm size for fixing frame to finished wall, plastic packers, plastic caps and necessary stainless steel screws etc. | 28.00 | sqm   |      | -      |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |     |  |   |
|---|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|-----|--|---|
|   | Profile of frame & sash shall be mitred cut and fusion welded at all corners , mullion (if required ) shall be also fusion welded including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing & direction of Engineer-in-Charge |       |     |  |   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |     |  |   |
|   | <b>PAINTWORK</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                       |       |     |  |   |
| 5 | Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre                                                                                                                                                                                                                                              | 55.00 | sqm |  | - |
| 6 | Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work                                                                                                                                                                                                                                                                                                                                      | 55.00 | sqm |  | - |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |       |     |  |   |
|   | TOTAL AMOUNT                                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |     |  | - |
|   | Add GST on Grand Total @ 18%                                                                                                                                                                                                                                                                                                                                                                                                                                           |       |     |  |   |