

BILL OF QUANTITIES OF CIVIL WORK OF RETAINING WALL & PAINTING WORK AT STATE BANK OF INDIA HOLIDAY HOME GUEST HOUSE AT DALHOUSIE (HP)					
S.No	ITEM	UNIT	QTY	RATE	AMOUNT
A	PART -A				
	REPAIR OF RETAINING WALL				
1	Dismantling the existing Stone wall, Tree if any, Plants etc. with all precautions for surrounding structure and public, clearing the site as directed and disposal of the unserviceable materials/ debris away from the site with no cost & risk to the Bank.	LS	1.0		
2	Coursed rubble masonry with hard stone (first sort) in superstructure above plinth level and upto floor five level. in cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	75.00		
3	Providing and laying cement concrete 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) for Base, Walls, Lintel/ Beam, Shelves excluding cost of reinforcement steel but including scaffoldings and suttering, curing all lead/ lifts etc complete.	Cum	50.00		
4	Reinforcement Steel for RCC Fe 500 including cutting, bending, all lead & lifts etc. complete	Kg	4500.00		
5	PCC 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size) under floor & Footing etc.	Cum	25.00		
6	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	Sqm	250.00		
7	Providing and fixing 4" dia perforated UPVC pipe for Earth drainage	Mtr	100.00		
8	Supplying & laying of bi-axial extruded high modulus polypropylene geogrid conforming to MORTH SPECIFICATION for base/sub-base reinforcement having minimum tensile strength 30kN/m in the longitudinal and transverse direction, with 10.5kN/m and 21kN/m tensile strength at 2% and 5% strain respectively in the longitudinal and transverse direction, junction efficiency not less than 95% and with 38mm X 38mm mesh opening.	Sqm	200.00		
	TOTAL FOR PART A (RETAINING WALL)				
B	PART -B				
	RENOVATION OF GUEST HOUSE				
1	Painting the wall & ceiling with plastic emulsion paint minimum 2 coats of 1st Quality paint (Asian apcolite or equevelet) to give an even shade including removeing old loose paint, filling Birla Putti (2 coats) and then sanding wall to give even surface one coat of Primer etc. complete	Sqft	10000.0		
2	Painting the External wall with Exetrior emulsion paint minimum 2 coats of 1st Quality paint (Asian Apex or equevelet) to give an even shade including removeing old loose paint, filling Birla Putti (2 coats) and then sanding wall to give even surface one coat of Primer etc. complete	Sqft	2500.00		
3	Painting the Door, Windows, Grills, & Roofing Sheets with Enamal paint minimum 2 coats of 1st Quality paint to give an even shade including removeing old loose paint, filling Enamal Putti and then sanding wall to give even surface one coat of Primer etc. complete	Sqft	7500.00		
4	Cleaning the site i.e. cutting unwanted plants/ trees, trimming fence and Grass, disposal of the debris away from the site at authrised place of Muncipal corporation	Lot	1.00		

S.No	ITEM	UNIT	QTY	RATE	AMOUNT
5	Plantation of new sesional plant/ flowers as per local weather conditions including mixing compost in earth etc. complet	Nos	150.00		
	TOTAL FOR PART B				
	TOTAL FOR PART A				
	SUB TOTAL FOR PART A+B				
	DISCOUNT IF ANY				
	NET AMOUNT AFTER DISCOUNT				
Net Amount in Words:-					
GST (as applicable) shall be paid extra					