

PRICE BID FOR ELECTRICAL WORKS AT STATE BANK OF INDIA, SHARGOLE BRANCH.					
ITEM DETAILS		QTY.	UNIT	RATE	AMOUNT
PART-I : COMPUTER POINTS & DISTRIBUTION					
1	Supply all material, storing, handling, fixing of computer points computer points in suitable size of GI/PVC box including providing 3 nos 5 amps 3 pin modular sockets to be provided under table top and controlled by 1 no 15 A moduler type switch and indicator (to be provided above the table top in partition) with moduler cover plate etc complete as required including 3X2.5 sq. mm copper armored cable.. Note: Maximum two computer points are to be provided on one circuit. (Switches : Make: Anchor/Crabtree/North-West/MK	10	each		
	NOTE: ONE POINT EACH PROVIDED FOR STAFF AND 3 POINTS FOR THE BM CABIN.				
2	Supply, installation, testing and commissioning of factory fabricated distribution board rust inhibited powder coated sheet fabricated comprising of incoming and outgoing isolator & MCBs neutral link or neutral bus, top and bottom detachable entry earthing bolts interconnection and grouting bolts etc complete as required as per details below. Make: Havells/HPL/Standard/ Legrand/L&T				
a)	12 way SPN MCBDB Double Door comprising of 1 No 63 Amp DP Isolator and 10 No SPMCB 10/16 Amp. (UPS output)	0	no.		
b)	8 way SPN MCBDB Double Door comprising of 1 No 63 Amp DP Isolator and 6 No SPMCB 10/16 Amp. (UPS output)	1	no.		
c)	6 way SPN MCBDB comprising of 1 No 63 Amp DP Isolator and 4 No SPMCB 10/16 Amp. (UPS output)	0	No		
d)	4 Way TP MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 100 A FP TPN and 6 Nos.32 A DPMCBS etc complete as required. (for Air conditioning only).	1	no.		
e)	4 Way TP MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising with 30mA ELCB 10 Nos. 6/20 Amp SPMCBS etc complete as required. (for Light, Fan)	1	no.		
f)	Raw Power DB: 4 WayTP MCBDB Double Door in recessed wall including cutting of wall and making good the damages comprising 1 no 100 A FP MCB and 12 Nos. 20/25 Amp SPMCBS etc complete as required. (for Raw Power Only)	1	no.		
3	RAW POWER: Supply all material, storing, handling, fixing of Raw power points in suitable size of GI/PVC box including providing 1 nos 15 amps 6 pin modular power sockets to be provided controlled by 1 no 15 A moduler type switch and indicator with moduler cover plate etc complete as required including 2X2.5 sq. mm FRLS copper wire + earth wire in dia 2 mm in thickness ISI Mark PVC pipe. Note: One RAW power points are to be provided on one circuit and directly to be connected on Power DB. (Switches : Make: Anchor/Crabtree/North-West/MK) (Wires Make: Havells/ RR Kable / KEI/Finolex)	6	each		

	NOTE: ONLY ONE RAW POWER POINT TO BE PROVIDED IN THE PANTRY. FOR AQUAGUARD PROVIDE 5AMP PLUG POINT WITH SWITCH.				
4	Providing and fixing, testing and commissioning of Heavy Duty modular air-conditioning plug & socket arrangement:				
a)	25 amp air-conditioning point modular type socket { to be fixed 1.5 foot below false ceiling} with 25 amp DPMCB "C SERIES" {to be fixed at Normal Height}.	6	no.		
5	Providing and fixing of suitable size MS box fabricated with 16 G MS sheet either in recess wall or on surface to accommodate dedicated earth from earth electrode and further distribution of earth to computer points including providing of 5 mm Bakelite on base connector strip and painting of box etc as required.	1	job		
6	Basic electrical Wiring of light points, plug points				
	Wiring for light point/ ceiling fan point/ exhaust fan point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed medium class PVC conduit ISI Mark, with 6Amp modular switch, modular plate, suitable GI junction & switch boxes & clip and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.(Wires Make: Havells/ RR Kable / KEI/Finolex) (Switches : Make: Anchor/Crabtree/North-West/MK)				
	(Rate includes 3 x 2.5 sq.mm FRLS copper conductor, single core cable in PVC conduit for circuit/sub main wiring along with earth wire)				
a)	single 6 Amp Switch controlling 1 light point for T-5, Wall Fans, exhaust Fans,Cove Light, Ceiling fan and other separate room supply only	29	no.		
b)	single 6 Amp Switch controlling 4 no. downlights / 4 no. LED downlight / 2 no. 2'- 0"x 2'-0" 36 watt light fittings	15	no.		
c)	single 6Amp socket controlling by 5Amp Modular switch in switch boards etc complete as required	8	no.		
	Note: Lihgts/fans points to be calculated by numbers of lights and no extra cost shall be paid for dummy switch.)				

PART-II : PANELS , KIT KATS & CABLES					
7	Providing and fixing of 03 no 250 Amps KITKAT with 1 no neutral link on suitable size of Bakelite sheet of thickness not less than 12 mm complete as required	1	job		
8	MAIN SUPPLY: Supply, installation, testing and commissioning of factory fabricated 8 Way vertical TPN distribution board rust inhibited powder coated sheet fabricated comprising of inbuilt copper bus bar with earthlink and wire set for cable management complete as required . Make: Havells/HPL/Standard/ Legrand/L&T				
	INCOMING				
	1 no MCCB Breaking Capacity 10 KA 125 Amp 4P make: Havells/HPL/Standard/ Legrand/L&T				
	OUTGOING				
	8 nos MCB of capacity 63 Amp 3P Havells/HPL/Standard/ Legrand/L&T	1	set		

9	Supply, Installation, testing & commissioning of PVC insulated PVC sheathed armoured cable of 1100 V (IS ;1554 Part 1) and fixing of cable on wall with suitable size of clamps /saddles or laid in floor/recess wall including cutting of wall /floor and making good the damages etc complete as required of following sizes (ISI marked). (Make: Havells/ KEI /Finolex/Pymen/Polycab)				
a)	3.5X50 sq. mm aluminum conductors armoured cable with two Nos. 8 SWG GI wire (For mains & DG Set)	0	mtr.		
b)	3.5X35 sq. mm aluminum conductors armoured cable with two Nos. 8 SWG GI wire	60	mtr.		
c)	4X10 sq. mm aluminum conductors armoured cable with two Nos. 8 SWG GI wire	0	mtr.		
d)	3.5X25 sq. mm aluminum conductors armoured cable with two Nos. 8 SWG GI wire (For Light DB/ Power DB/AC DB)	45	mtr.		
e)	3X6 sq. mm copper conductors armored cable with one Nos. 8 SWG GI wire	15	mtr.		
f)	3X2.5 sq. mm copper conductors armored cable (Metal Clad/Modular AC points to be provided adjacent to the Acs.	90	mtr.		
10	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium/Copper conductor cable of 1.1 kV grade as required.				
a)	3.5X50 sq.mm aluminum conductor	0	no.		
b)	3.5X35 sq.mm aluminum conductor	5	no.		
c)	4X10 sq.mm aluminum conductor	0	no.		
d)	3.5X 25 sq.mm aluminum conductor	6	no.		
e)	3X6 sq. mm Copper cable gland.	2	no.		
f)	3X2.5 sq. mm Copper cable gland.	12	no.		
11	Supplying & fixing the 1 no.4 pole 160 Amps capacity change over switch and complete connection with Electrical Panels as required .Make: Havells/HPL/Standard/ Legrand/L&T	1	no.		
12	Making necessary provisions for keeping the branch in working condition by providing or maintaining temporary electrical ponts for the computers/ac's/lighting etc. as per the direction of the Architect/Engineer-in-charge including the costs of the material, labour and dismantling.	0	Job		
13	UPS DISTRIBUTION BOARD				
	supply, installation, testing and commissioning of factory fabricated distribution board rust inhibited, powder coated sheet fabricated comprising of incoming and outgoing isolator and MCB's neutral link or neutral bus, top and bottom detachable entry earthing bolts interconnection and grouting bolts etc complete as requd. Make: Havells/HPL/Standard/ Legrand/L&T as per details below :-				
a	4 way DB comprising of 2 no. 63 amp DPMCB (UPS out put)	1	each		

b	4 way DB comprising of 1 no. 63 amp 4P MCB - 3 phase (UPS input)	1	each		
	Providing & fixing 16 S.W.G. M.S. Sheet adapter box, and also base frame for installation of M.C.B. D.B.'s plug & socket arrangement and to cover cables in system room including painting etc. complete	1	sqmt.		
14	Supply, fixing and testing of following 3 pin metal clad industrial type plug & socket arrangement with plug top cap & chain controlled by 1 No. MCB				
a)	20/25 amp with 20/25 amp SPMCB{ for Branch UPS output }	4	no.		
b)	32 amp with 32 amp SPMCB { 3 for Branch UPS input }	3	no.		
15	Providing and laying following sizes of PVC insulated copper conductor cable of 1100 V in flexible/ PVC conduit pipe with accessories such as glands bends etc (as per requirement) including making necessary interconnection etc complete as required.				
	2 X 6 Sq mm with 1 no suitable insulated 2.5 sq mm multi stranded copper wire in PVC flexible pipe. (Make: Havells/ RR Kable / KEI/Finolex/Polycab)	25	mtr.		
16	EARTHING				
a)	a)Supply and fix copper plate earth station with 600X600X3mm copper plate and termination of 20 x 3 copper strip with earth station 5m in length below ground level etc. as required, including all accessories such as watering pipe and funnel and providing masonry enclosure at top with cover plate i.e excavation of pit, supplying and filling of salt charcoal, refilling of pit etc complete as required as per IS 3043-1987. The voltage between neutral and earth must be below 1 V.	1	Sets		
b)	b)Supply and fix GI plate earth station with 600X600X6mm GI plate and termination of 20X3 mm G.I strip 5m in length with earth station below ground level etc as required, including all accessories such as watering pipe and funnel and providing masonry enclosure at top with cover plate i.e excavation of pit, supplying and filling of salt charcoal, refilling of pit etc complete as required as per IS 3043-1987.	2	Sets		
17	a)Providing and fixing of 8 SWG copper earth wire in the recess for loop earthing etc. as required.	40	Meter		
	b)Providing and fixing of 8 SWG GI earth wire in the recess for loop earthing etc. as required.	25	Meter		
18	Supply and laying following dia 2 mm in thickness ISI Mark PVC pipe under floor or in recessed walls from earth electrode to UPS room for computer dedicated earthing				
	25 mm diameter	65	Meter		
PART IV - TELEPHONE & DATA CABLE					
19	Wiring for telephone points with 0.6 mm dia 2 pair insulated annealed tinned electrolytic copper conductor in 2 mm thick 25 mm dia ISI marked PVC conduit complete with accessories such as bends, junction boxes etc. with suitable size of G.I./PVC box modular plate and cover in front on surface or in recess including providing and fixing modular type telephone socket outlet and making necessary connections etc. complete as reqd. (Make: Dglink/KEI/Finolex)	5	no.		

20	Supply, installation and testing & commissioning of PVC Tag Block 20 pair for telephone connections	1	no.		
21	Providing , Laying, testing & commissioning of 10 pair telephone cable from outside govt. / bsnl DB to Rack for lease line, ISDN of Make: Delton, finolex, polycab.	0	mtr.		
22	Data cabling work for computer networking starting from mounting rack at system room with UTP CAT-6e LAN Data cable in 2mm thick 25 mm dia ISI mark PVC conduit with accessories such as bends, Tees, junction boxes including providing and fixing cat-6 I/O plates and SMB complete with all networking accessories etc complete as reqd. (Make: D-Link/MOLEX/AMP/COMMScope). Note: Only One Data Points to be provided in One Table/Counter. Extra points not to be paid if provided. Maximum 6 no. data cable must be run in one pvc pipe.	10	no.		
23	supply, installation, testing and commissioning of 24-port Patch Panel	1	no.		
24	Supply and installation, testing and commissioning of mounted rack 15" high made of powder coated MS sheet	1	no.		
25	supply, installation, testing and commissioning of factory manufactured CAT-6e patch cord complete with 2 no. connectors etc. complete as reqd.				
a)	1 mtr. long	10	no.		
b)	2 mtr. long	10	no.		
	<u>PART-V : AIR CONDITIONING REFRIGERATION/DRAIN WORKS</u>				
26	Supplying & Laying of following COPPER REFRIGERANT PIPING Thickness 22 SWG For Air Conditioners units complete with fittings Suction / Discharge line insulated with 12 mm SUPERLON / ARMAFLEX suction line. Multi-runs between Indoor & Outdoor units shall be considered as ONE length for the purpose of measurement. (Make: Total Line/Armacell)				
a)	1/4" + 1/2" Refrigerant Copper piping - For Hiwall Split AC's (1.0Tr / 1.5Tr)	65	mtr.		
b)	5/8" + 3/8" Refrigerant Copper piping – For HWS/Cassette AC (2.0Tr / 3.0Tr)	35	mtr.		
27	Supplying & laying recessed in wall Rigid ISI Mark PVC drain pipe of size 20mm dia complete with fittings, U traps etc. & as specified to the nearest toilet / drain point under floor or in recessed walls for AC drains including cutting of walls, bends & Tees. making good the damages etc. wherever required. (Make: Diplast/Supreme)	40	mtr		
28	Supplying and providing Electrical flexible FRLS Copper cable of 3 x 2.5sq.mm multi strand suitable for 1.0Tr / 1.5 Tr H.W Split / 2.00 Tr Cassette Multi-runs between Indoor & Outdoor units and between Metal Clads to Out door for electrical supply etc complete as required (Make: Havells/ RR Kable / KEI/Finolex)	110	mtr		

29	Supplying and providing Eletrical flexible FRLS Copper cable of 3 x 4.0sq.mm multi strand suitable for 1.0Tr / 1.5 Tr H.W Split / 2.00 Tr Cassette Multi-runs between Indoor & Outdoor units and between Metal Clads to Out door for electrical supply etc complete as required (Make: Havells/ RR Kable / KEI/Finolex)	0	mtr		
30	Dismantling and re-Installation of existing AC's (Cassette/split of any TR capacity) at the locations marked or as per the direction of the engineer-in-charge. The vendor shall ensure proper installation and check for the gas, equipment or any other damage. The Damage shall be rectified or the gas filling shall be done without any extra cost. The AC's should be fully functional.	0	nos.		
	TOTAL OF SUB-HEADS I-V (A)				
	PART-VI : LIGHTS & FANS FIXTURES				
31	SITC of 2"x 2" Ceiling grid 33-36 watt LED panel fixtures with essential driver in false ceiling including making necessary arrangement for mounting the fixtures and connection with 2 x 1.5 sq.mm insulated copper cable from adjacent point in PVC flexible pipe etc Complete as reqd. Make BAJAJ cat. BZRSQ 43L LED GF or equivalent of Wipro / Bajaj.	17	no.		
32	SITC of 15 watt LED fixtures /dowlighters with essential driver in false ceiling including making necessary arrangement for mounting the fixtures and connection with 2 x 1.5 sq.mm insulated copper cable from adjacent point in PVC flexible pipe etc complete as reqd. Make BAJAJ cat no. 112676 BPSLR 15W WH or equivalent of Wipro / Phillips.	26	no.		
33	SITC of 18 watt of T5 LED fixtures directly on ceiling / wall including making necessary connections with 2x1.5 sq.mm insulated copper cable conductor wire etc. complete as reqd Make Phillips / Wipro / Bajaj.	13	no.		
34	SITC of 400/450 mm Metal sweep wall fan Crompton/Orient/Khaitan/Bajaj with 2/3 pin plug complete as required.	6	no.		
35	LED Strip light (4.5/5 watt) for cove (M/s Phillips /Wipro / Bajaj Complete in all respects with suitable drivers	40	MTR.		
36	SITC of 1200 mm CEILING fans with Brush less Direct Current motor complete as reqd. 1200mm BLDC Fan Make: Atomberg/Crompton/Orient)	1	no.		
37	SITC of 225 mm metal body exhaust fans complete with including necessary frame etc, complete as reqd. (M/s Crompton High Breeze or equivalent of USHA / Bajaj)	4	no.		
38	SITC of 30 watt LED Street light /Flood light for lighting the front side of the branch (M/s Crompton Cat No. LSTS-30-CDL or equivalent of Philips/Wipro .	0	no.		
39	SITC of Automatic Programmable Time Switch 24 Hour for Glow sign board ATM AC's (Make: L&T or equivalent to Legrand/Havells/Seimens)	1	no.		

40	Supply, erection, testing and commissioning of 1.5TR 3star HOT AND COLD TYPE Wall Mounted AC units with cordless remote complete with all necessary wiring duly insulated with 9mm thickness Nitrite rubber pipe insulation with (evaporate coil-copper only_ fan and fan motor, machine control panel improved refrigerant joints. Air conditioners shall be fitted with hermetically sealed type suction reciprocating or discharge cooled rotary compressor or scroll compressor, compressor unit operating on R32. All complete as per drawing and Instructions of the Engineer in-charge/employer (rates are to be inclusive of copper refrigerant pipe and supply cable with insulation and drain pipe up to 3mtr. length & powder coated MS Stand) Copper only (Make : Hitachi/Daikin/Carrier/Voltas/Blue Star).	4	no.		
	Supply, erection, testing and commissioning of 2.0 TR 3star HOT AND COLD TYPE Wall Mounted AC units with cordless remote complete with all necessary wiring duly insulated with 9mm thickness Nitrite rubber pipe insulation with (evaporate coil-copper only_ fan and fan motor, machine control panel improved refrigerant joints. Air conditioners shall be fitted with hermetically sealed type suction reciprocating or discharge cooled rotary compressor or scroll compressor, compressor unit operating on R32. All complete as per drawing and Instructions of the Engineer in-charge/employer (rates are to be inclusive of copper refrigerant pipe and supply cable with insulation and drain pipe up to 3mtr. length & powder coated MS Stand) Copper only (Make : Hitachi/Daikin/Carrier/Voltas/Blue Star).	2	no.		
41	S.I.T.C. of L shape / suitable shape M.S. Frame stand for mounting Outdoor Units on wall / On floor with all fixing hardwares. Within above Catwalk for cassette & split A.c.'s.	6	no.		
42	Providing and fixing 4KVA Stabilizer (copper winding) input voltage range of 170-270V and output to be 230V Make : Blue Bird/Logic state/ Everest/V-guard	6	no.		
43	SITC of ceiling mountable PIR sensor with detection of radial- dia 3m. Tangential- 6m angle 360 degree. Make: Wipro/Schnider	1	no.		
	TOTAL OF SUB- HEAD VI (B)				
	TOTAL OF PART : (A)				
	TOTAL OF PART : (B)				
	TOTAL AMOUNT (A+B)				
	Note: GST as aplicable shall be extra				