

	PROJECT STATE BANK OF INDIA, SOMATNEPHATA BRANCH,				
	INTERIOR WORK New Branch				
Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
Note :	Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris ,cleaning cutting wastage etc. all taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills. Contractor shall get all materials approved from Architect/ Bank before use it on site from approved make list also Contractor shall not use any material beyond approved make list. Contractor shall read all specifications carefully before quoting the rates and understand the scope of work. In case any discrepancy / interpretation Bank's decision will be final and binding to the contractor.				
	The premises has got double height in the major branch portion. The bidder has to consider this point while quoting. No additional amount will be payable for height purpose.				
[A]	FURNISHING WORK				
1	SINGLE WINDOW COUNTER AND CASH COUNTER SIZE 5'-0" X 2'-9"	RMT	7.0		
	Supplying, fixing and keeping in position single window counter complete as per design, and drawing made out of 18mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.				
	The cost shall be inclusive of S & F of a drawer and shelf unit with 18mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following.				
[a]	size :				
	Description: L B Ht.				
	Writing Top 5'-0" 2'-9" 2'-6"				
	Transaction Top 5'-0" 2'-6"				
	4 Drawers with				
	pegion hole 2'-0" 1'-3" 2'-0"				
	Computer key Board				
	Supplying and fixing metal key Board of approved make in counter as per design and instructions.				
[b]	Working table top and edges shall be finished with 6mm thick white corian of approved make, as per drawing and direction with all labour and materials all edges should be finished with corian				
[c]	Transaction Top : 2x6 mm thick flexy ply wood round shape with 6mm thick white corian shall be provided at front as per design, all edges should be finished with corian				

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
[d]	Front pannel (Front Apron) shall be finished with 6mm thick 18" high, glass blue lacquered glass of approved make and fixed on 18mm thick commercial ply wood with Natural Silicon gum as per manufacturers specification of approved make All complete as per drawing				
[e]	Foot rest of 3' x 1.5" in C.P. Teak wood. and CPU stand 16" x 24"				
[f]	All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
[g]	All fittings like S.S. handle/ approved make Auto Lock to each drawer and cabinet doors, piano hinges, ball catcher stopper, metal cable manager etc. approved make heavy duty full extension channel in drawers.				
[h]	Heavy duty telescope full extension sliding channel of approved make shall be used in all drawers.				
[i]	All the surface without lamination shall be Synthetic enamel paint/polishing of approved shade etc complte				
[j]	Counter shall be made independent in Length of 5'-0" and properly placed between two partition.Counter measured between two partition and paid				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 6mm thick white corian				
	2) Front Appron: Round corian and 6 mm thick lacquered blue glass fixed with Natural Silicon				
	3) Facing of Drawers: 1.00 mm thick laminate finish				

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
2	Providing and fixing 12 mm thick Toughened Glass partition on counter front side top as follows	SQMT	4.2		
	Location - SWO front side fixed partition				
	Providing and fixing 12 mm thick Toughened float glass with polished edges shall be fixed with necessary S.S Brush finish brackets support on wooden partition as directed. Making necessary cut out in glass all edges of glass shall be Diamond cut polished edges as directed complete.				
	the item shall include the following items				
a	Providing and fixing 12mm thick Toughened float Glass partition between Single Window counter partition front side as follows. (Round glass partition in between SWO partition)				
	Location- In between Single Window Counter towards public space round glass partition)				
	12 mm thick Toughened clear float glass with polished edges shall be fixed with silicon and T.W beading support on wooden partition as directed. All edges of glass shall be Diamond cut polished edges as directed complete. (Glass for Measurement outer longer width and height shall be measured and paid)				
3	Side Credenza For S.W Counter and other tables Size 3'-0"x1'-4" x 2'-6" ht. With openable shutter Side Table top and edges shall be finished with 1 mmThick laminate on all visible	SQMT	2.25		
	Supplying and providing side cabinet for keeping computer and printer size 1'-4" width 2'-6" height and 3'-0" length. Openable shutters as directed. Cabinet shall be made from 18mm thick commercial ply wood &. Back shall be made from 6mm th commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with 1.0mm th laminate and approved group lock, handle, hinges, magnet catch. Edges to be finished with teak wood lipping etc. including all internal surface to be polished/ Synthetic enamel paint etc.				
	As per drawing and instruction of Architect/Bank Complete				
	TABLES				
4	MANAGER TABLE SIZE: 6'-0" X 2'-9" X2'-6" HT..with Teak veneer with matt french coating finish on Table Top ,sides & Edges and all other visible surfaces etc complete as follows	NO	1		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Supplying and providing Table as per the following description Size 6'-0" x 2'-9". Table top shall be made from 18mm thick commercial ply wood with 3.50 mm thick Teak veneer with matt french Coating (Basic rate Rs.90=00 per Sft without GST) with necessary intermediates support. Table top shall be supported by 18mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-3" x 2'-0" x 2'-6" shall be provided using 18mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock / S.S. Handle. Commatt french ter Key board of metal of approved make shall be provided. Exposed surfaces of the cabinate shall have Teak veneer with matt french polish . Foot rest of 1 1/2" x 3" T.W members shall be provided. All the surface without veneer shall be polished/painting.				
	Apron (Modesty Panel) made from 18mm thick ply wood with teak veneer matt french Finish & groove pattern as per drawing				
	Table side made from 18mm thick ply wood with 3.50 mm thick teak veneer with matt french coating finish shall be provided in a pattern as per drawing directed. Veneer to be provided only on visible surface				
	Table shall have stand for keeping CPU and metallic cable Manager shall be provided in table top. All exposed edges of plywood shall have veneer with smooth edges & corners				
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required				
	All the surface without teak veneer shall be synthetic enamel paint /polished of approved shade				
	As per drawing and instruction of Architect/Bank Complete				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : Teak Veneer with matt french Coating & Burma Teak beading on Edges with				
	2) Front Apron & Sides: Teak Veneer with matt french Coating				
	3) Facing of Drawers: Teak Veneer with matt french Coating				
5	SIDE CREDENZA (SIDE TABLE)				
	Supplying and providing storage cabinate with Teak Veneer with matt french Coating on Top, Front Shutter & 35 mmx6mm thick Burma Teak beading on Edges with matt french Coating. Veneer to be provided only on visible surfaces (BM cabin side credenza)	SQ.MT	1.00		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Size : Depth 1'-4", 2'-6" ht. having openable shutter as directed. storage Cabinet shall be made from 18mm thick commercial ply wood for Top with Teak veneer with matt french Coating finish and 18mm thick ply wood for verticle, shelves, shutters and 6mm commercial plywood for backing. 3.5 mm thick Teak Veneer (Basic rate Rs.90=00 per Sft without GST) with matt french coating on all exposed surface. with verticle (at 3'-0" c/c) shelves at 1'-3" c/c Openable shutters in 18mm thick commercial ply wood with all S.S hinges, towers bolts, powder coated handle, ball catches, S.S approved make (group lock) multi matt french rpose lock complte. Edges to be finished with teak wood				
	All the surface without lamination shall have 0.8MM white laminate				
	Front surface area shall be measured for payment purpose.				
5	OFFICER TABLE FOR SERVICE MANAGER AND OTHER TABLE				
6	Same as above Item No 5 but size 5'-0" x 2'-6" with storage unit 4 Nos Drawer in table Finishing as follows	NO	2		
	Table Top finished with 1 mm thick				
	Apron (Modesty Panel) made from 18mm thick ply wood with 1 mm thick frosty white laminate of approved make shall be provided in a pattern as per drawing /directed.				
	Table side made from 18mm thick ply wood with 1mm thick frosty white laminate shall be provided in a pattern as per drawing/ directed.				
	All the surface without lamination shall have 0.8MM white laminate				
	As per drawing and instruction of Architect/Bank Complete				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 1.0 mm thick laminate finish & Burma Teak beading on Edges				
	2) Front Apron & Sides: Frosty white Laminate				
	3) Facing of Drawers: 1.0 mm thick Laminate Finish				
	ground floor				
	mezz floor				
6	SIDE CREDENZA (SIDE TABLE) for Sales officer and Service Manager and Other Officer	SQ.MT	1.5		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Same as above Item No 4 but 1.0mm thk external laminate and 0.8mm thk internal laminate with T.W Edges finished in white enamel paint. Other surfaces finished with laminate finished Size shall be 3'-0"/3'-3" x 1'-4" x 2'-6" ht. with openable shutters as directed.				
	As per drawing and instruction of Architect/Bank Complete				
8	REAR STORAGE IN MANAGER CABIN				
	Low height storage in BM cabin with Openable shutter with 3.50 mm thick Teak veneer with matt french Coating finish on Top, front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges with matt french Coating. Veneer to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment matt french rpose. (BM cabin back storage)	SQMT	1.9		
	Supplying and installation side cabinet for keeping commatt french ter and printer of size 1'-4" width 2'-6" height and 3'-6" length or as per existing storage dimensions having openable shutters as directed. Entire cabinet shall be made from 18 mm thick commercial ply wood including shelve with 3.50 mm thick veneer (Basic rate Rs.90=00 per Sft without GST) with matt french Finish on outer visible surfaces .Only back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with veneer finished and approved make group lock, handle, hinges, magnet catch, Rate				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply				
	All the surface without lamination shall have 0.8MM white laminate				
9	Same as above item No 8 but Supplying and providing storage cabinet with 1 mm thk laminate on all visible surfaces as directed & 35 mmx6mm thick Burma Teak beading on Edges with polishing etc complete. Laminate to be provided only on front,side visible surfaces	SQMT	3.3		
10	P/F ELECTRIC CUB BOARD	SQMT	2.5		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Providing and fixing Electric cup board using aluminium framing of 50x50x1.20 mm thick with 8 mm thick Bison board on both side for vertical sides, top, bottom partition and door shutter with 1.0 mm thick laminate on all exposed surface and synthetic enamel paint on all internal surface including shelves. 18 mm thick Bison board for inside verticle and horizontal divisions. Shutter will have Teak wood beading along periphery duly malamine polished and approved make lock, 200 mm handle, S.S. hinges, ball catches & 4 Nos. S.S perforated jali (12' x 6') etc. complete as directed. Depth of cup board will be around 380 MM (1'-3"). Height of shutter will be maximum 2135 MM (7'-0"). Only front elevation shall be measured for payment purpose.				
11	P/F PANTRY PLATFORM CUB BOARD	SQMT	1.4		
	Providing and fixing cupboard shutters below pantry platform using 38 x 63 MM (1 1/2" x 2 1/2") second grade T.W members for frame, 18 mm commercial plywood with 1.0 mm laminate for shutters and synthetic enamel painted on internal surfaces. Providing 18 X 6 mm th T.W beading all around shutter. Providing S S perforated jali (8" x 4") , 75 mm long S.S hinges, 100 mm long S.S Handles, stoppers and magnetic catch as directed. All non laminate surface shall be polished/ synthetic enamel paint as directed.				
12	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR S.W COUNTER AND CASH CABIN	SQMT	14.5		
	Location- SWO partition				
	Providing and fixing low height partition using 50mm x50mm x 1.20mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 6 mm thick commercial ply of approved brand on both side of aluminium skeleton and fixing 1.0 mm thick laminate of approved shed on both sides. Fixing 1.0 laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12 mm transparent toughened glass as directed. Applying polish on exposed steam beach members with lacquer				
	For Low height Single window and Cash cabin partition, Average height of partition shall be measured and paid.				
13	PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE	SQMT	2		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Providing & fixing wicket gate with 50 X 50 X 1.2 mm thick aluminum section and covered with 6 mm thick commercial ply both sides with 1 mm thick laminate with beading including 75 mm long SS hinges with countersunk SS screws, approved make Night latch, 75 mm long S.S Handles, Door stoppers, 150 mm long S S tower bolt of approved				
	Night Latch- Europa 8010 NS / Doorset - NL 180 S/S. / Godrej - 8812				
14	P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION	SQMT	#REF!		
	Location- other than SWO partition				
	Providing and fixing low height partition using 50mm x50 mm x 1.2 mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 6 mm thick commercial ply of approved brand on both side of aluminium skeleton and fixing 1.0 mm thick laminate of approved shed on both sides. Fixing 1.0 laminate in a shape as directed shall be fixed on all exposed edges. Fixing 12mm th free clear float glass as directed. Applying polish on exposed steam beach members with lacquer				
	Between tables				

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
15	P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION (BOTH SIDE LAMINATE PARTITION)	SQMT	31		
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 50mm x 1.20 mm thick Aluminium members in a maximum grid of 610 x 610 mm (2'-0" x 2'-0") fixing with 8 mm thick commercial ply with 1.00 mm thk laminate approved make on both sides shall be fixed on plywood, partition shall be well supported up to slab / beam. Providing and fixing 10 mm thick float glass as directed in the partition. Providing and fixing door shutter using 35.5 mm thick flush shutter with both side laminate and fixing 10 mm thick glass with beading patti, 100 mm long 4 Nos stainless steel hinges, doorstopper shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.				
	For purpose of payment, partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab / beam bottom.				
16	SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR (INNER SIDE 3.5 mm THICK TEAK VENEER WITH matt french COATING AND OTHER SIDE LAMINATE FOR MANAGER CABIN)	SQMT	32		
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 50mm x 1.20 mm thick Aluminium members in a maximum grid of 610 x 610 mm (2'-0" x 2'-0") fixing with 8 mm thick commercial ply with 3.5 mm thk teak venner with matt french coating on inner side and 1.00 mm thk laminate approved make on other side shall be fixed on plywood, partition shall be well supported up to slab / beam. Providing and fixing 10 mm thick float glass as directed in the partition. Providing and fixing door shutter using 35.5 mm thick flush shutter with one side veneer and one side laminate and fixing 10 mm thick glass with beading patti, 100 mm long 4 Nos stainless steel hinges, doorstopper shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall				
	For purpose of payment, partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab / beam bottom.				
	Provide Detailed measurement				

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
17	Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows.	SQMT	7		
	Providing and fixing 102x51 mm (4"x2") steam beach member for frame and Flush door shutter made out of 32 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 32x 12 mm thick TW / steam beach periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 4 Nos 100 mm long SS hinges with countersunk SS screws, Approved make Ded Lock, 300 mm S.S Handles, Door stoppers of approved make etc. all exposed surface /edges not laminated				
	GLASS DOORS AND PARTITIONS				
18	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Main Entrance Door For Branch and E-Lobby	SQMT	9		
	Location: & BM Cabin				
	Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings . The door will have patch lock, pti pivot, 120 kg floor spring & 400 mm long handles both sides, (Approved Make) , fixed with the glass by making necessary cutouts & holes. The glass edges shall be polish on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.				
	The patch fittings (Approved make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door, complete in all respect should be installed in positions as req.				
19	P & F FULLY GLAZED PARTITION With Patch Fitting for front side Main Entrance [FIXED PORTION WITHOUT DOOR] For Branch and E-Lobby with SS finish support as required. Height = 4.5m	SQMT	19		
20	P/F Wall panelling with laminate finishing for wall and Pillar etc	SQMT	89		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Providing and laying panelling on walls & pillars having 12 mm thick IS 303 PLY and 1.0mm th laminate fixed on wall & pillars with Aluminium. framing of 50mmx50mmx1.20mm thick at maximum 610MM (2'-0") c/c bothways on wall and pillar etc complete as directed. Entire work to be completed as per design and instruction of Architect.				
21	Same as above item no.28 but Providing & Fixing Wall panelling with Veneer matt french coating paint finishing for wall etc in Manager Cabin instead of laminate finish	SQMT	16		
22	Panelling for Display wall with 3M Vinyl Films with printed design and lamination finishing	SQMT	3		
	Providing and laying panelling on wall having 8 mm th MDF Board exterior grade with 3M vinyl films with printed design and lamination fixed on wall with Aluminium framing of 50mmx25mmx1.20mm thick at maximum 610MM (2'-0") c/c bothways etc. complete as directed. panelling as per design and instruction of Architect. Only Finished visible surface area shall be measured for payment (MDF board with 0.60				
	Exposed edges of Display wall four side shall be made 36 mm thick by providing additional required thickness MDF patta of required width.				
23	Panelling for 8MM THK BACK PAINTED GLASS	SQMT	15		
	Providing and laying panelling on wall with Aluminium framing of 50 mm x 25mm x 1.20 mm thick at maximum 610 MM (2'-0") c/c bothways. covers with 8mm th MDF Board exterior grade with 8MM THK BACK PAINTED GLASS OF APPROVED SHADE AND COLOUR.etc complete as directed by Architect/Engineer. Only finished visible surface area shall be measured for payment.				
	BEHIND STAFF				
24	SOFT BOARD	SQMT	8		
	Providing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6mm thick commercial plywood on back side and 12mm th soft board on front. Fixing cloth of selected design of Basic rate of Rs. 150 per mt.steam beach member shall have lacquer polish as directed complete.				

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
25	CUSTOMER WRITING DESK	NO	1		
	Writing Desk Size 3'-0" L x 1'-3" x (0'-6"+3'-0") ht.				
	Verticle Sides and bottom shall be made out of 36 mm (2X18) thick Commercial plywood and back side 12 mm thick ply wood with Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12mm th Toughend glass with polished edges making different divisions by 18 mm thick glass / plywwod with laminate on both side for slips or forms as per detail drawing and inststruction complete. Laminate to be provided on all visible surface				
26	Supplying and fixing Roller Blind Blackout /screen of approved make with selected fabric of approved design and shed. Selection of fabric shall be as per instruction by Architect/Engineer. (Basic Price of Rs 135=00 Per Sq.Ft excluding GST)	SQMT	7		
27	Providing and Fixing Frosted polyster film of 3M (Scotchcal 7725 - 324) or equivalent make over glass surfaces as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification.	SQMT	11		
28	ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION for BRANCH AND ATM ROOM IN SIDE WALL AND OUT SIDE	SQMT	65		
	Providing and fixing 3 mm thick aluminium composite panel with 0.25 mm foil with 50 mm x 50 mm x 1.50 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon compound seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standared Drawing and Architect's instructions etc complete.				
	FALSE CEILING WORK				
29	P/F GYPSUM BOARD FALSE CEILLING	SMT	118		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Necessary cut outs to be provided, finishing the surface and applying 3 coats of Plastic emulsion paint with birla putty, primer etc complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India / USG Boral. Visible surface area horizontal and vertical will be measured in Sq Mtr for payment purpose.				
	Saint Gobin:- 12.5 mm thick Gypboard plain & Gypultra ceiling section as per following brief details:- (i). 20X30X27mm perimeter chanel fixed with screws at 610mm center to center. (ii). 15X15X45mm intermediate chanel 1220mm center to center supended with 25X1mm ceiling angle at 600mm center to center. (iii). 51.5X26X10.5mm ceiling section at 457mm center to center. (iv). Board fixed over ceiling section with 25 mm drywall screws at 230mm center to center (staggered joint). Finished with Gyproc jointing compound, Gyproc joint paper tape & 2 coats of dry wall top coat. Work to be completed using all accessories, suspension system as per detailed specifications & manufacturer's recommendations/ datasheet. Work to be get inspected by company representative & quality performance certificate to be obtained				
	After completion of work to certificate from manufacture as specified above shall be submitted along with bill stating that work is satisfactorily completed as per their specification				
	Note : (1) Rate includes making necessary cutouts for lighting fixtures (2) Pattas of Less than 1'-0" shall be measured in Sqft and not in Rft and paid in Sqft. (3) Only finished visible surface area shall be measured for payment.				
30	Providing and Fixing of Armstrong Mineral Fibre Acoustical Suspended ceiling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid	SMT	77.00		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Providing & Fixing Mineral Fibre False Ceiling (Acoustical Suspended Ceiling System). Work to be completed using all accessories, suspension system as per detailed specifications & manufacturer's recommendations / datasheet. Necessary cut-outs shall be provided wherever required. Visible area shall be measured in sq mtr only. Quality / performance certificate from Company /Authorised dealer shall be obtained & submitted. Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose				
	ARMSTRONG:- 600X600X16MM Dune (Microlook) BE tiles fixed over Armstrong - SILHOUETTE XL 15mm mid range (6mm Black Reveal) Grid System. Main Runners spaced at 1200mm center to center, 1200mm long cross TEE interlocked between main runners at 600mm center to center and 600mm long cut cross TEEs at 1200mm center to center. 3000X19X19mm ARMSTRONG wall angle screwd to wall with screws at 450mm center to center. Armstrong Suspension system consisting of M6 Anchor Fastners, 26X26X25X1.2mm vertical hanger, 4 mm thk GI Hanger wire with adjustable hook clips to be provided maximum 1200 center to center both way (Butterfly suspensor).				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				
31	FIRE DOOR	NOS	1		

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Providing and fixing of Hollow metal fire rated doors as per IS 3614 part-1 & part-2 for stability and integrity. Pressed Galvanized steel confirming to IS 277 with the following specification. Recommended fire door shall have doors tested at CBRI or ARAI for maximum rating of 2hrs with vision panel. Test certificates should be available for vision lites /panels as part of the fire door assembly. Independent glass test certificates will not be accepted. Manufacturer test certificate shall cover doors both single and double leaf and all doors supplied should be within the tested specimen, deviation in specification and sheet thickness other than what is mentioned in the test certificates are not allowed. Proper label confirming the type of door and the hourly rating is mandatory. Approved manufacturer Shakti Hormann or approved equivalent.				
	Door frame shall be double rebate profile of size 143 x 57 mm made out of 1.60mm (16gauge) minimum thick galvanized steel sheet. Frames shall be Mitered and field assembled with self tabs. All provision should be mortised, drilled and tapped for receiving appropriate hardware. Rubber door silencers should be provided on the striking jamb. Frames should be provided with back plate bracket and anchor fasteners for installation on a finished plastered masonry wall opening. Once frame installed should be grouted with cement & sand slurry necessary for fire doors on the clear masonry opening.				

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Door leaf shall be 46mm thick fully flush double skin door with or without vision lite. Door leaf shall be manufactured from 1.2mm (18guage) minimum thick galvanised steel sheet. The internal construction of the door should be rigid reinforcement pads for receiving appropriate hardware. The infill material shall be resin bonded honeycomb core. All doors shall be factory prepped for receiving appropriate hardware and provided with necessary reinforcement for hinges, locks, and door closers. The edges should be interlocked with a bending radius of 1.4mm. For pair of doors astragals has to be provided on the meeting stile for both active and inactive leaf. Vision lite wherever applicable should be provided as per manufacturers recommendation with a beeding and screws from inside. The glass should be 6mm clear borosilicate fire rated glass of relavant rating of the door.				
	All doors and frames shall be finished with polyurethane aliphatic grade paint of approved colour. The door leaf and frame shall have passed minimum 250 hours of salt spray test.				
	Rate should include supply and installation of door and hardware set as mentioned in the door and hardware schedule.				
	2Hrs Fire Rated Door leaf of size as mentioned With vision panel with hardware set for each leaf as follows:				
	Ball bearing butt hinge 4" x 3" x3 mm in SSS				
	Mortice sash lock 50mm BS, 20mm sq for end strip, SSS 1"				
	6 pin EP cyl. L=70mm both side keys in SNP (1 each)				
	Tubular lever handle with roses and esc. SSS (1 each)				
	Door closer spring size 3 with standard arm, CE marked				

STAMP and SIGNATURE of Contractor

Sr. No.	Description	UNIT	Quantity	Rate	AMOUNT
	Concealed flush bolt body with rod, Length - 265mm , Vision panel of 6mm thick borosilicate Fire Rated clear glass of size 200mm (W) x 300mm (H), Self adhesive side roll (Ceramic Tape) as required				
32	Acrylic Emulsion Paint (only in branch front area touch up only)	sq.m	120		
	Preparing earlier treated surface by scraping, rubbing with sand paper, applying two coats of Birla white putty wherever required, to level the surface, and its rubbing with sand paper, to ensure smooth surface, suitable to receive paint and then applying 2 or more coats of approved colour and shade of Acrylic Emulsion Paint with low VOC content over a coat of approved primer complete as per manufacturers' specifications to internal walls/ceiling including necessary scaffolding etc. complete. Make:- Asian / Berger/ICI or approved equivalent make.				
	Grand Total				
	[GST as applicable will be paid as applicable]				

STAMP and SIGNATURE of Contractor