

**FINANCIAL BID OF INTERIOR /FURNITURE /CIVIL WORKS FOR
SBI SHAHPUR BRANCH, RBO 4 KHANDWA (M.P)**

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Part A (Interior Works)				
1	FALSE CEILING				
	Note : i) Rate to be included for all kinds of profiles and cut outs required for light fixtures, Speakers, Smoke detector, trap doors and AC grill in the ceiling. Provision for light fittings, AC grills and diffusers have to be made at no extra cost supported with tees, Angles, etc. suitably fixed all complete as per drawing and direction. The area of these cutouts which is less than 0.5 sqmt for one unit will not be deducted while measuring the ceiling area. ii) The contractor must co-ordinate with electrical & AC contractor for working out various levels for the false ceiling & make the marking on the walls / columns before starting the false ceiling work. (The test certificate from the manufacture for all theplywood/board/laminate/mica shall be subbmitted at the time of dilivery at the site address needs to be included)				
1.1	Mineral Fibre Grid Tile Ceiling :				
	Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanized Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T - section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include all fittings and materials complete ... contd...	Sqm	77.91		
	...contd... including proper installation and provisioning etc. The work is to be completed as per manufacturer's specification. (Make: Armstrong / Diamond / USG Boral)				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1.2	Gypsum Board False Ceiling :				
	Providing, making and fixing Gypsum Board False Ceiling straight or curve any profile of reputed make which includes G.I. Perimeter Channels of size 0.55mm thick (having One Flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall / partition with the help of Nylon sleeves and screws at 610mm centres. Then suspending G.I. intermediate channels of size 45mm (0.9 mm thick with two flanges of 15mm each) from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick fixed to soffit with G.I. cleat and steel expansion fasteners. Ceiling section of 0.55mm thick having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457 mm centres. The grid should be laid on Armstrong/Gyproc stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 12.5mm tapered edge Gypsum board (conforming to IS 2095-1982) is then screw fixed to ceiling section with 25mm dry wall screws at ... contd..	Sqm	34.76		
	... contd... 230mm centres. Screw fixing is done mechanically with drilling machine with suitable attachment. Finally tapered edges of the Gypsum boards are to be jointed and finished so as to have a flush look which includes filling and finishing with jointing compound, joint paper/fibre tape and two coats of dry wall top coat suitable for Gypsum board etc. complete as per the recommended practices / specifications of the manufacturer. Including two coats of primer suitable for gypsum board two or more coats of plastic emulsion paint of approved shade and also including making necessary openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitable fixed all complete as per drawing and specification and direction. Rate to be inclusive of shadow profile at the junction of wall & ceiling, in between of ceiling, etc. complete. (Make: Gyproc/ Saint Gobain / Gold Bond)				
1.3	<u>Cove in ceiling</u>	Rm	67.20		
	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
2	PARTITION				
	Rate to be included of all kinds of planes/levels, profiles and cut outs, etc. required for light fixtures, trap doors and ACs, boards, provision for light fittings and diffusers have to be made at no extra cost supported with metallic section etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC Works for cabling, AC pipe works etc.(Make: Archid / Century Green ply)(The test certificate from the manufacture for all theplywood/board/laminate/mica shall be subbmited at the time of dilivery at the site address needs to be included)				
2.1	FULL HEIGHT PARTITION :(As per Bank's specification) Providing, fabrication and fixing of flush type partition made of sal wood framework, 9 mm thk plywood and 5.5 mm thick plane glass. The horizontal and vertical section (2"x2.5" of kassi wood must be framed to from a mesh of 2'0"x2'0" c/c and 9 mm thick plywood to be fixed on both sides of the framed grid. The glass must be held in position properly in line and level. The exposed surface of ply must be covered with 1.0 mm thick laminate of approved brand and shade of Sunmica or equivelent.	Sqm	9.10		
2.2	Low Height partitions With/Without Glass :	Sqm	9.91		
(a)	P/F low ht. double skin glazed wooden partition approx. 1200 mm to 1450mm. High including float glass, with following specifications:				
(b)	Providing and fixing low height partly glazed double skin partitions made out of Frame work to be 50mm X 50mm X 1.60 mm thick aluminum section weight not less than 0.836 kg/rmt with maximum distance of 450mm c/c both ways(Horizontal/Vertical) or as directed, firmly fixed to floor or slab with 65 to 75 mm long screw or as directed by the Bank's Engineer as per site conditions with necessary grooves and cuts etc. including anti-termite treatment to all wooden members wherever used. The partition to be sandwiched with 8.00 mm thick exterior grade HDHMR board from both the sides and finished with 1.0mm thick approved shades and make (Make: Formica / Sunmica / Archid) of laminated finish & match the panelling pattern. The borders/edges to be laminated finish. The cost shall include all labor, materials, strictly as per the given design & drawing etc. in complete. One additional section 50 x 50 mm shall be placed at 700 mm level from floor to fix the table. Additional wooden members to be provided wherever door is to be provided. Wood shall be treated with antitermite chemicals				
©	P & F 12 mm thick (approx.) etched glass (film etching to be paid separately) as per design and shape fixed with stainless steel glass fixing brackets/crews etc. of length varying from 750 to 1550 mm and height appx. 300 - 400 mm. etc. complete as directed.				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
(d)	P & F wicket gate wherever required with required SS hinges, SS tower bolts, automatic surface mounted spring door closer, Godrej Night latch, etc. Rubber wood capping made out of sect. 65 x 15 mm fixed at edges incl. natural polish / painting etc. complete as directed.	No	0.53		
(e)	Glass Film : Providing & Fixing Birla 3M /Lunar make frosted film fixed on the float glass after cleaning and wiping glass surfaces free of any dust or foreign bodies and then fixed plain approved pattern / design film on the glass as per detail drawing inclusive of making necessary cutouts, carting away unserviceable materials out of compound, cleaning the site etc. complete as per the site requirements and the instructions of the Architect. (Basic Cost Of Film not less then Rs.430/- Per smt) . (Measurement area = Length X Height).	Sqm	3.72		
2.3	12mm toughned glass work (as required)	Sqm	6.20		
	Providing & Fixing 12mm thk. Toughned Glass Panels with SS glass connectors of 304 Grade, fixed in position, with etching / filming, as per interior details/instruction of the Achitect/SBI Engineer				
2.4	12mm Glass work	sqm	3.37		
	Providing, making and fixing in position 12mm thick clear float glass in the front side, vertically of height 400 mm and to place & fix another float glass of 12 mm thickness with round edged to be placed horizontally (of width 400 mm) above the vertical glass of length, equal to the length of the counter.				
	Above this horizontal glass, a glass of 12 mm thickness of approx. 300 mm height will be placed vertifcally above the horizontal glass. The top glass to have a arch type, semi circular opening of dia 150 mm. All the edges of the glass to be polished for a smooth finish and the glass is to be embedded in half partitions and fixed with " D " brackets/SS fittings. Etching of glass with film to be done as directed (measured separately). The cost to include all materials, labour, hardware etc., for a neat finished job as per drawings and directions etc., complete.(Make : Modi float, Triveni Float , Saint Gobian)				
	Providing, making and fixing 10mm thick clear float glass of reputed brands like Modi, Saint Gobain or equivalent as approved as glazing, glass shutters in displays, table tops etc. & of size as instructed, edge polished. Glass to be fixed from top and bottom in ply partitions or all four sides inside partitions or shutters with beadings, SS fittings, etc. complete.	Sqm	8.55		
2.5	MAIN ENTRANCE DOOR WITH 12.0MM TOUGHNED GLASS & Patch Fittings	Sqm	2.92		

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.(Make : Modi float, Triveni Float , Saint Gobian)				
2.6	Partly Glazed Door : (Partly Glazed Door on Floor Spring)	Sqm	7.56		
	Providing, making & Fixing of partly Glass door at site, door shall be of 32 mm thk flush door with 1 mm lamination on both sides and central portion to have 8 mm plain float glass, to be fixed to existing partition with heavy duty 4" hinges and shall have cylindrical lock.To be provided with necessary lipping, beading, etc. The cost shall also include providing and applying paint/polish on all surfaces including lippings etc. wherever instructed of approved shade and finish including thorough cleaning, rubbing and surface preparation, application of primer, sealers, etc. as required. The door shall be fixed, provisioning of locking system, with 2 Nos. of 450 mm S.S. brush finish handles (H type), providing "PUSH" * "PULL" sticker labels of approved design & make, outside Aldrop, its fittings and fixtures, etc. complete all of approved make. The rate to include all materials, labour, transport, taxes, delivered and placed in position at site of work.(Make : Modi float, Triveni Float , Saint Gobian)				
.					

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
3	PANELLING ON WALL	Sqm	30.0		
	Providing and fixing panelling on walls front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises as required with framework of 50 mm X 25 mm - 18 gauge section un anodised Aluminium (as per requirement) frame work @ 16" to 24" c/c for levelling and 10 mm thick prelaminated pre laminated HDHMR board board ply of approved ISI grade, and/or limited use o f 6mm Flexible ply for panelling of circular columns etc. including fixing as per pattern and style as directed, with covered with 8 mm thick fixed vertically and horizontally 600 mm c/c or less as per site condition and 6 mm thick HD MR plywood shall be fixed over the frame (either in one plane or at different levels) finished with 1mm thick decorative laminate of approved made and shade (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling / edges is to be provided lamination or with teak wood decorative beading of 50mm x 20 mm finished with polish/painting as directed.(Make: Archid / Century/ Green Ply)(The test certificate from the manufacture for all the plywood/board/laminate/mica shall be subbmited at the time of dilivery at the site address needs to be included)				
4	ACP Paneling(Exterior Grade)	Sqm	17.11		
	Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with framing of M.S. Tube sections of min. 50 mm x 25 mm and 18 gauge, (OR Aluminium tubular section of same sectional dimensions if required) of good quality, fixed/fabricated @ 600 mm c/c or less as per site requirement or members recommended by the manufacturer and in accordance with the specifications and recommendations of the manufacturer. The structure shall be fitted in place on walls/ beams/columns/ceilings/ MS fabricated structures etc. as instructed using recommended fixing method, with 3M or equivalent adhesive and with mirror screws, joints to be finished with silicon based sealant, etc. complete.				
	ACP to be in 600 mm width panels or distributed equally. it shall be of thickness of 3 mm minimum. Alubond / Eurobond / Fujibond / Alcobond or equivalent ISI brands to be used. Bright silver / shaden to be as per bank's approval. Additional sections to be provided to fix the indoor AC units. The AC units to be installed near the machine area at the highest position. Shutter Trap door will be of 12 mm prelaminated pre laminated HDHMR board board ply finished with ACP.The cost shall include all scaffoldings, chase making, lifting, cutting, on site adjustments, plaster repairing, etc. complete.MAKE: Alstrong,Alex,Aludecor				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
6	Cabinet for Electric Panel:	Sqm	0.56		
	Providing and fixing Electric panel cabinet using 19 mm thick facotry made wpc board for frame sides verticle and shelves and front shutters with aluminium framing of 50x25x1.5mm thick with 6mm thick panel on both side finished CNC jali with 1.0 mm thick laminate on all exposed surface and fire proof paint & synthetic enamel paint on all internal surface. Shutter with approved make lock handle, hinges, ball catchers, CNC jali shall be provided in shutter for ventilation, complete as directed, depth of panel 1'-3". Shutter height as required and above area fixed .Make: Archid / Century / -)(The test certificate from the manufacture for all theplywood/board/laminate/mica shall be subbmited at the time of dilivery at the site address needs to be included)				
		TOTAL			
	Part B (FURNISHING WORKS)				
7	FURNITURE (Modular series Make: AFC, Durian, Spark,Featherlite)				
	Workstation Metal CPU Trolley & KBT. supplying & installation of workstation with half ht. partition (Raceway) sutably fixed all complete as per-drawing and spectfication and ditecton of the Engincer-In-Charge. Partition thlckness 60 mm for stabilty and higher wire carying capacity.Horizontal frames are made of 1mm thick CRCA sheets confirming to IS 513:2008 & the verticals are mede ot Aluminum Extrusions fo 1.5mm thick Frame Horizontals are made of 1mm thick CRCA sheets. An lthe frames will be duly powder coated to a thickness of 50-60 micron DFT as per ASTM standard. All the frames are fastened together by means of M6 NUTS & BOLTS. They can be attached to form a 1-way, 2-way, 3 way or a 4-way configuration. All the Caṭrs via end inline &universal. These caps also ate finished in an epoxy powder coating finish in the same color. All the frames r are fnted with leveling bolts. Raceway:- Raceways are of 2 type Skirting raceways and interrmediate raceways. Skirting Raceways: Hinge raceway flap Made lout of1mm thick CRCA & powder coatedi. intermediate Raceways: Snap -fit mechanism Made out of 0.7 mm thick GI & powder coated.The electrical raceway can be provided below worktop or above worktop, these are` hook on type which wilt be mounted on the wverticals.Table tops and Gable ends are of 25 mm (thick Pre-laminated particleboards linterior Grade. All Edges are sealed with 2mm thick PVC edge-band from Rehau. Specially designed powder coated M.S. brackets fixed to the partition frame support the tabletops.				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Tiles: Options for tiles are a) Glass tile b) Fabric tile c)Steel tile'd)Pin up tile e)Magnetic tile Fabric Tile: Constructed out of 4mm thick:HDHMR Board and covered with Fabric of choice Glass tile: 4mm Toughened glass, fixed within GI powder coated frame. Two such (double skin) tiles o either iside of the frame complete the: assembly. Steel Tile: Constructed out of 0.7mm Gt sheet and finished in epox powder coating. It an be offered with plain / perforations/embossed finishes. Pin Up Tile: 0.7mm GI tray with 8 mm cross link foam coverediwith fabric of choice. Magnetic Tile: Constructed out of 0.7 mm Galvanized sheet confirming to ASTM -A563 and covered with fabric of cholce. Marker Tile: 4mmI MOF with 0.8mm glossy highly wear resistant facek laminate with a balancing laminate confirming to 1s 2046 Total thickness s 6mm				
	Bench linear workstation o f size 1500W X 900D X 750H with MDF Fabric Screen with In bult Pin-up Strip, Return Screen or Separator is of MDF Fabric finish. Table top : 18mm thick HDHMR board with 2mm PVC edge banding.MS Powder coated 50X50 Square legs and Mast leg for wire management in understructure.				
7.1	TABLES:				
7.1.1	Executives Table :	Nos.	1.00		
	1800+mobile pedestal Table. Table 2100MM 900 MM 750 mm pedestal. The table made up of18mm thk. pre laminated HDHMR board with post formed laminate flnish and having loperlor edge profile upported on Gable ends made out, 18mm thk pre laminated HDHMR board laminated and with 2mm thk PVC (adge banding,. Modesty panels are in 18mm thk HDHMR.Pre laminate finish. provision for mounting switches.				
7.1.2	Officer / Relationship Manager/ Auditor Tables :	Nos.	4.00		
	Table 1500+ mobile pedestal. Main table 1500 mm x 900 x 750mm with along with 350x470x545 mm nedestal.Prelam pre laminated HDHMR board board conforming to IS : 12823 linterior Grade with PVC edge banding. Top are with 125mm thk boards with 2mm PVC edge banding with enhanced scratch resistance supported on 18mm thk. Gable ends and 18mm thk Modesty panels. exposed edges are in 2mm thk PVC edge banding & sealed edges lare in 0.8mm thk PVC edge banding. Separate provision for mounting switches on the wall adjoining the tables shall be made by customer as the tables do not come with switch ounting facility. Wire routing / wire management groumets shal be provided on main or side table as specified				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
7.1.3	SIDE TABLE (size : 0.60X 0.60)	Nos	1.00		
	Providing in position side units made of 18mm thick pre laminated HDHMR board board with 1mm th laminate on The top, side and sliding shutter shall be made of 18mm thick pre laminated HDHMR board Board finished with 1mm thick laminate with an adjustable				
	shelf with lock facility with necessary hardware with PVC tape.				
	All exposed veneer / teak surfaces shall be finished with approved colour of melamine.(Make: Archid / Century /Green ply)				
7.2	SINGLE WINDOW COUNTER	Rmt	3.04		
	Providing, making and placing in position Single Window Operators Counters fitted to necessary partitions as per item 2.1 above (The partitlions will be measured and paid separately as per item 2.1 i.e. Half Height Partitions) with the following specifications and per dimensions specified.				
	The overall size of each Single Window Counter to be 1500mm - 1350mm x 900mm - 800mm x 750mm height. The top drawer to have cash separation arrangement.				
	The table edges shall be double thick, outside surface shall be curved using 3 layers of 6mm flexible plywood and all visible surfaces including table tops, facia of drawers and outside of shutters etc. shall be finished with 1 mm thick Plain or Textured Laminate as directed, the bottom and inside of table shall be finished with 1mm thick laminate of approved make, colour and design and all hidden areas like inside of drawers, cabinets, finished with 0.7 mm white laminate. .. contd ..				
	.. contd .. The table shall have provision for concealed LED strip lighting (cove type). Further the table and partition should have provision for fixing/embedding of vertical toughened glass partition and also glass in vertical/horizontal position on counter top, towards transaction side. (Make: Archid / Century / -)				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
8	Storages / Credenza :				
8.1	Officer Storage/Side Credenza :	Sqm	4.73		
(a)	Providing, making and placing in position low height storage cabinets as storage and/or runners from 350mm to 500 mm depth, height of 750 to 900 and length as per site requirement, and in pre laminated 18 mm pre laminated pre laminated HDHMR board board grade plywood construction with 6mm thk. pre laminated pre laminated HDHMR board board grade plywood backing complete. It shall have 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. All drawers shall be fitted with telescopic channels and locking arrangement and cupboards shall have locking arrangement and all exposed edges of plywood shall be fitted with lamination / PVC beading . shall have polish/painted of matching color.				
(b)	..contd.. middle made of 18 mm pre laminated pre laminated HDHMR board board grade plywood withPVC lipping on exposed edges duly polished. Two equal side hung shutters of 18 mm th pre laminated pre laminated HDHMR board board plywood with PVC tape of size 2mm on all edges for each compartment. .. contd..				
©	.. contd .. No vertical edge of the storage units should be left sharp. The rate to include for necessary hardware fittings (all SS brush finish) like shutters will be on ebco self closing hinges and drawers shall be on ebco plain slides, SS handle to drawers & shutters, one no. of brass magnetic ball catcher for each shutter, one no. 75 mm long SS tower bolt to relevant shutter and one "Godrej" made lock for each compartment & drawers with common key, etc. complete. All the edges of the BWR plywood in contact with floor also to be provided with PVC tape of size 20 x 6 mm. Nylon Buffers of suitable size to be provided under the storage units fixed with screws, wherever required.(Measurement area = Length x Height).(Make: Archid / Century / -) (The test certificate from the manufacture for all theplywood/board/laminate/mica shall be submitted at the time of dilivery at the site address needs to be included)				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
8.2	BACK CREDENZA (In Pre laminated 18 mm HDHMR board Providing and fabrication of 2'6" high and 1'3" wide side cabinet with cabinet body of 18mm and back 6 mm plywood. The drawer shall be made with 12mm & 6mm thick plywood. The door of cabinet to be fixed with EBCO hinges. Drawer shall be mde from 12mm and back shall be made from 6mm ply. All the external exposed surfaces of the cabinet must be covered with 1mm thick laminate of approved brand and shade of Formica or equivalent All the internal / hidden surfaces to be finished with 0.6 mm thick backer lamination. All the edges/ corners of the plywood must be protected with 6mm thick plain teak wood. Multipurpose lock and handle to be fixed to shutters and. (Measurement area = Length x Height).(Make: Archid / Century / Green ply)	Sqm	4.43		
9	<u>NOTICE BOARD :</u>	Nos	1.00		
	Size of Notice board shall be 1200x600 & 150 mm deep.				
	Providing and fixing Notice Board with 18mm BWP board frame & sides finished with 1.0 mm thk Decorative texture laminate, Box to have 75 x 35mm teak wood shutters with 6mm clear glass. The back to have 5-6 mm thick BWP board and 12mm soft Ply covered with cloth of approved shade. The item shall include polishing the wood surfaces etc. complete to the satisfaction of Architect/ Bank's Engineer.(Make: Archid / Century / Green ply).				
9.1	<u>PIN UP BOARDS :</u>	Nos	2.00		
	Providing and fixing Pin-up boards of 12mm thk. pin board covered with plain matt/cotton fabric as per approval, the fabric stuck with rubber based adhesive to the board as instructed. Cost shall include all tw lippings, base preparation required and joints on fabric shall not be approved.(Make: Archid / Century / Green ply)				
10	<u>ZEBRA BLINDS :</u>	Sqm	2.45		
	Providing, supplying & fixing Zebra Blinds of approved (make - Bali, Vista, Johnson) shade etc as per the directions of the Bank at the predetermined locations. The fabric used should be dust, moisture resistant and the vendor to get the sample approved from the Bank before supplying the item. The work includes 40mm / required roller tube / round channel and mechanism and other fitting fixed in position as per manufacture's specification, including all required hardwarw & Scaffolding, complete in all respects to the satisfaction of Architect and SBI engineer.				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Specification details of Zebra Blinds are Minimum width 500 mm, Minimum drop 500 mm, Maximum width 2400 mm, Maximum drop 2600 mm, Roller tube Aluminium, Bottom details Round and oval bottom rail to match cassette, Control Chain operation, Control side Right hand side and left hand side, Chain options 10 mm ABS beads with nylon cord, Fabric position Standard roll and reverse roll, Safety device Safety clip, Cassette height 78 mm, Cassette depth 76 mm, Cassette width 84 mm with pelmet, Fabric colour and texture As per the choice of user, Fabric thickness 1.2 to 1.8 mm, Fabric and sunscreen, width 70 mm and 70 mm. Fabric type Shear sunscreen (> 2mm mesh) and solid weave fabric. Operation Operation of the blind should be through a chain system located. (Make: Johnson Window Blinds, Vista Fashions, Vishak)				
				TOTAL	
	PART C CIVIL WORK				
11	PAINT				
11.1	Enamel Paint :Providing enamel paint to wooden /steel section (Make : Dulux, Nerolac, Asian paint)	Sqm	2.55		
11.2	Plastic Emulsion Paint :	Sqm	46.95		
	Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/ distemper/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing and applying Birla putty nor equivalent. The surface shall then be allowed to dry for atleast 24 hours. It shall be then sand papered to give a smooth & even surface. Holes shall be filled with BIRLA putty, made with plaster of paris.				
12	All Dismantling work	Job	1.00		
12.1	Dismantling of existing wiremesh partitions/m.s. Grill/ false ceiling and stored the same in a suitable places as per the instruction of the Branch including cleaning, shifting charges within the Branch premises etc. complete.				
13	Providing and laying vitrified floor tiles 1200 X 600 Multi/Double charged (Minimum top layer thickness 2.0mm) Neno Polished self design, in different size with water absorption less than 0.05% and conforming to IS:15622 of approved make in all colours & shades, quality/ premium quality in flooring laid on 12mm thick cement mortar 1:4 (1 cement : 4 sand) including grouting the joints with white cement and matching pigments etc. complete Make: Kajaria/Somany/Johnson or equivalent as per sample approved by the SBI Engineer. (Basic Tile Cost Rs. 732/- PER Sqm.)	Sqm	174.91		
14	Aluminium sliding Windows/Ventilators (with frame):				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Providing and fixing in position aluminium sliding window of extruded builtup standard sections and power coated aluminium section of Jindal, Hindalco, Mann or equivalent approved make and of size, fixing with dash fastners of required size, including filling up the gaps at junctions i.e. top, bottom & sides with required EPDM rubber / neoprene / polysulphide sealant etc. Alluminium section shall be smooth, rust free, straight and jointed mechanically wherever required, including cleat angle, alluminium snap beading for glazing / paneling, stainless steel screws all complete.. The window to have extra sliding track window with MS mosquito mesh fitted to it. 5 mm Glass panes shall be fixed with approved EPDM gasket ting, beading, to be free from settling. Bottom rail shall be with self cleaning gutter section. Rate to be inclusive of cost of all fittings, fixtures, locking arrangement, handles, pegstays, gaskets, screws, hinges etc. complete.	Sqm	2.37		
	modular and anodised aluminium section of approved make and of size 122.2 mm * 45 mm*1.3 mm thick (1.829 kgper running meter for bottom. 122.2 mm * 31.75mm *1.2 mm tick (1.093 kg per running meter for top and sides) comprising of bearing bottom and top of size 40 mm * 18 mm * 1.2 mm thick (weight 0.417 kg per running meter). Interlocking section of size 40 mm *26.70 mm*1.1 mm tick (weight 0.469 kg per running meter). And hand side of 40 mm*18 mm*1.25 mm tick (weight 0.417 kg per running meter) with 5 mm tick plane clear glass of make Asahi/ Saint Gobin. Fixed in Shutter, including approved quality of neoprene gasket, fixtures, fastenings and accessories likes PVC Rollers of make Swastik or equivalent approved, Locks of Starlocks, and stainless screws etc. complete as directed by engineer in-charge.				
15	M.S. grills and windows Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. HORIZONTAL & VERTICAL GRILLS FRAME SECTION 25 X 25 X 3MM (SHS) SQUARE STEEL HOLLOW SECTION (2.04 KG/M	Kg	26.00		
TOTAL					

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
16	PART D PANATRY AND TOILET WORK				
17	Plastic Emulsion Paint :				
	Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/ distem-per/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing and applying Birla putty nor equivalent. The surface shall then be allowed to dry for atleast 24 hours. It shall be then sand papered to give a smooth & even surface. Holes shall be filled with BIRLA putty, made with plaster of paris. Make Asian, Nerolac, Dulex)	Sqm	46.95		
18	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice .husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm ² , modulus of elasticity 850 N/mm ² and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moistureproof and fire retardant and fixing with stainless steel butt hinges of required size with necessary full body threaded star headed counter sunk S.S screws, all as per direction of Engineer-InCharge. (Note: stainless steel butt hinges and necessary S.S screws shall be paid separately) 9.170.1 24 mm thick 24 mm thick WPC.	Sqm	4.47		
19	Aluminium hydraulic door closer door weight upto 36 kg to 80 kg Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with IS1, IS: 3564, embossed on the body, door weight upto 36 kg to 80 kg and door width from 701 mm to 1000 mm) with double speed adjustment with necessary accessories and screws etc. complete.(Make: Decorum, Khetan)	No.	4.00		
20	SINK				
	Providing and fixing stainless Steel kitchen Sink with drain board (JAYNA, Niralli, Neelkanth or equivalent size 1040 X 510MM Glossy as per I.S. 13983 with C.I. brackets, waste jali, bottle trap etc. including painting of fittings and brackets, cutting and making good the walls and floors wherever required..	No	1.00		

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
21	Providing & constructing Zade Black Granite platform for pantry and wash basin counters complete as per specifications with 18-24 mm kota stone stand and kota stone or MS angle/T section supports as required and as instructed, including base stone in kota stone and fixing of 15-18 mm thick mirror polished, machine cut jet black granite with simple full round edge moulding and facia for pantry counter and double thick edges with full round moulded edges and of required size. The granite full round moulding shall be fixed with araldite adhesive to the counter top. The cost shall be inclusive of cutting for sink, basin, taps etc. as and when required.	Sqm	1.46		
22	Providing and fixing white vitreous china extended wall mounting water closet of approved shape including providing and fixing white vitreous china cistern with dual flush fitting, of flushing capacity 3 litre/6 litre (adjustable to 4 litre/8 litres), including seat cover, an cistern fittings, nuts, bolts and gasket etc complete. (Make: CERA , JAQUAR , PARYWARE)Jaquar WHT - 963UFSM WITH P trap	Nos	2.00		
22.1	Providing and fixing in position Flush Valve Dual Flush Concealed Body Type Jaquar make(Code : FLV-CHR-1093NSQ)or equivalent upon approval with all WCs complete including all required connections and settings for proper functioning to the Engineer's satisfaction.	Nos	2.00		
22.2	Providing and fixing in position Angular Stop Cock with Wall Flange Jaquar make (Cat. No. FLR 5053N) or equivalent upon approvalcomplete including all required connections and settings for proper functioning to the Engineer's satisfaction.	Nos	4.00		
22.3	Providing & Fixing CP finish Two Way Bib cock with wall flange Jaquar make (Cat. No. FLR 5041N) or equivalent along with Hand Shower (Health Faucet) (ABS Chrome Plated) with 8mm dia and 1 M long Flexible tube and wall hook (Cat. No. ALD 573) or equivalent upon approval make and design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc.complete	Nos	2.00		
22.4	Providing & Fixing CP finish Pillar cock long body bib cock of Jaquar make (Cat. No. FLR 5011N/ FLR 5047N) or equivalent make upon approval and design as per approval complete including fixing and connecting and including all materials, teflon tape, cp nipples, cover plates with testing etc.complete	NO	3.00		

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
23	Providing & Fixing inclusive testing and commissioning conforming to I.S 2556 of oval / Circular /square/ rect. shape counter top / bottom wash basin installed on Granite finished counter and CI brackets, 15mm wall mounted pillar cock with electric / battery operated sensor, 32 mm dia CP waste coupling, 32 mm dia CP brass bottle trap with extension piece with all necessary fittings as per the Technical specification and drawings . The works shall include cutting and making good the walls & floors. (Counter cost for wash basin not considered).Jaquar Model No: JDS-WHM-25907N size 530 x 420 x 140 mm	Nos	2.00		
24	Providing and laying 1200mm x 600mm x10mm Antiskid tiles of approved make and approved sample in pattern as per detailed drawings on average 25mm thick cement mortar bed of proportion 1:4. The rate should be inclusive of surface preparation, giving necessary slopes, cleaning the joints and grouting them with approved white cement paste with pigmented additives to match shade of the tile. Tile shall be free from any colour & size variation. Cost all inclusive of Insurance, Freight,loading- Unloading at site and covering the same with pop. Rate will not be paid extra for cement mortar bed upto 75 mm. thk. complete.Basic rate of tile 700/-per Sqm. make Kajaria, kerovit,Nitco the work as per site conditions and instructions of Architect, Branch engineer.	Sqm	4.95		
25	Providing and Fixing 1200mm x600mm x 8mm vitrified tiles to wall of approved make, colour and in pattern as per detailed drawings in neat cement paste . The rate should be inclusive of Base coat in 1:4 CM, surface preparation, cleaning joints and grouting them with approved white cement paste with pigmented additives to match shade of the tile. Tile shall be free from any other colour & size variation. Cost all inclusive of S.S (brush finish) corner edge profile as per details.Basic rate of tile 700/-per Sqm. make Kajaria,Nitco, Kerovoit .complete the work as per site conditions and instructions of Architect, SBI BRANCH engineer.	Sqm	27.17		
				TOTAL	

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	PART E BOUGHT OUT ITEMS				
26.1	Sofa set :				
	Providing, making and fixing in position 3SEATER sofa set with side arms made for best quality badam/hillock wood framework and legs fitted with rubber nylon shoes fixing with 8mm thick commercial ply back side. Providing 150 mm thick high density (min 40) foam rubber of approved quality to seat of zigzag spring of approved quality over 12 mm thick phenol formaldehyde bonded approved quality commercial ply and 50 mm thick foam rubber of approved quality, density mini. 32 to back covered with upholstery of rate not less than Rs. 450/- per mt. finish of approved quality materials including polish finish complete of approved quality and make selected by the Engineer in Incharge. Rate inclusive of cost of material, transportation, loading/unloading, labour tools & tackles up to any lead and lift etc.	PER SEAT	3.00		
26.2	High back, revolving executive chair with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved, of makes viz. Godrej Bravo/Featherite/ Wipro/ Methodex make or equivalent as approved for BM.	Nos.	1.00	NA	
26.3	Medium back, revolving executive chair with cushioned seat and back and molded PVC hand rest, hydraulic vertical movement, swivel type chair with castors, as per quality and design approved, of makes viz. Godrej Bravo/Featherite/ Wipro/ Methodex make or equivalent as approved for officers viz. Sales Manager, Service Manager, Discussion room, SWO counters, Visitor Chairs for BM cabin, etc.	Nos.	6.00	NA	
26.4	Medium back fixed type chairs with cushioned seat and back and molded PVC hand rest Godrej, S-frame type, as per quality and design approved, of makes viz. Godrej Bravo/Featherite/ Wipro/ Methodex make or equivalent as approved for visitors etc	Nos.	11.00	NA	
27	GRAHAK MITRA TABLE	Nos.	1.00		
	Providing, making and placing in position arch shape 1650mm long Grahak Mitra Table of approximate size 1650mm x 800mm - 900mm x 750mm with the following specifications and per dimensions specified. Grahak mitra table with transaction top of 370mm wide and height 150 mm made out of 12mm glass with blue laquered to be fixed with SS studs.. Exposed faces would be finished with 1 mm thick laminate on external surfaces and 0.7 mm thick lamination on internal surfaces of approved made and shades.". The table shall have provision only for concealed LED strip lighting (cove type).				
28	Wall Mounted Writing desk :				

Item No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Providing and fixing half round / rectangular customer voucher holders writing counter of width 900 mm and maximum depth 450 mm fixed to be wall or partition at a height of 1050mm made of 18 mm thk. MR plywood and 12 mm thick glass top, and sides and edges shall be finished with 1 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed . The cost shall be completed with lippings, mouldings, fittings,and accessories etc as per specification. as per the drawing and instruction given by the Bank Engineer.	No	1.00		
				TOTAL	
	Sub Total : Part A (Interior Works)				
	Sub Total : Part B (Furnishing Works)				
	Sub Total : Part C (Civil Works)				
	Sub Total : Part D(Panatry and toilet works)				
	Sub Total : Part E (Bought Out Items)				
	TOTAL ESTIMATED COST				
Note:- The rates quoted includes all other taxes,duties, loading, unloading, transportation, other expenses etc to site.					
	GST will be paid additionally as applicable				
		Vibha Shrivastava, Architect,			
		Bhopal,			