

STATE BANK OF INDIA					
ADMINISTRATIVE OFFICE, BHAGALPUR					
PRICE BID FOR INTERIOR FURNISHING & ALLIED CIVIL WORKS OF BANKA MAIN BRANCH					
BRANCH : BANKA MAIN BRANCH			UNDER RBO : BHAGALPUR		
S.No	ITEM DESCRIPTION	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	<u>FALSE CEILING TILES</u> Providing and fixing of approved make Mineral Fibre Acoustical false ceiling tile of RH-99% of approx size 600mm x 600mm x 12mm with square / tegular edge at all heights laid on Hot dipped galvanized exposed grid 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design, specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independently. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-ordinating with all trades and making any cutouts required for the same, full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.	Sqm.	180		
2	<u>GYPSUM FALSE CEILING</u> Providing and fixing in position Seamless Gypsum Board Plain False Ceiling in one or more levels as directed including vertical surfaces between different levels. The Ceiling including vertical surfaces is to be done with 12.5 mm thick plain Gypsum boards (of approved/equivalent make), duly finished with recommended filters, tapes, etc. to have a seamless flush look. The ceiling system is to be fixed to a concealed GI framework (Gypsteel Ultra make or approved equivalent) by 25 mm long GI drywall screws at 250 mm intervals along both ways. The framework shall be suspended securely from MS angle hangers fixed to true ceiling surface by dash fasteners. The whole system is to be fitted with all necessary arrangements like perimeter channels, intermediate channels, ceiling sections, ceiling suspension angles, rawl plug, soffit cleat etc. The work includes applying two coats of approved putty & primer suitable for Gypsum boards after necessary surface preparation and final painting with approved acrylic emulsion paint on the surface. Lids shall be made out of 9 mm thick BWR plywood duly painted to match the ceiling surface and provided with 2 No. 75 mm SS butt hinges & 1 No. 100 mm SS tower bolt along the surface. The work is to be completed with all materials, accessories. Labour, tools & tackles and in strict conformity with manufacturers	Sqm.	80		
3	<u>REPAIRING OF EXISTING LOW HEIGHT PARTITION(3mm MDF board with white/blue laminate)</u> Providing and laying 3mm MDF board with top laminated with 1 mm thick blue / white high gloss laminate of approved or equivalent make of approved shade and colour on both side of all existing partitions. All complete work as per specifications and direction of Engineer-in-charge /Bank.	Sqm.	50		

4	<u>REPAIRING OF EXISTING WORK STATIONS / TABLES(3mm MDF board with white/blue laminate)</u> Providing and laying 3mm MDF board with top laminated with 1 mm thick blue / white high gloss laminate of approved or equivalent make of approved shade and colour. Inner portion of table shall be painted with matt finish 3 coat of synthetic enamel paint with primer. Change all locks/Hinges(If required) with Godrej or equivalent make. Rate shall be including of 3mm MDF sheet, 1mm gloss laminate and all mechanical accessories for Table including side unit.				
	(i) 1800 mm x 900 mm x 750 mm(For BM) with side unit 900 mm x450 mm x750 mm	Nos.	1		
	(ii) 1500 mm x 750 mm x 750 mm(For FO) with side unit 900 mm x450 mm x750 mm	Nos.	8		
5	<u>PROVIDING AND FIXING COLUMN PANELING AS PER DRAWING & DESIGN</u> The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically. The framework is to be fixed by means of Aluminium angles of appropriate size for proper fixity. The framework is to be covered by 8- 9 mm thick BWR plywood on exposed side with suitable fixtures. The surface is to be finished with 0.8 mm thick high gloss laminate of approved shade & make. Provisions are to be made for fixing LED strips. The work is to include all necessary materials, accessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc. Executed elevation area is to be measured for finished				
	(a) Interior Columns in Banking Hall	Sqm.	40		
6	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surfaces even and smooth complete in the direction of Engineer-Incharge (Make: Birla/Asian), (Including all necessary scaffolding for height work)	sqm	522		
	Painting with synthetic enamel paint for interior wall/weather coat paint for exterior of approved brand and manufacture of required to give an even shade :				
7	Two coats of New work over an under coat of suitable shade with ordinary paint of approved brand and manufacture(Make:Asian Paint) with one coat of primer(included).(Including all necessary scaffolding for height work)	sqm	1162		
8	<u>VITRIFIED TILES</u> Providing and laying Vitrified Tiles in floor in different sizes (thickness to be specified by the manufacture) with water absorption less than 0.08% and confirming to IS:15622, of approved brand and manufacture, in all colours and shade, laid on 20mm thick cement mortar 1:4 (1 cement: 4 Coarse Sand) jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. Laying of tiles will be done with the notch trowel , plier, wedge, clips, of required thickness levelling and rubber mallet for placing the tiles gently and easily.(Make: Kajaria/Johnson/Somany only)				
	Doble charge vitrified tile polished finish of size of Tiles (600X 1200mm)	sqm	250		
9	<u>CEMENT PLASTER (IN COARSE SAND)</u> 12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)(Ceilings /Wall repairs)	sqm	120		
10	<u>ACP PANELING</u> Supply and fixing 3 mm thick ACP panels for paneling to walls with 25mmx38mmx1.5mm thick aluminum pipe sections for framing at 600 mm intervals horizontally and vertically as per manufacturer's specifications. The rate shall include cost of all material and labour etc. The grooves and joints in the panels should be filled with suitable filler. The rate shall include cost of necessary fixing materials likes cleats etc.(Panel Box: if required)	Sqm.	10		
#GST will be paid extra as per applicable			GRAND TOTAL		