

ESTIMATE FOR INTERIOR PAINTING & POLISHING WORKS OF CGM RESIDENCE HOUSE NO. 118 AT SECTOR-9 A CHANDIGARH					
S.No	Description	Qty	Unit	Rate	Amount
1	Applying two or more coats Royal (ready mixed) interior paint over primer base and acrolic putty of approved shade and colour. The work includes sand papering, base prepration, removing old paint/distemper/white wash etc. complete in all respect to give even and smooth finish as per directions of the Engineer incharge. (Make:- Royal Asian paints/Nerolac/Berger as approved)	14500	Sq.ft		
2	Applying two or more coats of synthetic enamel paint on doors, windows, shutters, steel grills, ventilators, etc. including prepration of base coursew as per directions of the Engineer incharge. (Make:- Asian/Nerolac/Berger as approved)	2000	Sq.ft		
3	Spirit polish to exisitng window & doors/Storage cabinets includung rubbing, filling sealer and thinner etc. to give smooth finish and base prepartion as per directions of the Engineer incharge. (Make:- Asian/Nerolac/Berger)	843	Sq.ft		
A	Total estimated value of repair & Maintenance work				0.00