

STATE BANK OF INDIA
ADMINISTRATIVE OFFICE, RANCHI
PRICE BID FOR INTERIOR FURNISHING WORKS AT 3rd FLOOR OF A.O. RANCHI

S.No	Item Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	<u>FULL HEIGHT PARTITIONS PARTLY paneled AND PARTLLY GLAZED/SOLID PARTITION/DOOR</u> Providing and fixing double skin partly paneled & partly glazed or solid full height partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members (Gamhar, Malaysian Sal wood / hollock) at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting, fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 6 mm thick BWR grade plywood and 0.8 mm thick (Greenlam / century or equivalent) laminate with grooves / small / panels cut and pasted in the same as per typical design, on both sides so as to form able skin partition to level 900 mm and with 8.0 mm clear float toughen glass of approved make of Modi float or equivalent above, etched / etching film pasted as per design fixed in wooden frame . The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fasteners so as to form a stable system / partition all complete work with provision for wiring to be done by other agencies all complete work as per specifications and direction of Bank. Rates are inclusive of all hardware, paints, ply, laminate, toughened glass & other material, labour etc. All work to be completed as per drawing, design, specification and direction of Engineer-in-charge /Bank.	Sqm.	58		
2	<u>LOW HEIGHT PARTITION</u> Providing and fixing low / half height partitions up to 4' 0" with double skin paneling up to 3'-0" and 12 mm thick toughened glass of approved make above frameless on the top and sides and sturdily fixed at the bottom all complete job with all other specifications and details to be as per item No. 1 above and as per the design. All complete work as per Corporate Centre, Mumbai approved materials Colour & Laminate etc and specifications and direction of Engineer-in-charge /Bank.	Sqm.	53		
3	<u>12 MM THICK TOUGHENED GLASS DOOR/PARTITION</u> Providing and fixing / fitting 12 mm thick toughened glass door/partition of approved make with all necessary hardware accessories, floor spring etc. including cost of labours and materials etc.	Sqm.	4.8		
4	<u>WORK STATIONS / TABLES</u> (a). Making and erecting Desk-top with provision of wire manager having two sides vertical support panels and modesty panel. All made of 19 mm thick BWR grade plywood of Green/Century or equivalent make, top laminated with 1 mm thick laminate of approved or equivalent make of approved shade and colour. Inner portion of table shall be painted with matt finish 3 coat of synthetic enamel paint with primer. (b) Making & providing drawer chest with two drawers and one cupboard with concealed hinges and Godrej or equivalent make multipurpose locks. Box made of 19 mm thick and bottom with 6 mm BWR grade ply of approved or equivalent make, front shall be clad with 1 mm thick laminate of approved or equivalent make of approved shade and colour. All drawers shall have 'Z' shape powder coated MS runners with PVC sound less rollers. All work to be completed as per Corporate Centre, Mumbai approved materials Colour Laminate and specifications and direction of Engineer-in-charge/Bank. (c) Providing and fixing key board tray (as per design and specification at 1- above) and made of PVC / Laminated board on 'Z' shape powder coated runner with PVC soundless rollers.				
	(i) 1500 mm x 750 mm x 750 mm(For AGM/CM) with side unit 1050 mm x450 mm x750 mm	Nos.	8		
	(i) 1350 mm x 750 mm x 750 mm(For Officer/Award) with side unit 900 mm x450 mm x750 mm	Nos.	23		

5	<u>STORAGE CABINET</u> Making and fixing storage cabinet with drawer and cupboard with shelf as per the drawing/ design all made of 19 mm thick BWR plywood (of approved or equivalent make), top and front laminated with 1 mm thick laminate (of approved or equivalent make). Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be melamine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per specifications and direction of Engineer-in-charge.	Sqm.	49		
6	<u>PROVIDING AND FIXING WALL & COLUMN PANELING AS PER DRAWING & DESIGN</u> The Paneling shall be fixed on a concealed wooden framework of required section placed at 600 mm c/c both horizontally & vertically. The framework is to be fixed by means of Aluminium angles of appropriate size for proper fixity. The framework is to be covered by 8- 9 mm thick BWR plywood on exposed side with suitable fixtures. The surface is to be finished with 0.8 mm thick laminate of approved shade & make. Provisions are to be made for fixing LED strips. The work is to include all necessary materials, accessories, labour, tools & tackles and also allow provisions for electrical, computer & telephone wiring conduits, switch boxes etc. Executed elevation area is to be measured for finished (a) Interior Columns in Banking Hall (b) With 8 - 9 mm thick BWR grade plywood fixed on frame finishing paneling surface with 0.8 mm thick laminate.	Sqm. Sqm.	28 29		
7	<u>HYDRAULIC DOOR CLOSER</u> Providing and fixing hydraulic door closures of Hardwyn, Everite or equivalent approved brand all complete as per specifications and direction of Engineer-in-charge /Bank.	Nos.	3		
8	<u>FOOT REST</u> Providing and placing foot rest made of 19 mm BWR grade plywood with wooden lippings. All portions shall have a coat of matt finish enamel paint all complete work as per drawing, design. Specification and direction of Engineer-in-charge.	Nos.	31		
9	<u>LOCKS</u> S/F/F Godrej or equivalent mortise locks/ Night latches including cost of labor & materials etc. to complete job.	Nos.	3		
10	Supplying and making table 675 mm wide and 750 mm high, top, bottom, side and space for keeping the CPU of computer under the table and drawer & shelves at every 1.2 m, made of 19mm thick BWR Plywood, shutter and shelves made of 12 mm thick BWR plywood, back finished with 6 mm thick ply. The keyboard tray made of 19 mm thick BWR Plywood and pencil drawer made of 12 mm thick ply with ISI mark. All exposed vertical surfaces including top and horizontal finished with 1 mm thick laminate. Inside of the cabinet will be paint finished and including hardware's etc. Making the hole on the table top for connecting the wires and hole to be covered with dark coloured PVC wire manager with all complete job for counters.	Rmt.	4.3		
11	Carefully dismantling existing plywood/blockboard/wooden tables with side unit including all fixtures and fittings and taking away the dismantled materials by the contractor and rebate for the same, all complete as directed by EIC.	Nos.	-29		
12	Carefully dismantling existing plywood/blockboard/wooden low height back cabinet including all fixtures and fittings and taking away the dismantled materials by the contractor and rebate for the same, all complete as directed by EIC.	Sqm.	-20		
13	Carefully dismantling existing plywood/blockboard/wooden partition at 3rd floor of A.O. Ranchi and taking away the dismantled materials by the contractor and rebate for the same, all complete as directed by EIC.	Lumpsum	-1		
14	<u>ROLLER BLIND</u> Providing & fixing of roller blinds (vista level or classic/ or equivalent of standard make) in off-white or any approved color on all windows. All complete with all mechanisms etc. (Note: The area of the blinds shall be measured for payment). All complete work as per drawing, design Specification and direction of Engineer-in- charge /Bank.	Sqm.	75		

15	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm.	120		
16	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour. Two coats	Sqm.	120		
				TOTAL	
#GST will be paid extra as per applicable					