

BOQ FOR REPAIRING WORK OF GUWAHATI WEALTH HUB					
Sl.No	Description of Items	Unit	Qty	Rate (Rs.)	Amount (Rs.)
1	Removing the existing laminate finish from wall panelling by carefully dismantling the laminate without damaging the existing plywood/substrate, cleaning and scraping the exposed surface to remove all residual adhesive, gum, dust and loose particles, making the surface smooth and ready to receive new laminate finish, including disposal of unserviceable materials and all labour, tools, tackles, scaffolding (if required), and complete as directed by the Bank/Engineer-in-Charge.	sqm	146.5		
2	Patch repairing of existing wall panelling by providing and fixing 6 mm thick BWP (Boiling Water Proof) grade plywood of approved make wherever required after removing the damaged/defective portion of the existing panelling. The work shall include cutting to required size, proper fixing with approved screws/adhesive, making the surface true, level and flush with the existing panelling, including all necessary edge finishing, filling of joints, labour, tools and tackles, and disposal of unserviceable materials, complete in all respects as directed by the Engineer-in-Charge.	sqm	30		
3	Providing and fixing 1.0 mm thick decorative laminate of approved shade, colour and make on the prepared existing plywood/panel surface after thorough cleaning, scraping, removal of old adhesive, surface preparation and making the surface smooth and even. The work shall include application of approved synthetic/rubber-based adhesive, proper pressing, trimming, edge finishing, buffing, matching edge lipping wherever required, and making the laminate free from bubbles, wrinkles and undulations. The rate shall include all materials, labour, tools & tackles, scaffolding (if required), and all incidental works complete in all respects as directed by the Engineer. Laminate Make: Greenlam/Centurylam/Merinolam/ or equivalent	sqm	146.5		
4	Repairing of existing AGM table: Removing of existing laminate and fixing of approved make plyboard of 6mm thick and finished with 1mm laminate. All exposed edges to have finished with 1mm laminate. All inner surface to be finished with 1mm laminated too. The works to include all hardwares such as : castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make. Table to be finished with 8mm thick glass duly finished on edges and necessary cut to accomodate wires, edges to be m/c polished, with ms powder coated wire manager, complete as directed by EIC.	Job	1		
	Ply/Block Board Make: BWP Grade of Century/ Green/Archid or equivalent.				
	Laminate Make: Greenlam/Centurylam/Merinolam/ or equivalent				
5	Providing and fixing miscellaneous hardware and accessories for existing/new 12 mm thick toughened glass door, including replacement/supply of all necessary fittings such as SS heavy-duty hydraulic floor spring (where required), SS patch fittings, top and bottom pivots, heavy-duty hinges, SS H-type handles (300-600 mm), door stopper, glass lock with keys, patch lock, floor guide, rubber gaskets, nylon bushes, SS cover plates, anchor fasteners, screws, silicone sealant, setting blocks and all other accessories required for proper installation, smooth operation and alignment of the glass door. The work shall also include dismantling of damaged fittings (if any), minor drilling/cutting, adjustment, testing, cleaning and making the door fully functional, complete in all respects as directed by the Engineer-in-Charge.	Job	2		
6	Repairing of existing wooden door by replacing/repairing the door shutter wherever required with approved quality flush door shutter finished with 1.0 mm thick decorative laminate of approved shade and make on both faces, including balancing laminate on edges wherever required. The item shall include providing and fixing all necessary hardware fittings such as lock, brass/SS handles, door stopper, heavy-duty SS/brass hinges, tower bolt, screws and all other accessories required for proper functioning of the door. The work shall also include repairing of door frame (wherever required), surface preparation by filling defects with wood filler/putty, sanding, application of wood primer/sealer coat, and finishing with approved quality melamine polish/PU finish or duco paint (as directed), including all necessary coats to achieve a smooth and uniform finish. The rate shall include all materials, labour, tools and tackles, removal and disposal of unserviceable materials, complete in all respects and as directed by the Engineer-in-Charge.	Each	5		
			TOTAL		
NOTE :The rates are exclusive of statutory taxes (GST) on work contract					