



PRICE BID

Tender No:RBO/KDJ/R-III/2026-26/07 Date: 25/08/2026

INTERIOR FURNISHING WORK AT THE PROPOSED PREMISES FOR OPENING OF SBI-RAIKALA BRANCH

No	Description of work	Unit	Quantity	Rate	Amount
A	Interior & Furnishing Work				
1	Gypsum Ceiling Work: Providing and fixing false ceiling at all height including providing and fixing of frame work made galvanized M.S. sections as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long.				
	Fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of Engineer in charge including cost of painting the false ceiling with two coats of acrylic emulsion paint over a cost of putty				
	12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks)	sqm	150.00		

2	<u>Modular Ceiling Work:</u> Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.	sqm	50.00		
3	<u>Flush Door Work:</u> Providing & Fixing 35mm thickness BWP grade flush door finished with 6mm thick hard wood lipping on all edges duly polished, three SS Hinges for each door, one door stopper, one mortise lock/ cylindrical lock combo set, Door Closure per door finished with 1mm thickness laminates on both sides of approved shade and colour (solid and glazed with 5.5mm thickness float glass). If required, glazing of required size shall be given. The door shall be fixed to the partition. Border at Three sides will be given by 6mm wood lipping with duly polished and finished.	sqm	18.00		

4	Fully Glazed Door: Providing and fixing frameless fully glazed 12mm thick toughened float glass door fixed with necessary patch fittings including cutting, making holes, cut-outs in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / Bank's logo , approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA or Approved Equivalent Make Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG 9300 EQ - S 25mm dia X 300mm length) Glass: Saint Gobain, Aasahi Float, Modi Guard Patch Fittings, Floor Springs and Top Hinges: Dorma, Godrej, Ozone Handles: Godrej, Hettich, Haffle, door set. Locks: Dorma, Dorset, Godrej	sqm	7.85		
5	Roller Blinds: Supplying and fixing Roller Blinds of approved make with selected fabric of approved design and shade having powder coated rod and adjustable string, etc. complete. (Basic Price of Rs 80 Per Sq.Mtr excluding GST) Roller Blind- Vista wall fashion / Mac or equivalent	sqm	14.50		
6	Frosted Film: Providing & Fixing frosted film of 3-M or equivalent make of approved design pattern, shade and colour to glass panels including cleaning glass panels etc complete.	sqm	24.75		
7	Branding: Branding of Bank's standard logo with Branch Name i.e. "Puri Main Branch" with 3mm color / white acrylic fitted with LED of 2 watt of samsung make for full glow with necessary driver for LEDs and complete as instructed by Engineer-In-Charge.	One Job	1.00		
8	Work Station: Officers/ Associate work station 5'x2'-6" x2'6"along with side unit of 18"x42"x2'6": Made with 19mm MR grade BB in table top, sides with one drawer unit of 450mm x 150mmx450mm with sliding channels and one cup board. The side units shall have one shutter with provision of storage units (450x450x750). All necessary hardware's, locks, handles, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table units shall be pasted with inner laminate of 0.6 mm thick. A 40mm drop shall be provided on customer side with 19mm BB and laminate. Edges shall be finished with half round wood lipping on writing desk side and PU polished for smoothness. Drawers shall be finished with lipping polished. 10 mm thick glass shall be provided for the table top (Cost of glass shall be paid extra).Ply: MR KITPLY/Mayoor/Century/ Sylvam / Green, and laminate: Green/ Marino/ Century/Kit ply as approved.	Each	1.00		

9	BRANCH MANAGER'S TABLE:- BM table 6' X 3' (as per drawing) along with side unit of 24"x48": Made with 19mm MR grade Block Board in table top, sides with one drawer unit as per drawing and one cup board with shutter. The side unit shall have one shutter with provision of storage units as per drawing. All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be finished with inner laminate. A 40mm drop shall be provided on customer side with 19mm BB and laminated. Edges shall be finished with 1 mm laminate. Drawers shall be finished with lipping polished. 10 mm thick glass shall be provided for the table top (Cost of glass shall be paid extra) Ply: MR KITPLY/Mayoor/Century/ Sylvam / Green, and laminate: Green/ Marino/ Century/Kit ply as approved..	Each	1.00		
10	Single Window Counters: SWO Counter(5'x3'x2'6" and side unit of 3' to 3'6"x16"x30") : Made with 19mm MR grade BB table top, sides and 12mm thick ply on front modesty panel; with three equal depth drawer units (400x450 with depth as directed by engineer) with auto locking system, telescopic sliding channels, one PVC KBT, cable manager. Customer side shall be rounded with 6mm flexi ply (350 to 400mm depth) followed by 6mm ply duly supported on each side by a profile frame of 19mm BB and as directed by engineer. Round / curve shape shall be made after 3' width of table top. 12mm thick toughened glass shall be provided at 2'6" distance thus leaving 6" for customer desk space. (Cost of glass shall be paid extra). All the exposed surfaces shall be finished with 1mm thick laminate bi-colour as directed by engineer. 6mm teak wood lipping shall be provided in all drawer edges, exposed edges of counter including side units. Side unit shall have one cupboard with shutter fitted with all accessories as directed by engineer. All inside surfaces shall be polished. Make: MR Ply/BB: Kit ply/Century/green/mayoor, Laminate: Kit ply/century/green/ Marino; Hardware Godrej/ebco/ Hettich as approved	Nos	2.00		
11	CVE Table: Supply and installation of table of size 4'X2' made from 19mm thick MR grade ply-wood finished with 1mm laminate on the external surface and 0.6 mm thick laminate on inner surface. The table shall be provided with a single drawer unit of 450 mm wide, foot rest, cable manager etc with all the necessary hardware and complete as per direction of EIC / Project Architect.	Each	2.00		
12	2' Wide running table: supply and installation of 2' wide running table made from 19mm plywood of MR Grade. All the exposed surface shall be finished with 1 mm thick laminate and inner surface with 0.6 mm laminate of approved shade and brand. Rate shall be inclusive of all hardware, adhesive, overhead and a pin drawer etc and complete as directed by the Engineer-in-Charge / Project Architect.	Rmt	2.50		
13	Toughened Glass Partition: P&F 12mm thick Toughened glass partition with patch fittings at floor, top and side walls for full height Cabins, main entrance doors and other locations as directed by engineer. The glass shall be Saint Gobain / TATA while patch fittings shall be Godrej/ Ebco/ Dorma/ equiv. The glass panels shall be rigidly fixed to walls, floors and ceiling runners in proper alignment.	Sqm	15.35		
14	Grahak Mitra Counter: Providing, fitting & Fixing Grahak Mitra Table as per the design from 18 mm thick block board finished with 1 mm thick laminate as per drawing and complete as per instruction of EIC. The table shall be provided with three drawer units of 450 mm deep each.	Each	1.00		

15	Partitions: Full height and Low height Partition: Providing & fixing in position 70mm thick +/- 2mm full height/ low height solid/opaque wooden partitions finished with laminate on both sides comprising as under:- (i) Framing- Made out of 50mm x 25mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slightly vary as per unavoidable site conditions) bothways (horizontal and vertical) fixed rigidly on floor, wall / column & true ceiling. (ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood IS 303 on both sides of the framework. (iii) Finishing:- Providing 1.00 mm thick, approved quality and shade laminate, on both sides of partitions in approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-incharge using adhesive complete. (iv) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site. (v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as directed at site. (vi) Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door openings, cutouts etc. complete. (vii) The rate shall include cost of required hardware, necessary transportation, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.	sqm	43.25		
16	12 mm thick Glass for Table Top: Providing and fixing in position 12 mm thick clear float glass of approved make in table top with required etching of SBI emblem & border on the glass as directed and with machine polish finish edges. All glasses should be clean, beveled edges and machine cut and machine moulded . No extra payment will be made on this account. Allowable tolerance for glass thickness is + 0.3 mm.The glass shall be clear float glass and should be approved by the Engineer in Charge. It shall be clear, float transparent and free from cracks, flaws, Bubbles or Vision defects. The float glass shall conform to the IS 14900.	Sqm	6.70		

17	Panneling Work: Providing and fixing panelling in wall / Column: i) Framing : Framing with aluminium hollow section channel of 25mm X 50mm X 0.80 mm thick at 600 mm centre to centre duly anchored to the Brick wall / RCC column and complete as per instruction of EIC. ii) Plywood: Fitting and fixing of 9mm thick plywood over the framing with counter shunk screw at 150 mm centre to centre including finishing of the surface by grinding to receive the adhesive and laminate. iii) Laminate Skinning: Fitting and fixing of 1 mm thick laminate of approved brand and shade with adequate adhesive to give smooth and finish look. Any kind of defects like bubbling, the vendor has to rectify the same. In case of repeatation, the vendor has to replace both plywood and laminate as well.	sqm	58.00		
18	Louvours Work: Providing, Fitting and fixing of louvers of 125 mm wide and 2400 mm long over the panelling by adhesive as per instruction of the manufacturer and complete as per direction of Engineer In Charge. Make: Meraki / Rang/ Indo Prime/ Delica	Sqm	9.50		
19	Storage Units: Storage units 450mm deep: Made with 19mm MR grade Block board on all five sides and 9mm backing ply. Vertical separators shall be provided at each 3' Centres with door leaf of each shutter of 18" wide supported by plane hinges. All inside surface shall be finished with 0.60 mm thick laminate. Exposed surface including shutter edges shall be finished 1mm laminate of approved shade. Hardwraes like locks, handles shall be provided. Make: Mr Ply: Kit ply/Century/green/mayoor, Laminate: Kit ply/century/green/ Marino; Hardware Godrej/ebco/ Hettich as approved Make:	sqm	9.00		
20	Putty Work: Providing and applying 2 or more coats of Birla putty on internal walls of average thickness of 3 to 4 mm in line & level including its rubbing with sand paper to ensure smooth & even surface including necessary scaffolding etc. complete. Make :- Birla or approved equivalent make	sqm	500.00		

21	Priming & Paint work: Preparing earlier treated surface by scraping, rubbing with B14 sand paper, applying two coats of Birla white putty wherever required, to level the surface, and its rubbing with sand paper, to ensure smooth surface, suitable to receive paint and then applying 2 or more coats of approved colour and shade of Acrylic Emulsion Paint with low VOC content over a coat of approved primer complete as per manufacturers' specifications to internal walls/ceiling including necessary scaffolding etc. complete. Make:- Asian / Berger/ICI or approved equivalent make.	sqm	500.00		
22	Solid Surface Work: Installation of 6 mm thick solid surface over the furniture as directed by the Engineer Incharge as per specification of manufacturer. Make: corian/du-point/ green/ merino of approved shade.	sqm	10.60		
23	ACP Work: Providing fitting and fixing ACP panelling on the interior walls by using ACP in metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick). The aluminium composite panel cladding sheet shall be coil coated, with Kynar 500 based PVDF / Lumiflon based fluoro polymer resin coating of approved colour and shade inclusive of screws, nuts, bolts, washers, cleats, weather silicone sealant, backer rods etc. and complete as per the instruction of the engineer in charge for walls where instructed by the engineer incharge	Sqm	23.25		
24	WPC Chowkath Work:- Providing & fixing factory made single extruded WPC solid chowkath of appropriate section of virgin PVC ploymer of K vaule 58-60(suspension Grade), calcium carbonate and natural fibers(wood powder/rice husk/wheat husk) and non toxic additives(mximum toxicity index of 12 for 100 gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750Kg/Cum, screw withdrawal strength of 58 N/MM2, modulus of elasticity 900N/mm2 and resistance to spread of flame of class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in position with M.S hold fast/lugs/SS dash fasteners of required dia and length complete as direction of Engineer-in-charge.(M.S hold fast/lugs or SS dash fasteners shall include in this quoted price)	Rmt	11.00		