

PRICE BID FOR SBI MAIN BRANCH DEHRADUN

S. NO.	Brief Description of Item	UNIT	QTY.	RATE	AMOUNT
1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : 6.4.1 Cement mortar 1:4 (1 cement : 4 coarse sand) as per the direction of Engineer-in-charge.	CUM	25.00		
2	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5 mm thick) wire of high tensile strength of 165 kg/ sq. mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	MT	100.00		
3	Providing and fixing grill on windows of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer. (MS Grill of 12mm ms square bar size at 3 inches c/c in both direction).	KG	1900		
4	Providing and applying 2 or more coats of water based 100% acrylic premium emulsion paint interior grade of Asian, Dulux, Berger or equivalent approved make and shade having zero VOC & UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives to concrete and plastered surfaces, ceilings, etc. with roller finish including preparing surfaces, applying 01 or more coats of putty of required thickness over plastered surface & applying primer including scaffolding, etc. after thoroughly brushing the surface to remove all the dirt and all loose powder free from mortar dropping and other foreign material and sand paper smooth, etc. at all heights and locations complete in all respects and as per instructions of Architect / Engineer. Approved makes- Asian paints, Nerolac, Birla Opus, Dulux or equivalent.	SQM	250		
5	Providing, fabricating and fixing heavy-duty MS grill gate for Strong Room/Safe Room, fabricated with minimum 5 mm thick MS frame and 19 mm dia solid MS bars @ maximum 100 mm c/c, complete with heavy-duty hinges, locking arrangement, anchor fasteners, primer and two coats of enamel paint. Including dismantling of existing door/frame and localised wall/finish, masonry and plaster repairs, putty, painting, dismantling and replacement of damaged wall/floor tiles, grouting, debris disposal and complete making good, all as per site requirement and Engineer-in-Charge's instructions.	No.	1.00		

					
6	Shutter Work				
a	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80 x 1.25 mm M.S. laths with 1.25 mm thick top cover (DSR2023 item no .10.6.1)	SQM	10		
b	Providing and fixing ball bearing for rolling shutters. (DSR 2023 item no .10.6.1)	Nos	20		
c	Extra for providing mechanical device chain and crank operation for operating rolling shutters. Exceeding 10.00 sqm and up to 16.80 sqm in the area (DSR 2023 item no 10.8.1)	Nos.	2		
7	Dismantling of Brick works				
	Demolishing brick work, partition or glass manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. (DSR2023 item no 15.7.4)	Nos	1		
8	Providing & laying 12 mm cement Plaster in the ratio of 1:4 (1 cement: 4 coarse sand) (Approved Make- Ambhuja, Ultratech or equivalent of OPC Grade 43/53)	SQM	300		
	Note:- 1. The GST will be paid extra. 2. The work need to be done as per direction /instructions of Bank's Engineer.				
A	TOTAL CIVIL WORK				