

Price Bid

**NAME OF WORK : TENDER OF AIR CONDITIONING WORK FOR SBI , MAIN BRANCH ,
JALANDHAR (660)**

SN.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE	AMOUNT
	SUB HEAD 1 - PART- A				
1/a	Supply of Air-cooled ceiling suspended Ductable split units with motorated hermetically sealed single or twin compressor with Scroll technology having in-built compressor protection with warranty of minimum 3 years including dismantling of existing duct able unit . Make: Danfoss / Manuerop or equivalent.				
b.	The Evaporator should have aluminum fins, non woolen synthetic fibre filter with 90% efficiency & 10 microns, blower section with motor and drive, air-cooled condenser, thermostatic expansion valve, initial charge of gas and oil, high & low pressure cutouts. Evaporator casing must be powder coated galvanised sheet duly phosphated for increased corrosion resistance.				
c.	Units must have Scanner, displaying - Single phase/ unbalanced trip, phase reversal, over & under voltage cutouts, which ensures low power consumption.				
d.	d) Prices shall include supply, installation, FOR delivery, and no other charges upto commissioning and handing over.				
e.	e) 17.0 TR +-3% Duct type unit, 100% copper	6	Each		
	<u>Make : Mitsubishi /Panasonic/Bluestar/Daikin</u>				
2	Suitable condenser frame/outdoor unit satnd structurally suitable for outdoor units made of structural steel and painted with one coat of primer and two coats of synthetic enamel paint of colour same as that of condenser unit of 17.0Ton complete as required.	6	Each		
3	24 gauge Ducts made out of G.S. sheet of SAIL/ TATA/ JINDAL/ ISPAT make. Complete job as per detailed drawings including suspension from RCC ceiling with MS hangers, MS angles, steel rawl plugs, fasteners; painting the MS structure with enamel paint of approved colour & quality with Thermal insulation of the supply air duct (tail end) and return air duct (as mentioned) with 25mm thick aluminium foil backed fiber glass of UP twigs/Fgr (CR-150) jointing with 50mm wide aluminium tape.	1	Sq.mt.		
4	Drain piping U.P.V.C 32/50mm dia. With all accessories e.g. elbows, unions, sockets, reducers, reducing tees, reducing elbows, tees, nipples etc. Complete job including cutting chasing in walls, floors, roof insulation with 9mm thick nitrile rubber making good all the chases/cuts etc. and discharging the drain into a floor trap/gully trap as per the site conditions.	100	Mtr.		
5	Supply,installation, testing and commissioning of refrigerant grade copper tubing in ceiling/ wall interconnecting outdoor and indoor units duly insulated with insulation to prevent any heat loss, suitable sizes as per specifications. Make Totaline / Maxflow (Indoor To Outdoor) 5/8" dia & 1 1/8" dia Copper pipes	70	Mtr.		
6	Supply and fixing of suitable size canvas connection complete as required for the 17.0 Tr ductable machine.	6	Nos.		
7	Supply and laying of copper flexible cable 6 core 1.5 sq mm from indoor to outdoor in 25mm PVC pipe, t, bends compelete as required	300	Mtr.		
8	Removing/ Dismantaling of Old Duct as per requirement	1	Sq. mtr.		

9	Removing/ Dismantling/shifting of Old Ductable Acs	6	Each		
10	17.0 TON Ductable AC (Buy Back of Old units) (Bank's decision will be final whether the machines are given in buyback or not.	6	Nos.	(-)	
	TOTAL SUB HEAD – 1				
	SUB HEAD - 2 (Annual Maintenance Charges) (Part-B)				
SN.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE	AMOUNT
1	Compehensive parts replacement annual maintence charges for the unit 17 TR for period of 5 years including providing all spares as required after the defect liability period of one year.	102	TR		
a	1st year after defect liability period	102	TR		
b	2nd year after defect liability period	102	TR		
c	3rd year after defect liability period	102	TR		
d	4th year after defect liability period	102	TR		
e	5th Year after defect liability period	102	TR		
	TOTAL SUB HEAD - 2				
	GRAND TOTAL SUB HEAD (1 + 2)				
	G.S.T as applicable will be paid extra by the bank				
Note:	The Payment of AMC shall be released on half yearly basis in arrears and shall be awarded only after successful completion of defect period liability period of one year. Bank's decision will be final in allotment of AMC work.				
	L-1 bidder will be decided on the basis of cummulative rates of "GRAND TOTAL SUB HEAD (1+2)"				

Seal & Signature Of The firm/bidder