

BOQ For Dismantling, Disposal, Installation of Prefabricated Structural steel brackets & Reconstruction of First and Second Floor Sunshades with GRC Panels at SBI PY branch, INDORE						
Item No.	Description of Item		Quantity	Rate	Amount	Remarks
A	DISMANTLING WORKS					
1	Dismantling RCC Sunshade at First Floor and Second Floor level: Careful dismantling of existing inclined RCC sunshade (assumed 150mm thick). Work involves supporting the structure during demolition, cutting steel, breaking concrete, and safe removal. <i>Vol = 1.65m(Inclined L) x 0.15m(Thk) x 76.18m(Total L)</i>	Cum	37.71			
2	Debris Disposal: Carting away dismantled RCC and brick debris to an approved municipal dumping ground, including loading, unloading, and transportation. <i>Total Vol = 37.71 Cum</i>	Cum	37.71			
	Total Base Cost (A)					
B	FABRICATION & ERECTION WORKS					
B.1	Truss & Purlin					
1	SHS 80x80x4.8	Kg	7974			
2	10 mm thk Plate	Kg	816			
3	16 mm dia bolts (Hilti/ Fischer)	Nos	448			
4	Chemical Grouting of Bolt	Nos	448			
B.2	GRC Panel - Dholpur Red Stone Spec					
5	Top GRC Panel	sqm	251			
6	Bottom GRC Panel	sqm	229			
7	Front GRC Panel	sqm	22			
8	Additional Formwork (2 included in proposal by vendor)	nos.	2			
	Total Base Cost (B)					
	Total Base Cost (A+B)					