

**STATE BANK OF INDIA
LOCAL HEAD OFFICE, GUWAHATI
PREMISES & ESTATE DEPARTMENT
GUWAHATI, ASSAM.**

BOQ FOR HI WALL SPLIT & 4- WAY CASSETTE UNIT AC					
SBI Regional Business Office , 2nd Floor					
Sl. No.	Description's of Items	Unit	Qty.	Rate (excl. GST)	Amount (Excl. GST)
1	Supply of 1.0 TR Capacity Hi Wall mounting 5-star rated Inverter Split inverter type with cordless remote and Copper Condensor Coil with anti corrosive Blue fins with turbo cooling , Energy management. Make as per NIT. For Doctor's Cabin , Pharmacy	Nos.	2		
2	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split inverter type with cordless remote and Copper Condensor Coil with anti corrosive Blue fins with turbo cooling , Energy management. Make as per NIT. For Electrical Room	Nos.	2		
3	Supply of 2.0 TR capacity 5 star rated ceiling monting 4- Way cassette unit inverter type, having R-32 Gas , air flow volume of 784 CFM, with Turbo cooling & Maximum air flow with multispeed option,having Wireless remote & Inverter compressor for efficient performance. Make as per NIT. For Asst General Manager , R.M.Sectt	Nos.	2		
4	Supply of 3.0 TR capacity 5 Star rated ceiling monting 4- Way cassette unit inverter type, having R-32 Gas , air flow volume of 1097 CFM, with Turbo cooling & Maximum air flow with multispeed option,having Wireless remote & Inverter compressor for efficient performance. Make as per NIT. For Bank area, Conference room, Pensioner's Lounge	Nos.	15		
5	Dismantelling, Shifting, Re-Installation, Testing, Commissioning of below mention Capacities of Inverter Normal Cassette Units from existing premises of AO Guwahati. (will be taken up at the last stage of project)				
a)	2.0 TR Inverter Cassette Unit for Co-perative Store	Nos	2		
b)	2.0 TR Inverter Cassette Unit for Recreation room	Nos	1		
c)	2.0 TR Inverter Cassette Unit for Staf Association RM (1,2,3)	Nos	3		
d)	2.0 TR Inverter Cassette Unit for Dining Area	Nos	3		
6	Installation & Commissioning of High Wall split / Cassette unit etc.	Nos.	21		
7	supply and installation of 4KVA, 5KVA and 7.5 KVA Stabilizer for 1.0 TR , 1.5 TR , 2.0 TR and 3.0 TR Cassette / Split Unit as suiatable	Nos.	6		
8	supply and fixing of 32 mm UPVC Drain pipe with Insullation.	Mtr	400		
9	Supply and fixing of Power Cable 4C x 2.5 Sqmm copper Cable for Indoor to Outdoor Connection	Mtr	600		

10	supply and installation ofCopper Pipe with proper nitrile Insullation for Hi Wall Split & Cassette Unit	Mtr	480		
11	Supply and fixing of ODU Stand for 1.0, 1.5 TR & 2.0 TR Hi Wall Split / Cassette Unit.	Nos.	6		
12	Supply and fixing of ODU Stand for 3.0 TR Cassette Unit.	Nos.	15		
	Grand Total (excl. GST)				