BOQ of Electrical & A.C. works for Sports Room & Sales Room at SBI Main Br. GPO Building, Indore

Sr.No.	Description	Unit	Qty	Rate	Amount
1	LED LUMINARES:- 2' x2' X42W (FULL GLOW TYPE) LED light fittings (600 X600mm) dimension suitable for grid/gypsum ceiling complete with its electrionic driver as required per instruction of Bank's Model No	Nos	18		
2	LED DOWNLIGHTER 15 Watt, recessed mounted circular down lighter , 6" dimension	Nos	20		
3	CEILING FAN (5 Star rating, BLDC Fan) Single phase heavy duty grease filled double ball bearing.	Nos	5		
4	Providing and fixing of point wiring with above specifications. One light point controlled by one switch.	Nos	22		
5	Providing and fixing of point wiring with same above specifications. Two light points to be controlled by one switch.	Nos	15		
6	Providing and fixing of ceiling fan point controlled as under (i) one 6 amp switch	Nos	8		
7	Power Wring (6 / 16 AMP. POWER POINTS). Supply, fixing, testing and commissioning of 1 No 16 A switch & 1 No.six pin 6/16 Amp. Multi Socket (Modular Type)	Nos	10		
8	Power Wring (6 / 16 AMP. POWER LOOP POINTS). Supply, fixing, testing and commissioning of 1 No 16 A switch & 1 No.six pin 6/16 Amp. Multi Socket (Modular Type)	Nos	10		
9	SPECIAL POINTS : (For Computers). Supply, fixing, testing and commissioning of following Modular type switch socket with cover plate, PVC modular box on Surface / sheet steel box in concealed manner I/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed. 2 Nos. 6 A Switch + 3 Nos. 6 A, 3 pin Socket (Minimum two and Maximum three points are loop with one circuit as mentioned beolw)	Nos	2		
10	SPECIAL POINTS : (For Computers Loop Point). Supply, fixing, testing and commissioning of following Modular type switch socket with cover plate, PVC modular box on Surface / sheet steel box in concealed manner I/c electrical connections and making good all the damages, painting, cleaning the site etc complete including all accessories as per site requirement and as directed. 2 Nos. 6 A Switch + 3 Nos. 6 A, 3 pin Socket (Minimum two and Maximum three points are loop with one circuit as mentioned beolw)	Nos	2		

11	Providing, fixing, testing and commissioning of all nodes of four pair UTP CAT 6 LAN cables length upto 30 meter length or less as per site conditionin suitable size 20/25 mm dia, 16 SWG wall thickness rigid PVC conduit with conduit accessories	Nos	3		
12	Providing and fixing 4 way TPN double door DB for LIGHT /POWER POINTS with 63 Amp TPN , controlling 12 Nos. 16/32 Amps SPMCBs. & Complete.	Nos	1		
13	4X 25 Sq.mm XLPE.Al.armoured Cable (POWER /LIGHT/ UPS)	Mtr	20		
14	AC/Geyser Point (Single Phase). Supply, Installation, Testing and commissioning of the surface / recess mounting A.C. / GEYSER power point with the followings	Nos	4		
15	Supply, installation, testing and commissioning of Higher Efficient models of Inverter -Variable speed CASSETTE TYPE AIR CONDITIONERS (Minimum 3 Star rated) 2.00 Ton Machines	Nos	3		
16	Supply, installation, testing and commissioning of Higher Efficient models of SPLIT AC, FIVE STAR INVERTER RATING OF BEE AIR ONDITIONERS 1.5 Ton Machines	Nos	1		
17	Supply and installation of soft & prime quality of min. 22 G Copper pipe for " Split AC only" with class "o" Nitrile insulation of minimum 12mm for split air conditioner including interconnection power/ communication cable between indoor and outdoor unit	Mtr	65		
18	Drain Pipe (If Required additional) Applicale to both ACs(Cassette & Split AC). Supply and laying of heavy gauge PVC drain piping of 40mm with insulation as per site	Mtr	70		
19	Providing & fixing Hanging Light	Nos	4		
20	BOX TYPE LUMINAIRES: LED TUBE FITTINGS, 1200mm, 18/20 Watt	Nos	6		
21	LED COVE/ STRIP LIGHT WITH ITS ELECTRONIC DRIVER(BLUE COLOUR):- Supply, installation, testing and commissioning of bright LED strip light with its electronic driver complete as required.	Rmt	30		
	Total				
	GST extra				