	BOQ For Sports Room & Sales Team Room (MS Structure Work, Flooring, False Cealing, Cement Sheet & Other Miscellaneous Work) at SBI Main Branch, GPO Indore.				
S.No.	**Description of Item**	**Qty.**	**Unit**	**Rate**	**Amount (Rs.)**
1	Providing, fabricating, erecting and fixing HEAVY MS structural framework for walls including 100x100x3.0 mm SHS main columns, 50x50x3.0 mm SHS vertical studs at approx. 2'-0" c/c, 50x50x3.0 mm SHS horizontal rails, bracing, cleats, connection plates, cutting, welding, drilling, fasteners and primer complete as per approved structural drawing and direction of Engineer-in-Charge. (Make - Jindal /Tata)	2,896.43	Kg		
2	Providing and fixing approved cement board/sheet on both faces of MS framed external and internal partition walls including screws, joint treatment, cutting and finishing complete. Quantity presently GROSS; deduct door/window openings after final opening schedule.	116.85	Sqm		
3	Providing and fixing approved pre-painted GI/profile roofing sheet including self-drilling screws with EPDM washers, side/end laps, cutting and fixing complete in wall (Make - Jindal /Tata)	116.85	Sqm		
4	Providing, fabricating and erecting HEAVY MS structural framework for single-slope roofing including 100x50x3.0 mm RHS main rafters at approx. 5'-0" c/c, 50x50x2.6 mm SHS purlins at approx. 4'-0" c/c, bracing, cleats, plates, cutting, welding, drilling, primer and fixing complete; roof level varying from 11'-0" to 10'-0", as per approved structural drawing and direction of Engineer-in-Charge.(Make - Jindal /Tata)	957.94	Kg		
5	Providing and fixing approved pre-painted GI/profile roofing sheet including self-drilling screws with EPDM washers, side/end laps, cutting and fixing complete in Roof. (Make - Jindal /Tata)	107.30	Sqm		
6	Providing and fixing profile-sheet roof edge treatment including barge/side flashing and gutter/rainwater finishing complete; measured on 140 rft outer perimeter basis.(Make - Jindal /Tata)	42.67	Rm		
7	Providing and laying approved floor tiles over prepared base including adhesive/cement mortar, cutting, laying, joint filling, grouting and cleaning complete. Make - Nitco, Kajaria, Somany, Johnson.	97.55	Sqm		
8	Providing and fixing tile skirting/dado of approved size/shade including adhesive, cutting, joint filling and finishing complete.	49.99	Rm		
9	Providing and fixing approved false ceiling on GI framework including hangers, perimeter channels, ceiling boards/tiles, joint treatment, cutting and finishing complete.	97.55	Sqm		

10	Providing and fixing approved windows complete with frame, glazing, shutters/openable portions, hardware, fasteners and sealant: 2 Nos. 3'×3' in Seals Team Room and 4 Nos. 5'×3' in Sports Room.	7.25	Sqm		
11	Providing and fixing approved doors complete with frame, shutter, hinges, handles, locking arrangement and fittings: 2 Nos. 3'×7', one for each room.	3.90	Sqm		
12	Providing and applying approved primer/paint system to exposed MS structural members including surface preparation complete.	175.47	Sqm		
13	Providing and applying approved finishing/putty cement-board Perafit wall surfaces including joint treatment, required coats complete.	233.70	Sqm		
14	Providing and applying approved finishing/paint system to cement-board and Perafit wall surfaces including joint treatment, required coats complete	233.70	Sqm		
	TOTAL AMOUNT				

GST EXTRA