Tender Price Bid Datta Mandir Road, Wakad

Sr. No.	Particulars	Quantity	Unit	Rate	Amount
	SINGLE WINDOW COUNTER / CASH COUNTER				
	Approx Size- 1500 mm X 900 x 750 mm with White acrylic solid surface & blue lacquered glass finishing				
	Supplying & fixing single window counter as per design and drawing made out of 18 mm thick IS MR grade ply wood boxing of approved make, complete with 18 X 6 mm Teak wood beading on all edges wherever required. Table top				
	The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit (in place of bottom 2 drawers) made of 18 mm thick MR grade plywood and with approved make multipurpose Auto Lock in drawer and group lock in shelf unit. Inner width of				
	Foot rest of 75 mm X 38 mm (3" x 1.5") in Teak wood and CPU stand of 18 mm ply finished with 1 mm thick laminate of size 400 mm X 375 mm. Key board tray of approved make of size 450 mm X 375 mm to be fixed.				
	All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
	All fittings like 75 mm long S.S. handle, Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make.				
	Heavy duty telescopic full extension sliding channel of approved make shall be used in all drawers.				
	All the internal surface (non visible surface) shall be provided with 0.80 mm thick balancing laminate of approved shade etc. complete				
	Counter shall be made independent in Length of 1500 mm and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid.				
	FINISHING DETAILS				
	1) Table Top: 6 mm thick white acrylic solid surface 2) Front Appron: Round 6 mm thick white acrylic solid surface and 6 mm thick blue lacquered glass fixed with Natural Silicon				
	Brief list of make are as under or any equivalent make will be permitted by the Engineer				
	MR grade Ply wood (IS :303) - Green / Century / Samrat or equivalent approved make				
	Acrylic solid surface (Corain) - Dupont/ Merino/ REHAU or equivalent approved make				
	Laminate- Green / Century /Marino or equivalent approved make				
	Multipurpose group Lock - Ebco / EG / Godrej or equivalent approved make				
	Telescopic channels - Ebco / Everite or equivalent approved make				
	Keyboard tray - Ebco / Hettich / Innofit / Featherlite or				
	Auto lock- Ebco / Dorma / Ozone or equivalent approved make				
	Cable Manager (60mm) - Metal - Ebco or equivalent approved make				
	Adhesive- Fevicol / Pedilite / Araldite / Royal Bond or equivalent approved make				
1	**Single Window Counter / cash Counter with Matt Finish Laminate**				

	Same as above item No 1 but providing 1 mm thick Matt finish superwhite laminate of approved make instead of white acrylic solid surface and 1.00 mm thick matt finish sapphire Blue laminate of approved make or equivalent Make instead of blue lacquered glass etc complete as directed by the engineer in charge.	5.00	RMT		
2	**Providing and fixing 12 mm thick Toughened float Glass partition towards front side of Single Window counters towards public space as follows.**				
	12 mm thick Toughened clear float glass of required shape with bevelled edges on top portion shall be fixed with SS brackets with flat back on wooden partition and counter top as directed. All edges of glass shall be Diamond cut polished edges as directed complete.				
	Brief list of make are as under or any equivalent make will be permitted by the Engineer				
	Glass- Asaahi/ Modi guard / Saint gobain or equivalent approved make				
	Square / D bracket S S finish of required size - Oswal / Riddhi / Swift or equivalent approved make	3.00	Sqm.		
3	**BRANCH MANAGER'S TABLE:- Size: 1800 mm X 830 mm X 750 mm**	1.00	Nos		
	Supplying and installation of Table as per the following description : Table Top: Providing and fixing 18 mm thick MR grade plywood with 4mm thick Teak veneer with 3 coats melamine polish with necessary intermediate support. Table top shall be supported by 18 mm thick MR grade ply wood with plywood framing. The top of the table shall be provided with equal sized 12mm thick toughened glass fixed at a vertical gap of 50mm using SS stud fasteners. The top level of the glass shall be 750mm. Apron (Modesty Panel) made from 18mm thick MR grade plywood finished with teak veneer with melamine Finish & 12 mm thick toughened glass fixed on SS studs & groove pattern as per drawing. Table sides, back & intermediate panels (at 50cm from each				
	Drawer / Storage cabinet: Box of 450 X 800 X 720 mm shall be provided using 18 mm thick MR grade ply wood. Each Drawer Fascia made out of 18/19 mm thick plywood and all sides of drawers be made of 12 mm thick ply wood & bottom of drawers shall be of 8/9 mm thick MR grade ply wood. The drawer unit box and individual drawers to be fixed with 4mm veneer finished with melamine polish on all exposed sides and all the internal surfaces shall be finished with 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles C-type for each drawer.				
	Computer Key board (550 x 375 mm) of metal / PVC of approved make shall be provided. Exposed surfaces of the drawer unit shall have Teak veneer with PU polish. **Foot rest** of 38 x 76 MM T.W members shall be provided. All internal surface will have min. 0.80 mm thick balacing laminate. Table shall have stand of 18 mm ply finish with 1 mm thk. Laminate of size 400 x 375 mm for keeping CPU and metalic cable Manager shall be provided in table top.				
	All the surface without teak veneer / laminate / balancing laminate shall be lacquered polished of approved shade				
	As per drawing and instruction of Architect/Bank, work to be Completed				
	MR grade Ply wood (IS :303) - Green / Century / Samrat or equivalent approved make				
	Laminate- Green / Century /Marino or equivalent approved make				
	Multipurpose group Lock - Ebco / EG / Godrej or equivalent approved make				

	Telescopic channels - Ebco / Everite or equivalent approved make				
	Keyboard tray - Ebco / Hettich / Innofit / Featherlite or				
	Auto lock- Ebco / Dorma / Ozone or equivalent approved make				
	Cable Manager (60mm) - Metal - Ebco or equivalent approved make				
	Adhesive- Fevicol / Pedilite / Araldite / Royal Bond or				
4	**OFFICER'S TABLE:- Size: 1500 mm X 750 mm X 750 mm**				
	Supplying and installation of Table as per the following description : Table top shall be made from 18 mm thick MR grade plywood with 1mm thick with necessary intermediate support. Table top shall be supported by 18 mm thick MR grade ply wood with wooden framing. The top of the table shall be provided with equal sized 12mm thick toughened glass fixed. Apron (Modesty Panel) made from 18 mm thick ply wood finished with 1mm laminate & groove pattern as per drawing. Table sides & intermediate panels (at 50 cm from each sides)				
	Drawer / Storage cabinet of 400 X 630 X 720 mm shall be provided using 18/19 mm thick MR grade ply wood. Each Drawer Fascia made out of 18/19 mm thick plywood and all sides of drawers be made of 12 mm thick ply wood & bottom of drawers shall be of 8 mm thick MR grade ply wood. The drawer unit box and individual drawers to be fixed with 1mm laminate on exposed sides and all the internal surfaces shall be 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer.				
	Computer **Key board** (550 x 375 mm) of metal / PVC of approved make shall be provided. **Foot rest** of 38 x 76 MM T.W members shall be provided. All internal surface will have min. 0.80 mm thick balacing laminate. Table shall have stand of 18 mm ply finish with 1 mm thk. Laminate of size 400 x 375 mm for keeping CPU and metalic cable Manager shall be provided in table top.				
	All edges to be provided & fixed with teak wood lipping patti finished with melamine polish	3.00	Nos		
	As per drawing and instruction of Architect/Bank, work to be Completed				
	MR grade Ply wood (IS :303) - Green / Century / Samrat or equivalent approved make				
	Laminate- Green / Century /Marino or equivalent approved make				
	Multipurpose group Lock - Ebco / EG / Godrej or equivalent approved make				
	Telescopic channels - Ebco / Everite or equivalent approved make				
	Keyboard tray - Ebco / Hettich / Innofit / Featherlite or equivalent approved make				
	Auto lock- Ebco / Dorma / Ozone or equivalent approved make				
	Cable Manager (60mm) - Metal - Ebco or equivalent approved make				
	Adhesive- Fevicol / Pedilite / Araldite / Royal Bond or equivalent approved make				

5	**Flush Door with Laminate finish:-** Providing & fixing 35 mm Flush doors with 1.0mm laminate on both sides as per design. Door frame:- Providing and fixing door frames using teakwood members of size 100mm x 50mm and finished with melamine polish. Shutter:- Providing and fixing block board shutters of 35mm thick . Skin:- The shutters shall be finished with 1mm thick laminate of approved quality and make. The Doors to have all hardware such as 125mm SS hinges, 450 m long SS handles, SS tower bolts, Mortice Locks (Dorma/ Godrej). Exposed edges of shutter shall be provided with teakwood beading of 30mm width and finished with melamine polish. The item also includes SS rods 6mm x 6mm inserted in	5.00	Nos		
6	**Grahak Mitra counter**				
	Providing and supplying Grahak Mitra counter of size 1800mmx 600mm in curvature and 750mm height:- Glass Top: with chamfer edged glass 12mm thk for top on stainless steel studs of 90mm height. Table top, sides and back:- Providing & fixing table below the glass to be made out of 18mm thk IS grade MR Plywood with front apron to have 18mm thk IS grade MR Plywood with side and intermediate supports @ max. 600mm or as directed by Engineer in charge / as per Architectural drawings. Finish:- The top & exposed sides of the table shall be provided with approved 1mm thk laminate including	1.00	Nos		
	Drawer / Storage cabinet of 350 X 630 X 720 mm shall be provided using 18/19 mm thick MR grade ply wood. Each Drawer Fascia made out of 18/19 mm thick plywood and all sides of drawers be made of 12 mm thick ply wood & bottom of drawers shall be of 8/9 mm thick MR grade ply wood. The drawer unit box and individual drawers to be fixed with 1mm laminate on exposed sides and all the internal surfaces shall be 0.80 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. The table shall be provided with readymade keyboard tray (ebco or equivalent) and CPU trolley and top to be provided with wire-managers.				
7	**STORAGE CUPBOARDS**				
C	Low Height /full height Cupboard with Laminate Finish: Providing & fixing Low Height Storage Cupboard of 750-1200 mm height and 450mm deep Outer exposed structure with to be made with 18/19mm MR ply as per IS 303 and back side using 8/9mm MR grade ply. All shutters and shelves to be made with 18/19 mm thk.MR ply. All internal and external surfaces to be finished with 1mm laminate of approved shade and make. All edges of the cupboard should be edgebanded using PVC edgebanding tape of approved shade. Shutters to be provided with S.S. 200mm handles, magnetic catchers, self closing SS hinges, locks (Godrej/ Hettich/Haffele), SS towerbolts etc. All shutters to to be made overlapping the frame Only front elevation will be considered for area calculation. Make: Ply:- Archidply, Greenply, Century, Duro or approved equivalent. Laminate:- Greenlam, Century or equivalent	6.00	Sqm.		

D	Low Height Cupboard with Veneer Finish: Providing & fixing Low Height Storage Cupboard of 750-1200 mm height and 450mm deep Outer exposed structure with to be made with 18/19mm MR ply as per IS 303 and back side using 8/9mm MR grade ply. All shutter and shelves to be made with 18 mm thk.MR ply. All the external surfaces (i.e front side of shutters, top and sides of the cupboard), to be finished with 4mm thick VENEER to be finished with melamine polish. All internal surfaces to be provided with 1mm laminate. All edges of the cupboard should be edgebanded using PVC edgebanding tape of approved shade. Shutters to be provided with S.S. 200mm handles, magnetic catchers, self closing SS hinges, locks (Godrej/ Hettich/Haffele), SS towerbolts etc. All shutters to to be made overlapping the frame Only front elevation will be considered for area calculation. Make: Ply:- Archidply, Greenply, Century, Duro or approved equivalent Laminate:- Greenlam, Century or equivalent	3.00	Sqm.		
8	**Low Height wooden Partitions (LHP) with laminate finish**				
	Providing & fixing in position 70 mm +/- 2mm thick Low height wooden partitions with 450mm high glass panel finished with laminate on both sides comprising as under:- (i) Total Height of the partitions shall be from 1200 mm to be 1350 mm including 300 to 450 mm high 12 mm clear glass panal as per approved drawing. (ii) Framing : Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium sections placed bothways (horizantal and vertical) not exceeding 450 mm c/c rigidly fixed to floor, wall / columns etc including extending end/intermediate vertical members not exceeding 1500 mm c/c for total finished height of LHP. (ii) Plywood skin : Providing & fixing 12 mm thick MR plywood IS 303 on both sides of the framework and alround vertical posts extendeding upto total height of LHP.				
	(iii) Finishing :- Providing and fixing 1.00mm thick appproved quality and shade laminates using approve qulaity adhessive, over ply as per approved design & pattern including providing grooves as per Architectural drawing and as directed by the Engineer-in-charge. (iv) Glazing :- **Providing and fixing 12mm thick approved make clear float glass panels** (not exceeding 1.50 m in length) with polished edges on all sides, fixed using suiable CP Brass /SS 'D' brackets placed not exceeding 450mm c/c on horizontal surface of partition and at both ends on vertical posts to rigidly hold the glass panels.				
	(v) Providing finished section size 70/75 x 8mm thick seasoned second class Teak wood moulding to all exposed edges of partition including applying 2 or more coats of melamine polish / Duco paint including necessary preparatory work for surface preparation with putty, priming coat, sealer coat etc. complete as per sample approved by the Bank. (vi) Making necessary cutouts for electrical conduits / cables & swithboards etc., including providing additional supports wherever required complete as per drawings and as directed by Engineer. (vii) The rate shall include cost of required hardware, necessary transportaition, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.				

	Approved make:- (a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (c) Laminte:- Greenlam/Century/Archid or equivalent approved by the Bank. (d) Adhessive: Fevical SH/Vamicol or equivalant approved by the Bank. (e) Enamel Paint/polish: Asian/Nerolac/Berger or equivalant approved by the Bank. (d) Glass: Saint Gobain, Asahi Float, Modi Guard.	22.00	Sqm.		
9	**Full height solid wooden partition with both sides laminate**				
	Providing & fixing in position 70mm thick +/- 2mm full height solid/opaque wooden partitions finished with laminate on both sides comprising as under:- (i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slighly vary as per unavoidable site conditions) bothways (horizantal and vertical) fixed rigidly on floor, wall / column & ceiling. (ii) Plywood skin:- Providing & fixing 8/9 mm thick MR plywood IS 303 on both sides of the framework.				
	(iii) Finishing:- Providing 1.00 mm thick, appproved quality and shade laminate, on both sides of partitions in approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approve qulaity adhessive complete.				
	(iv) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site. (v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as direced at site.				
	(vi) Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door opoenings, cutouts etc. complete. (vii) The rate shall include cost of required hardware, necessary transportaition, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc.				
	Approved make:- (a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Samrat or equivalent approved by the Bank. (c) Laminte:- Greenlam/Century/Merino or equivalent approved	85.00	Sqm.		
	Mode of measurement:- Though aluminium frame shall extend up to RCC slab/Beam bottom level above false ceiling, clear partition area below false ceiling shall be measured including deductions for Doors and openings above 0.50 Sqm.				
	Note: Project Engineer-in-charge may consider specifying use of MR ply in lieu of MR ply, if the site conditions so warrants, after recording due justifications for the same.				
10	**Full Ht Partition with one side laminate and other side venner**				
	SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR (INNER SIDE 3.5 mm THICK TEAK VENEER WITH matt french COATING AND OTHER SIDE LAMINATE FOR MANAGER CABIN)				

	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 50mm x 1.20 mm thick Aluminium members in a maximum grid of 610 x 610 mm (2'-0" x 2'-0") fixing with 8 mm thick commercial ply with 3.5 mm thk teak venner with matt french coating on inner side and 1.00 mm thk laminate approved make on other side shall be fixed on plywood, partition shall be well supported up to slab / beam. Providing and fixing 10 mm thick float glass as directed in the partition. Providing and fixing door shutter using 35.5 mm thick flush shutter with one side veneer and one side laminate and fixing 10 mm thick glass with beading patti, 100 mm long 4 Nos stainless steel hinges, doorstopper shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members if not laminated shall have lacquer polished as directed.				
	For purpose of payment, partition height up to bottom of false ceilling only shall be measured and paid . No extra payment shall be made for members going up to slab / beam bottom	7.00	Sqm.		
	Provide Detailed measurement				
11	**Veneer Finished Columns/Wall Panelling**				
	Providing and fixing in position wooden paneling to column / walls finished with Veneer comprising as under**:-** (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizantal and vertical), fixed rigidly on wall / columnns in perfect line, level and plumb.				
	(ii) Panel Finishing:- Providing & fixing 8/9 mm thick approved make MR plywood to Aluminum framework finished with 4 mm thick appproved quality and shade Veneer, using approved adhessive, in approved pattern & design, including providing grooves, decorative mouldings etc. as per Architectural drawings and as directed at site by the Engineer-in- charge. (iii) Providing approved quality, seasoned, full length, Teak Wood moulding 15 mm thick with adequate width as required at site, all openings, cutouts etc duly polished with melamine polish complete as direced by the Engineer-in-charge at site.				
	(iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site. (v) Applying 2 or more coats of melamine polish to panelling including preparation of surface, sealer coat etc. complete as per sample approved including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete.				
	Approved make:- (a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Samrat or equivalent approved by the Bank. (c) Veneer:- Greenlam/Century/Archid / Jalaram or equivalent approved by the Bank. (d) Adhessive: Fevical SH/Vamicol or equivalant approved by the Bank.	10.00	Sqm.		
	Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear panelling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sqm.				
12	**Laminated Columns/Wall Panelling**				

	Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under**:-** (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizantal and vertical), fixed rigidly on wall / columnns in perfect line, level and plumb.				
	(ii) Panel Finishing:- Providing & fixing 12 mm thick approved make MR plywood to Aluminum framework finished with 1.00 mm thick appproved quality and shade laminate, using approved adhessive, in approved pattern & design, including providing grooves, decorative mouldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge. (iii) Providing approved quality, seasoned, full length, Teak Wood moulding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as direced by the Engineer-in-charge at site.				
	(iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site. (v) Applying 2 or more coats of melamine polish to exposed edges of panelling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete.				
	Approved make:- (a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Samrat or equivalent approved by the Bank. (c) Laminte:- Greenlam/Century/Merino or equivalent approved by the Bank. (d) Adhessive: Fevical SH/Vamicol or equivalant approved by the Bank.				
	Mode of measurement:- Though, the aluminium frame may extend above false ceiling level, clear panelling area available below false ceiling shall only be measured after deduction for all openings above 0.50 Sqm.	85.00	Sqm.		
13	ELECTRICAL STORAGE Providing and fixing 120x30x60(h) cm Cabinet for electrical panel board area:- The shutters (openable and partly louvered) made out of 18/19mm thick MR ply wood shutters with 1mm laminate finish on exposed sides. The inner sides of the storage to be of 12mm. thk MR grade ply with 6mm. thk bision board finished with paint on all internal surfaces. Colour polish to external edges brass hinges, 6" SS handles etc. as per the details. The shutters should be provided with Powder coated louvers having minimum height of 150mm each (50% of total area of shutter) on top and bottom for ventilation. The electric panel shall be fixed over 19mm MR grade ply. Measurement will be taken for a single unit of specified size.	3.00	Sqm.		
14	**CUSTOMER WRITING DESK**				
	Writing Desk Size 900 mm (3'-0") L x 380 mm (1'-3") depth x (900 mm + 150 mm) (3' + 6") ht.				

	Vertical Sides and bottom shall be made out of 36mm (2X18) thick MR grade plywood and back side 12 mm thick ply wood with 1 mm Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12 mm thick toughend glass with polished edges, making different divisions by 12 mm thick glass and edges with 18 mm thick plywood with laminate on both side for slips or forms as	1.00	Nos.		
	Brief list of make are as under or any equivalent make will				
	MR grade Ply wood (IS :303) - Green / Century / Samrat				
	Laminate- Green / Century /Marino				
	Glass- Asaahi/ Tata / Modi guard / Saint gobain				
	Adhesive- Fevicol / Pedilite / Araldite / Royal Bond				
15	**ROLLER BLINDS** -Supplying and fixing Roller Blinds of approved make with selected fabric of approved design and shade having powder quoted rod and adjustable string, etc. complete. Basic Price of Rs 1200 Per Sq.Mtr excluding GST)Roller Blind- Vista wall fashion / Mac or equivalent	10.00	Sqm.		
16	**Fully Glazed Door shutters**				
	Providing and fixing **frameless fully glazed 12mm thk toughened float glass door** fixed with necessary patch fittings including cutting, making holes, cut-outs in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. **Rate shall include necessary etching film / Bank's logo , approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items**.(DORMA or Approved Equivalent Make Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG 9300 EQ - S 25mm dia X 300mm length) (Main entry, ATM and BM cabin)				
	Patch Fittings, Floor Springs and Top Hinges: Dorma, Godrej, Ozone	9.00	Sqm.		
19	**False ceiling - Gypsum Board**				
	Providing and fixing false ceiling at all height including providing and fixing of frame work made galvanized M.S. sections as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel				
	with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval.				

	Fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings,				
a	12.5 mm thick **tapered edge gypsum plain board** conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks)	67.00	Sqm.		
20	**False ceiling - Tiled false ceiling**				
	Providing and fixing **tiled false ceiling** of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc.				
	Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.				
	Providing & Fixing mineral fibre board false ceiling of AMF / ARMSTRONG or equivalent false ceiling system (THERMATEX FEINSTRATOS MICRO PERFORATED with FINELINE of 15mm GRID with Black GRID REVEAL) of grid size 600mm X 600mm with G.I. ceiling frame work as per Manufacturer's specifications including filling of Acoustic ceiling tiles 15mm thick of size 600mm X 600mm microlook having 0.55 NRC, 38dB & 95% RH and 90% Light Reflector	74.00	Sqm.		
21	**ACP CLADDING:**				
	Supplying and fixing aluminium composite cladding with skin material 0.5 mm thick aluminium sheet cover material natural polyethylene aluminium cladding panel fixed with extruded aluminium basis frame (50x25x1.5mm) angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work including necessary accessories complete in all respects including all labour, scaffolding charges etc., complete for finished item of work. ACP Cladding - 4 mm thick. (INCLUDING THE WALLS OF THE ATM)	54.00	Sqm.		
22	**Protector sheet over virtified tiles**				

	Providing and spreading PVC/ rubber sheet of required thickness over the existing vitrified flooring to void scratching of tiles and damages, with high impact resistance waterproof, highly durable, with application of adhesive tapes on ths joints wherever required. With miminum 250 GSM vairant.The quoted rate should include the cost of removal of the sheet and also replacement of the damaged tiles after completion of all works at the premises. Make - Nilkamal Floor Guard or equivalent	215.00	Sqm.		
23	**Toughened glass partition of approved make:**				
	Providing and fixing in position 12mm th. Toughened glass partition at front side of branch and in between machines with pipes / brackets of HETTICH or equivalent make Including patch fittings etc. complete. Providing and fixing 12mm thick straight toughened glass full height partitions comprising as under:				
	Rate shall include for providing transport charges, handling, loading and unloading & installation of all necessary hardware's, scafolding, wastage, providing necessary structural supportsto the framework with walls/roof ceiling etc. complete all as per manufacturers specifications as directed. (ATM)	28.00	Sqm.		
24	**Providing & fixing of Dressing Table with Puffy**				
	Dressing Table shall have 460x1220 mm size 5 mm thick mirror with SS studs.12 mm thick MR plywood of size 610 x 152 mm with 1 mm thick laminate on top and having polished edges/bottom supported by brass bracket 2 Nos. as directed to be fixed perpendicular to mirror. Item includes fixing of 12 mm thk. glass shelve having approx. size 460x75mm. Edges of glass shall be diamond polish. Puffy shall be made of using TW member of size 51x51mm and18 mm thick plywood for seat support. Seat shall be padded with 100 mm thick 40 density foam covered with hession cloth and upholstered with Approved shade and quality fabric. Basic price of fabric shall be Rs.650/-per Rmt. Visible wooden support shall be polished. Size of Puffy shall be 460 x 460 mm. MRgradePlywood (IS:303)	1.00	Nos.		
25	**FIRE DOOR**	1	no		
	Providing and fixing of Hollow metal fire rated doors as per IS 3614 part-1 & part-2 for stability and integrity. Pressed Galvanized steel confirming to IS 277 with the following specification. Recommended fire door shall have doors tested at CBRI or ARAI for maximum rating of 2hrs with vision panel. Test certificates should be available for vision lites /panels as part of the fire door assembly. Independent glass test certificates will not be accepted. Manufacturer test certificate shall cover doors both single and double leaf and all doors supplied should be within the tested specimen, deviation in specification and sheet thickness other than what is mentioned in the test certificates are not allowed. Proper label confirming the type of door and the hourly rating is mandatory. Approved manufacturer Shakti Hormann or approved equivalent.				

	Door frame shall be double rebate profile of size 143 x 57 mm made out of 1.60mm (16gauge) minimum thick galvanized steel sheet. Frames shall be Mitered and field assembled with self tabs. All provision should be mortised, drilled and tapped for receiving appropriate hardware. Rubber door silencers should be provided on the striking jamb. Frames should be provided with back plate bracket and anchor fasteners for installation on a finished plastered masonry wall opening. Once frame installed should be grouted with cement & sand slurry necessary for fire doors on the clear masonry opening.				
	Door leaf shall be 46mm thick fully flush double skin door with or without vision lite. Door leaf shall be manufactured from 1.2mm (18guage) minimum thick galvanised steel sheet. The internal construction of the door should be rigid reinforcement pads for receiving appropriate hardware. The infill material shall be resin bonded honeycomb core. All doors shall be factory prepped for receiving appropriate hardware and provided with necessary reinforcement for hinges, locks, and door closers. The edges should be interlocked with a bending radius of 1.4mm. For pair of doors astragals has to be provided on the meeting stile for both active and inactive leaf. Vision lite wherever applicable should be provided as per manufacturers recommendation with a beeding and screws from inside. The glass should be 6mm clear borosilicate fire rated glass of relavant rating of the door.				
	All doors and frames shall be finished with polyurethane aliphatic grade paint of approved colour. The door leaf and frame shall have passed minimum 250 hours of salt spray test.				
	Rate should include supply and installation of door and hardware set as mentioned in the door and hardware schedule.				
	2Hrs Fire Rated Door leaf of size as mentioned With vision panel with hardware set for each leaf as follows:				
	Ball bearing butt hinge 4" x 3" x3 mm in SSS				
	Mortice sash lock 50mm BS, 20mm sq for end strip, SSS 1"				
	6 pin EP cyl. L=70mm both side keys in SNP (1 each)				
	Tubular lever handle with roses and esc. SSS (1 each)				
	Door closer spring size 3 with standard arm, CE marked				
	Concealed flush bolt body with rod, Length - 265mm , Vision panel of 6mm thick borosilicate Fire Rated clear glass of size 200mm (W) x 300mm (H), Self adhesive side roll (Ceramic Tape) as required				
26	Acrylic Emulsion Paint (only in branch front area touch up only)	100	Sqm		

	Preparing earlier treated surface by scraping, rubbing with sand paper, applying two coats of Birla white putty wherever required, to level the surface, and its rubbing with sand paper, to ensure smooth surface, suitable to receive paint and then applying 2 or more coats of approved colour and shade of Acrylic Emulsion Paint with low VOC content over a coat of approved primer complete as per manufacturers' specifications to internal walls/ceiling including necessary scaffolding etc. complete. Make:- Asian / Berger/ICI or approved equivalent make.				