STATE BANK OF INDIA
LOCAL HEAD OFFICE, GUWAHATI
PREMISES & ESTATE DEPARTMENT
GUWAHATI, ASSAM.

GUEST HOUSE, GUWAHATI
BOQ for Supply, Installation, Testing and Commissioning of Air-conditioners in 04 Suit rooms

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Exclusive of GST)	Amount (Rs.) (Exclusive of GST)
A	**High Side work: Supply of Machines**				
1	Supply of 2.0 TR Capacity Hi Wall mounting 5-star (as per new rating in 2026) rated Inverter Split Ac having ISEER more than 5.0 with cordless remote and Copper Condensor Coil. **AC Make, Voltas/Bluestar / Daikin /LG/Hitachi** (For BM Cabin)	No.	4		
2	Supply of 2.0 TR Capacity Hi Wall mounting 5-star (as per new rating in 2026) rated Inverter Split Ac having ISEER more than 5.0 with cordless remote and Copper Condensor Coil. **AC Make, Voltas/Bluestar / Daikin /LG/Hitachi** (For BM Cabin)	No.	1		
3	Installation charges of the **1.0/2.0 TR** Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	5		
4	**For 2.0 TR hi wall split type air conditioners:** Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	20		
4	Supply and Installation of 5 KVA Stabilizer for 2.0 TR ACs	Nos.	4		
	Supply and Installation of 4 KVA Stabilizer for 1.0 TR ACs	Nos.	1		
5	Supply and Installation of addional drain water UPVC pipe for properly conecting to the drain point	RM	25		
GST will be extra as applicable.		**Total: (In Rupees) excluding GST**			