PRICE BID

E-TENDER AO/BAM/RBO-3/2026-27/17 Dated 30.09.2026

INTERIOR WORK FOR STATE BANK OF INDIA FOR PROPOSED MEDICAL COLLEGE CAMPUS BRANCH, PHULBANI

Last date of submission of online price bid	01.00 PM 13.10.2026

BOQ for Interior Furnishing works at SBI- MEDICAL COLLEGE CAMPUS BRANCH, PHULBANI

Sr. No	Description of work	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	**Dismantling of Stone / Block / RCC/Brick Masonry** Dismantling manually or by mechanical means all type of Stone / brick / block masonry in the entire building including plastered walls, parapet on terrace, compound wall etc. in existing sub structure and superstructure at all height and location. The contractor should take care that dismantling of structure should not cause any damage to the existing / adjacent structures near the building and even take care of dust control, noise control etc. Blasting is not permitted. All the work shall be carried out as instructed by Architect / SBI. The rate to include carting away unserviceable material /debris to a place approved by Local Authority/Municipal Corporation. The work also includes levelling the ground after carting away.	Cum	4.47		
2	**Dismantling of Flooring / Dado / Cladding Tiles** Dismantling manually or by mechanical means all type of existing Floor / Dado / Cladding Tiles including kitchen and vanity platform at all height and location. The contractor should take care that dismantling of structure should not cause any damage to the existing / adjacent structures near the building and even take care of dust control, noise control etc. Blasting is not permitted. All the work shall be carried out as instructed by Architect / SBI.The rate to include carting away unserviceable material /debris to a place approved by Local Authority/Municipal Corporation. The work also includes levelling the ground after carting away.	Sqm	1.46		
3	Supplying, diluting and injecting Imidacloprid Chlorpyriphos or Equivalent approved chemical emulsion for **POST-CONSTRUCTIONAL anti- termite treatment** :Treatment of existing masonry joints with flooring (at ground floor level) using chemical emulsion @ one litre per hole at 300 mm interval including drilling holes at 45 degree and plugging them with cement mortar 1:2 (1cement : 2 coarse sand) using coloured white cement to the full depth of the hole using approved Chemical having concentration.as per manufacturer's recommendations. Approved Agencies: PCI/ PECOPP/ GODREJ HI-CARE or Equivalent approved by the Bank	Sqm	260.00		
4	Providing and laying in position mechanically mixed **Reinforced Cement Concrete (RCC) 1:2:4** using 20 mm nominal size and downgrade metal of specified grade in Super Structure (Excluding reinforcement) at all levels and hight for various RCC structural elements in any shape and design as per structural drawings and as directed including transporting (manually / mechanically), laying, compacting and finishing the surface in line, level and plumb as required and cost of curing etc. complete. The Rate to include cost of rquired formwork , centring,	Cum	1.00		
5	Providing and laying in position external **Sand Cement Plaster,** average 20 mm thk, in two coats, at all heights with first coat of av. 12 mm thk in Cement Mortar 1:5 using natural silt free fine sand, and second coat of average 6 mm thickness in C.M. 1:4, including necessary stagging, scafolding, curing, roughening the first coat to recieve second coat of plaster etc, providing approved water proofing compound @1 kg per bag of cement or as specified by the manufacturer and adding polyproplyne fibre of approved make as per manufacturers specifications to prevent shrinkage cracks, complete as directed by the Engineer-in-charge.	Sqm	683.97		
6	Providing and constructing **Brick masonry walls in superstructure with cement sand ratio (1:6)** using locally available approved quality Bricks, well (Kiln/Chimney) burnt, uniform size and colour having average crushing strength not less than 35 kg/cm2 for walls, shaft walls, parapets, drains, manholes, trenches etc. in proper line, level and plumb including striking out / raking out joints, curing, necessary scaffolding, etc. complete at all heights and levels as per the approved drawing and as per instructions of the Architect / Engineer-in-charge	Cum	60.82		
7	Providing and constructing **half brick masonary works** with cement mortar 1:4(cement:sand) walls in superstructure using locally available approved quality Bricks, well (Kiln/Chimney) burnt, uniform size and colour having average crushing strength not less than 35 kg/cm2 for walls, shaft walls, parapets, drains, manholes, trenches etc. in proper line, level and plumb including striking out / raking out joints, curing, necessary scaffolding, etc. complete at all heights and levels as per the approved drawing and as per instructions of the Architect / Engineer-in-charge	Sqm	57.64		
8	**Vitrified Tile Flooring of size (1200mmx600mm)** Providing & laying in-position Vitrified tiles in floor and skirting of approved make and colour uniformly in line, level and in approved design, including laying avg. 20 to 25 mm thick bed of CM 1:6 (1 cement : 6 coarse sand) and filling the joints with epoxy based joint filling compound of matching shade, curing the joints etc complete. Rates to include providing & fixing 100 mm high skirting as per drawing flushed with finished surface of wall in line and level and 6 mm wide groove to be made in wall at the junction of skirting and finished surface of wall etc. complete matching to flooring as per direction of Engineer In-Charge.	Sqm	238.68		
9	**Granite slab with moulding** for Kitchen (Machine Polished / Flame Burnt etc.) Providing and laying in position 18mm ± 2mm thick machine cut pre-polished Granite stone flooring and skirting in approved colour, shade, design and patterns as per architectural drawings ilaid over 20 mm (average) thick cement mortar 1:6 (1 cement : 6 coarse sand) bedding fixed and jointed with neat cement cement slurry and filling joints using white cement slurry admixed with pigment of matching shade or epoxy based joint filling compound of approved make including grinding, mirror polsihing, curing, nosing, making grooves etc. complete as specified in the Architectural drawings and as directed by the Engineer-in-Charge. (Basic rate Rs. 1,800/- per sqm. In vanity counters, Kitchen platform etc. using full width single slabs not less than 1.80 meter in length with full round mouded edges duly mirror polished.	Sqm	2.21		
10	Providing and fixing in position premium quality joint free /paper cut edges digital print **ceramic wall tiles** of size 300 X 450 mm in walls/dado conforming to IS: 15622 (thickness to be specified by the manufacturer) of approved make, colours and shades as per sample approved by Engineer in-Charge fixed over 15mm thick rough finished backing plaster in CM 1:4 fixed with neat cement slurry including filling joints using white cement/epoxy based joint filling compound with matching pigment including acid cleaning of tiles complete in all respect and at all heights, levels and locations. Rate includes cost of CM 1:4 backing plaster with waterproofing compound, cahmferring of tiles at corners and excution of work all heights and locations including necessary scaffolding etc. complete. Make: Kajaria, Somany, Simpholo, Johnson, RAK, Nitco	Sqm	6.51		
11	**Anti Skid Digital Print Ceramic Tile (300mmx300mm)** Providing and laying in position Anti Skid Digital Print Ceramic Tile (9 mm min. thickness) flooring of approved colour, shapes and texture laid in required pattern in uniform line, level including laying avg. 20 to 25 mm thick bed of CM 1:6 (1 cement : 6 coarse sand) and neat white cement float, filling joints with neat cement slurry of appropriate colour, curing and cleaning complete. Tiles shall be free of any variation in colour or texture in all aspects as specified and directed by the Engineer/Architect. Make: Kajaria, Somany, Simpholo, Johnson, RAK, Nitco	Sqm	8.88		

12	Providing, Cutting, bending & welding/tying additional epoxy coating, Fe 500/550 TMT reinforcement bars of required diameter at all positions, drilling holes of required diamter to insert the bars in old RCC upto 50 mm depth and tying the same with annealed Galvanised Binding wire, wherever welding of old and new reinforcement is not possible, including providing cover blocks of appropriate sizes etc. complete as specified and instructed by the consultants.	Kgs	300.00		
13	**PH & SANITARY WORK**				
i	Providing and fixing 25 mm dia (concealed) Chlorinated Polyvinyl Chloride (CPVC) pipes SDR 13.5, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings. The work includes concealing of pipeline by chiselling or breaking brick wall/ RCC/PCC and making good to damages in C:M 1:3, jointing of pipes & fittings with one step CPVC solvent cement and the cost of Tees, bends, elbows , couplers, clamps etc and the rates are inclusive of scaffolding charges upto any height including testing of joints complete as per direction of Engineer in Charge.	Rmt.	30		
ii	Providing and Fixing 40mm dia cPVC pipeline of same specification as above	Rmt.	2		
iii	Providing and Fixing 75mm dia uPVC pipeline of same specification as above	Rmt.	16		
iv	Providing and Fixing 110 mm dia uPVC pipeline of same specification as above	Rmt.	13		
v	P&F toilet louvers size 600mmx450mm made of anodoized aluminum frame and 5 mm thk float glass in position with provision for exhust fan	Nos	3		
vi	EWC:Providing, fitting and fixing white vitreous water closet (European type WC pan 400mm high)wall/floor mounted (Medium Range) as per site condition & as directed of Essco/Parryware/Johnson HR/ Eqv approved by EIC make with seat cover and 7.5 lit PVC Cistern Tank, CP brass hinges and rubber buffers with fittings and fixtures.	Nos	3		
vii	Sink :Providing fitting & fixing of approved of size (4500x600) mm as directed by the EIC	Nos	1		
viii	Wash Basin: Providing, fitting and fixing white vitreous china wash basin of size 550mm x 440mm of Essco/Parryware/Johnson HR/ make CI/MS brackets, 32mm CP brass waste coupling of standard pattern, CP stop cock with plug and flexible PVC waste line	Nos	4		
ix	Mirror:Providing fitting & fixing decorative mirror of Jaquar / Cera/Essco Hindware make model no C8061 of size (600x450) as directed	Nos	4		
x	Pillar cock: Providing fitting & fixing chrome plated (CP) pillar / sink cock with aerated flow system of Cera/ Hindware/ Jaquar make complete as directed and specified	Nos	4		
xi	Health Faucet:Supply and fixing 15 mm dia Health Faucet with 1.2 mtrs long PVC connecting pipe of approved make : Parryware/ Hindware/ Cera/ Jaquar with flange all complete.	Nos	3		
xii	two in one bib cock:Providing fitting & fixing chrome plated (cp) bib cock of Jaquar/Hindware/Cera make with aerator flow system including flange, diverter and necessary fittings complete as directed and specified.(Basic Cost Rs. 1500/-)	Nos	4		
xiii	Angle cock:Providing fitting & fixing chrome plated (cp) angle/ stop/bib cock of Jaquar / Cera/ Essco/ Hindware make complete as directed and specified.	Nos	7		
xiv	Providing and fixing SS Gratings	Nos	5		
xv	Providing and fixing CP towel rod of 18" length	Nos	4		
xvi	Liquid Soap dispenser (PTMT)	Nos	4		
xvii	Soap tray (SS)	Nos	3		
xviii	Plastic/PTMP shelf	Nos	4		
xix	Coat hook	Nos	3		
14	**Fire doors record & UPS room** Providing and fixing 60 mm thick glazed fire resistant door shutters of 60/120 minutes Fire rating conforming to IS:3614 (Part II) or EN1634-1:1999, tested and certified as per laboratory approved by Engineer-in-Charge, with suitable mounting on door frame, consisting of vertical styles, top rail & side rail 60 mm x 60 mm wide and bottom rail of 110 mm x 60 mm made out of 1.6 mm thick G.I. sheet (zinc coating not less than 120 gm/ sqm) duly filled mineral wool insulation having density minimum 96 kg/ cum and fixing with necessary stainless steel ball bearing hinges of size 100x89x3 mm of approved make with D handle lock arrangements, device for single leaf door(for inside operation), clear fire rated 6 mm this glass with metal vision panel of size(200x300mm), Anchor fastner(10x100mm), fire door closure, pair of SS tower bolt of 300 mm long, mortise dead lock with 70mm cylinder both side, SS D handle(19x250mm) followed by applying a coat of approved fire resistant primer or powder coating not less than 30 micron etc all complete as per direction of Engineer-in-Charge.Preferable size 1200x2100 mm. Make Hormann or Equivalent passing all criteria as specified above				
a	with 120 minutes retaining (1200mmx2100mm) for record & UPS room	Sqm	4.23		
15	**Doors for wash room**				
a	Chowkath Providing and fixing factory made single extruded WPC (Wood Polymer composite) solid door/window/Clerestory windows & other Frames/Chowkhat of size 50x100 mm comprising of virgin PVC polymer of Kvalue58-60(SuspensionGrade), calciumcarbonate and natural fibers (woodpowder/ rice husk/wheat husk) and non toxic additives (maximum toxicity indexof 12 for 100gms) fabricated with miter jointsafter applyingPVCsolvent cement and screwed with full body threadedstar headed SS screws having minimum frame density of 750kg/cum,screw withdrawal strengthof 2200N(Face) & 1100N(Edge), minimum compressive strength of 58N/mm2, modulus of elasticity 900N/mm2 and resistance to spread of flame of Class A category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in positionwithM.Shold fast/lugs/SSdash fasteners of required dia and length complete as per direction of Engineer-In-Charge. (inclusive of M.S hold fast/lugs or SS dash fasteners). Note: For WPC solid door/window frames, minus 5mm tolerance in dimensions i.e depth and width of profile shall be acceptable. Variation in profile dimensions on plus side shall be acceptable but no extra payment on this account shall be made.	Rmt	20.12		
b	WPC shutters Providing and fixing factory made single extruded WPC (Wood Polymer composite) solid door/window/Clerestory windows & other Frames/Chowkhat of size65x125mmcomprisingof virginPVCpolymerofKvalue58-60(SuspensionGrade),calciumcarbonateandnatural fibers(woodpowder/ rice husk/wheat husk) and non toxic additives (maximum toxicity indexof 12 for 100gms) fabricated with miter joints after applying PVC solvent cement and screwed with full body threaded star headed SS screws having minimum frame density of 750kg/cum,screw withdrawal strength of 2200N(Face)&1100N(Edge),minimum compressive strength of 58N/mm2, modulus of elasticity 900N/mm2 and resistance to spread of flame of ClassA category with property of being termite/borer proof, water/moisture proof and fire retardant and fixed in positionwithM.Shold fast/lugs/SSdash fasteners of required dia and length complete as per direction of Engineer-In-Charge. (inclusive of M.S hold fast/lugs or SS dash fasteners).. Note: For WPC solid door/window frames, minus 5mm tolerance in dimensions i.e depth and width of profile shall be acceptable. Variation in profile dimensions on plus side shall be acceptable but no extra payment on this	Sqm	6.50		

16	**Rolling Shutter:** Supplying & Providing rolling shutter with guide & locking arrangement Supplying and fixing a Manually Operated rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x1.25 mm M.S. laths with 1.25 mm thick top cover including providing and fixing ball bearing for rolling shutters, providing mechanical device chain and crank operation for operating rolling shutters etc.complete in all aspects. The rate to include applying a priming coat of approved steel primer with two 2 or more coat of synthetic enamel paint. (Outer dimensions including hood will be measured for payment purpose.) preferable size(8'/5'x7'6")	Kg	864.00		
17	**Collapsible Gate**: Providing and fixing in position collapsible steel shutters with vertical channels 20x10x2 mm and braced with flat iron diagonals 20x5 mm size, with top and bottom rail of T iron 40x40x6 mm, with 40 mm dia steel pulleys, complete with bolts, nuts, locking arrangement, stoppers, handles, including applying a priming coat of approved steel primer with two or more coat of synthetic enamel paint. Preferable size (5'x7'6")	Kg	853.13		
	INTERIOR WORKS				
A	**PARTITION WORKS**				
18	**FULL HEIGHT Partition** (Solid/Semi Glazed): Providing & fixing in position 70mm thick +/- 2mm full height solid/opaque wooden partitions finished with laminate on both sides comprising as under:- (i) Framing- Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium square sections at spacing not exceeding 600 mm (may slighly vary as per unavoidable site conditions) bothways (horizantal and vertical) fixed rigidly on floor, wall / column & ceiling. Item to include 8mm thick glasses per design and fitted with 31/4" thick beach/teak wood beading and 2"x2"T.W.member for door sides and frosted film of 3-M/ LG make of approved design pattern, shade and colour to glass panels including cleaning glass panels etc as advised by EIC complete (ii) Plywood skin:- Providing & fixing 9 mm thick MR plywood IS 303 on both sides of the framework. (iii) Finishing:- Providing 1.00 mm thick, appproved quality and shade laminate, on both sides of partitions in approved design & pattern including making grooves as per Architectural drawing or as directed by the Engineer-in-charge using approve qulaity adhessive complete. (iv) Making suitable cutouts/ openings/ channels for Doors, electrical conduits, cables & switch boards, AC ducts etc including providing necessary wooden supports wherever required and directed at site. (v) Providing and making suitable door frame with rebate for door shutters using approved quality seasoned full length Teak Wood having finished sectional size 75mm x 20mm to the door perimeter complete as per detailed Architectural drawing and as direced at site. (vi) Applying 2 or more coats of approved matching shade and finish, melamine polish to all exposed edges of partitions including those in door opoenings, cutouts etc. complete. (vii) The rate shall include cost of required hardware,necessary transportaition, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete. (Note: Incase of false ceiling, the vertical members to be fixed with pucca ceiling butth area of partition payable will be below the false ceiling only). Make:Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank. Pywood (MR Ply): Century / Green / Archid/ Sylvm,	Sqm.	11.90		
19	**LOW HT PARTITION**:Providing & fixing in position 70 mm +/- 2mm thick Low height wooden partitions with 450mm high glass panel finished with laminate on both sides comprising as under:- (i) Total Height of the partitions shall be from 1200 mm to be 1350 mm including 300 to 450 mm high 12 mm clear glass panal as per approved drawing. (ii) Framing : Made out of 50mm x 50mm, 1.2 mm thick hollow aluminium sections placed bothways (horizantal and vertical) not exceeding 450 mm c/c rigidly fixed to floor, wall / columns etc including extending end/intermediate vertical members not exceeding 1500 mm c/c for total finished height of LHP. (ii) Plywood skin : Providing & fixing 9mm thick MR plywood IS 303 on both sides of the framework and alround vertical posts extendeding upto total height of LHP. (iii) Finishing :- Providing and fixing 1.00mm thick appproved quality and shade laminates using approve qulaity adhessive, over ply as per approved design & pattern including providing grooves as per Architectural drawing and as directed by the Engineer-in-charge. (iv) Glazing :- Providing and fixing 10 mm thick approved make clear float glass panels (not exceeding 1.50m in length) with polished edges on all sides, fixed using suiable CP Brass /SS 'D' brackets placed not exceeding 450mm c/c on horizontal surface of partition and at both ends on vertical posts to rigidly hold the glass panels including fixing of frosted film of 3-M/ LG make of approved design pattern, shade and colour to glass panels complete (v) Providing finished section size 70/75 x 8mm thick seasoned second class Teak wood moulding to all exposed edges of partition including applying 2 or more coats of melamine polish / Duco paint including necessary preparatory work for surface preparation with putty, priming coat, sealer coat etc. complete (vi) Making necessary cutouts for electrical conduits / cables & swithboards etc., including providing additional supports wherever required complete as per drawings and as directed by Engineer. (vii) The rate shall include cost of required hardware, necessary transportaition, execution of work at all heights and locations including all lead, lift, wastage, statutory liabilities etc. complete.	Sqm	19.66		
20	**Cement Board Partition** (Solid/Semi Glazed): Providing and fixing in position partly glazed / full solid Partition work as per drawing, in frame work at 2'x2'grid (horizontallyandvertically) comprising of 2"x1½"x1.30mm almunium section and/or as per frame work shown in the drawings with 9mm Biason Cement board on both sides . Item to include 8mm thick glasses per design and fitted with 31/4" thick beach wood beading and 2"x2"T.W.member for door sides and frosted film of 3-M/ LG make of approved design pattern, shade and colour to glass panels including cleaning glass panels etc complete. All exposed T.W /beading surfaces to befinished in melamine polish . (Note: Incase of false ceiling, the vertical members to befixed with pucca ceiling butthe area of partition payable will be below the false ceiling only).	Sqm	0.56		

21	**P&F 12mm thick Toughened glass partition** with patch fittings at floor, top and side walls for full height Cabins, main entrance doors, infront of SWO counter and other locations as directed by engineer. The glass shall be Saint Gobain / Ashi/Modi while patch fittings shall be Godrej/ Ebco/ Dorma/ equiv. The glass panels shall be rigidly fixed to walls, floors and ceiling runners in proper alignment with powder coated tubular aluminum profile section at edges or else all edges of the glass are to be finished with mirror polishing. Cost includes frosted film of 3-M/ Avery Dennison make of approved design pattern, shade and colour to glass panels including labour, fixing transportation, wastage, cleaning etc complete.	Sqm.	14.66		
B	**FALSE CEILING WORKS**				
22	**Plain Gypsum False Ceiling**:- roviding and fixing of frame work made galvanized M.S.sections as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm lon. Fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of Engineer in charge including cost of painting the false ceiling with two coats of acrylic emulsion paint over a coat of putty.	*Sqm*	140.01		
23	**0.600mX0.600m (2'-0"X2'-0") Silhouette Grid False Ceiling:-** Providing and fixing in true horizontal level false ceiling grid system of **Armstrong World Industries/Insula/Daikin** etc. The suspension system shall be 2'-0"X2'-0" plain grid system with 15mm wide flanges main runners and cross tees to have mitred ends with "birds mouth " notches to provide mitred cruciform junctions. Mineral fibre Grid false ceiling: Providing and fixing metallic Grid Based False Ceiling, of MicroLook mineral fibre board acoustical tegular ceiling tiles of 15mm thk, preferably Armstrong RH-99 or equivalent of approved make, shade & thickness are to be laid over a 6 mm white flat tegular reveal grid of 600 mm X 600 mm size. The grid is to be made with a framework of powder coated GI tee sections of 0.35 mm thickness (Gypsteel Ultra make or approved equivalent) in a standard 15 mm silhouette profile. The silhouette framework shall have main runners at 1200 mm c/c and cross tees at 600 mm c/c, all of 42 mm size. The grid system is to be suspended securely from true ceiling surface by 4 mm dia. GI hangers and fitted with all necessary arrangements like wall angle, rawl plug, soffit cleat, etc.. The work is to be completed with all materials, accessories, labour, tools & tackles, and in strict conformity with manufacturer's specification & recommendations.. .(Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc., if any).	*Sqm*	29.74		

C	**FURNITURE WORKS**				
24	**Single Window Counters:** Providing and fixing in position 750 mm high single window counter with side credenza.The rate quoted for SWC shall consist of: a) Basic Structure: 19mm thick MR ply/ BB for Top (1500 x 825 mm), Front (1500x750 mm), Two sides and one middle member (each 825x750 mm). Design and detail of the counters shall be as per Bank's new uniform colour, layout & elevation policy, with curvature in front made of flexi ply. b) One drawer unit (at every 1500-1800 mm length of counter) of 400mm wide (clear internal size). The chest of Drawer units shall have two smaller draw of equal size (150 mm) on top and one bigger vertical filling drawer at bottom with autolocking push type locks (Godrej/Link) and "C" type SS finish handles. The drawers to be made out of 12mm thick MR ply at sides, bottom and rear, 19mm thick MR plywood at front side. c) One Side Table (Credenza) of size 1000x450x750)mm with shutter unit of 600mm, with 1 drawers and one openable shutter made with 19mm MR ply / Block Board with necessary hardware viz., ' W ' hinges, handles, locks, tower bolts, etc. Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand. d) The table and credenza top- exposed surfaces shall be cladded with 1 mm thick laminate of shade and pattern as directed by the Engineer-in-charge with 6mm Flexi Plywood in curvature (which should be achieved with a frame work of 50mm x 50mm sal wood frame to be fixed from the front modesty panel / apron and the bottom of this niche to have provision of cove lighting with LED strips) and other exposed surface to be finished with 1 mm thk laminate of approved make and shade as directed by EIC. e) All un-exposed surfaces shall be finished with 0.7 mm thick laminate of approved make and shade. f)Ebco/Godrej make telescopic sliding key board tray and a mobile CPU stand & foot rest 75 mm X 38 mm. Make: MR Ply/BB: Century / Green / Archid/ Sylvm, Laminate: Sunmica/ Century/ Green/ Merino/ NewMika/ Levin; Hardware Godrej/Ebco/ Hettich/Dorset as approved	Nos	3.00		
25	**Branch Manager Table:** Office table 6'x2'6"x2'6"along with side unit of 18"x39": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side credenza unit shall have one drawer unit (400x450x150mm) and one cup board with shutter. All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest & CPU stand. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be finished with 0.7 laminate. A 40mm drop shall be provided on customer side with 19mm BB and laminated. Edges shall be finished with teak wood beading 6mm thick polished for smoothness. Drawers shall be finished with lipping polished. Make: MR Ply/BB: Century / Green / Archid/ Sylvm, Laminate: Sunmica/ Century/ Green/ Marino/ NewMika/ Levin; Hardware Godrej/Ebco/ Hettich/Dorset as approved	Nos	1.00		

26	**Officer Table:** Office table 5'x2'6"x2'6"along with side unit of 18"x39": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side credenza unit shall have one drawer unit (400x450x150mm) and one cup board with shutter. All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest & CPU stand. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be finished with 0.7 laminate. A 40mm drop shall be provided on customer side with 19mm BB and laminated. Edges shall be finished with teak wood beading 6mm thick polished for smoothness. Drawers shall be finished with lipping polished. Make: MR Ply/BB: Century / Green / Archid/ Sylvm, Laminate: Sunmica/ Century/ Green/ Marino/ NewMika/ Levin; Hardware Godrej/Ebco/ Hettich/Dorset as approved	Nos	1.00		
27	**Associate table**: 4'x2'3"x2'6"along without side unit of 18"x39": Made with 19mm MR grade BB in table top, sides with one drawer unit (400x450x150mm) and one cup board with shutter. The side credenza unit shall have one drawer unit (400x450x150mm) and one cup board with shutter. All necessary hardware's, locks, handles, hinges, PVC KBT of approved make shall be provided including foot rest & CPU stand. Front modesty panel shall be 12mm MR grade ply. All exposed surfaces shall be finished with 1mm thick laminate. Inside surface of table and side units shall be finished with 0.7 laminate. A 40mm drop shall be provided on customer side with 19mm BB and laminated. Edges shall be finished with teak wood beading 6mm thick polished for smoothness. Drawers shall be finished with lipping polished. Make: MR Ply/BB: Century / Green / Archid/ Sylvm, Laminate: Sunmica/ Century/ Green/ Marino/ NewMika/ Levin; Hardware Godrej/Ebco/ Hettich/Dorset as approved	Nos	2.00		
	Grahak Mitra Table: Providing curved table of 1500x900x750 mm in curved pattern with table top made of 19mm th. ply and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm thk ply with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm thk laminates as per design of approved shade and the inner surface is finished with 0.7 mm thk laminate Quoted rates shall also include cost of polished teak wood moulding (finished 40x20 mm section) to edges of table. top: polished teak wood- lipping (6mm thick) to free edges of block board /plywood surfaces; approved drawer-slides, hinges and locks with keys in duplicate : other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers , foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be completed including all labour and material.	Nos	1.00		
28	**Storage:** Providing and fixing 750mm high and depth of 450 storage cabinet having minimum 2 filing cabinets made out of 19 mm thk. MR ply/block board. All exposed surfaces shall be cladded with 1 mm thick s laminates of approved make and shade except edges . Edges which shall be covered with 1mm thk PVC lipping as directed by the Engineer-in-charge and Cabinet Top is to be provided with 1mm thick laminate. All un-exposed surfaces shall be cladded with 0.7 mm thick laminate of approved make and shade storage cabinet should be complete in all respect as per the drawing and direction of Engineer-in-charge including all hardware and locking arrangements. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc.Make: MR Ply/BB: Century / Green / Archid/ Sylvm, Laminate: Sunmica/ Century/ Green/ Marino/ NewMika/ Levin; Hardware Godrej/Ebco/ Hettich/Dorset as approved	Sqm.	15.38		
29	**Running Table:** Providing and fabricating of running table top of size 2'-0"wide and a front drawer unit consisting 3 Nos of drawer units slides on telescopic slider made up of 19mm th.MR ply/BB with locking arrangement. The exposed edge surfaces are to be finished with 1.0mm th.laminates as per design of approved shade and the inner surface is finished with 0.7 mm thk laminate . Quoted rates shall also include PVC moulding of required thickness to edges of table., approved drawer-slides, hinges and locks with keys in duplicate , other necessary hardware and accessories including satin finish S.S handles. knobs and wire - managers, foot rest etc. of approved quality. It also include readymade keyboard of engineering plastic (KD 575 PMT/INNOFITT SYSTEMS OR Equvialent) .The keyboard is a pullout type, fixed to channels and screwed to below table top . The CPU stand is made up with 19 mm ply with laminate finish as per design. The work should be completed including all labour and material. Make: MR Ply/BBnate finish as per design. The work should be completed including all labour and material. c) O	Rmt.	1.50		

D	**DOOR & MISCELLANEOUS WORKS**				
30	**Flush Door Work:**Doors – semi glazed standard size 3' x 7 ': Providing and fixing partly glazed doors of sizes as shown in the drawing. The door shutter shutter made out of 35 mm MR grade flush door finished with 1mm laminate of approved brand and shade on each side and 4mm thk teak wood lipping on edges. The shutter will have partly glazed 8mm thk float glass incl. etching film of approved pattern and necessary TW wood beading etc mat polished with melamine polish of asian / ici , complete to match the aligned partition elevations designs, the rates are inclusive of cost of providing and fixing 125 mm heavy duty SS butt hinges @ 3 no. per door shutter, 1 no. door stopper per door shutter and hardware fittings tower bolts 200mmx10mm, aldrops ,handles upto 6" length etc of S.S. finish and all labour, materials, taxes, leads & lift to the place of work executed to the satisfaction of the Architect/EIC excluding cost of door closures, floor springs, long handles 300mm or above size and locks etc.	*Sqm*	7.16		
31	**Main Entrance Glazed Doors** – :Providing, fixing in position glazed entrance Double door OR Single door with patch fitting of approved make using 12mm thk toughened glass edge polished and frosted film of 3-M/ LG make of approved design pattern, shade and colour to glass panels including cleaning glass panels etc complete.. The Door to consist of Heavy Duty Floor spring (paid extra), Upper Patch, Bottom Patch, Lock Keeper Plate, Euro Profile Cylinder (EPC), "H" Type Handle 32 x 600mm, Corner Lock and the side fixed glass to have 2 Nos. Bottom Patch and 2 Nos. Upper Patch for each door to a neat finish etc., complete as per drawing and direction of EIC. Glass: Saint Gobin/ Ashi/Hardyn/Eqv as approved by Bank; Hardware Godrej/Ebco/ Hettich/Dorset as approved. Cost of floor spring shall be paid extra.	*Sqm*	4.55		

32	**Wicket gate/Flap doors**: Proving and fixing flap door shutter made out of 30mm thk MR grade ply of approved brandsfinished with 1mm laminate on both sides and 50mm x 50mm TW frame including all hardware fittings of S.S. finish, door stopper, door buffer, auto locking SS Knob , 2 Nos. SS 2 ball-bearing hinges, slide bolt all complete as per drawing, design, specification & direction of Engineer-in-charge. The rate shall include cost of all materials, labour, taxes, T&P, transportation, royalties etc. MR Ply/BB: Century (Sainik)/ Green (Eco Tech)/ Saburi (Scoutt)/ Wigam Ply/ Kajaria, Laminate: Sumnica /Century/Green/ Marino/ NewMika/ Kajaria; Hardware Godrej/Ebco/ Hettich/Dorset as approved	*Sqm*	4.70		
33	**Door Closure** : Providing and fixing Dorma/Dorset/Godrej equivalent approved make over head door closers in door with necessary fixtures and fittings etc.	Nos	3.00		
34	**Floor spring** : Providing and fixing Dorma/Dorset/Godrej equivalent approved make heavy duty floor spring (120 kg capacity) in entrance door with necessary fixtures and fittings etc.	Nos	3.00		
35	**Night latch lock**: Supplying and Fixing 48x80x100 mm size Godrej /Dorset/Ozone or eqv Night Latch for SWO Doors outside opening 7 lever with automatic dead locking system and 3 keys incl all latch assembly assesories	Nos	3.00		
36	**Cylindrical lock**: Supplying and Fixing a pair of Godrej /Dorset/ or eqv SS finish cylindrical knob locks of size 180x70x70 mm with 3 keys and automatic dead locking system	Nos	2.00		
37	**Mortise Lock**: Supplying and Fixing SS finish Godrej /Dorset/Ozone or eqv mortice lock made of high grade zinc alloy incl 2 nos door handles, 1 no striker plate,lock body and 3 keys . Ref model : NEH15-200 mm lock of godrej make.	Nos	2.00		
38	**Door Handle** : Supplying and Fixing SS finish 25 x 450 mm length H type door handles of Godrej /Dorset/Ozone or eqv make incl required assessories in pairs	Nos	2.00		

E	**PANELLING WORKS**				
39	**PLY Panelling:** Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under:- (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizantal and vertical), fixed rigidly on wall / columnns in perfect line, level and plumb. (ii) Panel Finishing:- Providing & fixing 9 mm thick approved make MR plywood to Aluminum framework finished with 1.00 mm thick appproved quality and shade laminate, using approved adhessive, in approved pattern & design, including providing grooves, decorative mouldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge. (iii) Providing approved quality, seasoned, full length, Teak Wood moulding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as direced by the EIC (iv) The rate should include cost of necessary hardware,making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the EIC (v) Applying 2 or more coats of melamine polish to exposed edges of panelling, moulded beadings etc. including preparation of surface, sealer coats etc.complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc.complete. (Note: Incase of false ceiling,the vertical members to befixed with pucca ceiling butth earea of partition payable will be below the false ceiling only). Make: MR Ply/BB: Century / Green / Archid/ Sylvm, Laminate: Sunmica/ Century/ Green/ Marino/ NewMika/ Levin	Sqm.	44.68		
40	**ACP Panelling** : Providing and fixing in place aluminum Composite panel cladding of approved quality, shade, colour, make (Euroband / Altobond / Alucobond etc.)per design, in flat or rounded shapes, perfectly in level / slope, line, and plumb, at all heights, over Aluminum frame and as directed by EIC. Panels shall be installed with accessories recommended by the Manufacturer, required hardware, silicon sealent (Dow Corning 789) masking tape, necessary scaffolding etc. complete in all respects. The support structure and aluminum frame shall be of 50mmx25mmx1.25mm angle cleats, weather sealants, rivets, GI brackets all as approved, using suitable bolts on structural steel work . Aluminum Composite Panels shall meet the following minimum specifications: Panels shall be exterior grade, 4mm thick (0.5mm – 3mm – 0.5mm) composed of Polyethylene Core sandwiched between two sheets of Aluminum of minimum 0.5mm thickness. The outer top skin shall be coated with KYNAR 500 PVdF or similar coating. The panel product shall carry a 10 years Warranty on weather durability, UV color fading, corrosion, chalking, weather damage and manufacturing defects and confirm to ASTM standards.	Sqm.	16.82		
F	**OTHER FURNISHING WORK**				
41	**Window Blinds:** Providing and fixing roller blinds of Vista/ Marble/ equiv as approved by engineer-in-chrage with colour and shade as approved along with all accessories	Sqm.	2.32		
42	**Writing Ledge:** Providing , fitting , fixing writing plat form at a height of 4' above floor level fixed to the wall made out of 19 mm MR block board with lamination 1 mm tk on top & hard wood beading polished . At least 4 nos vertical slip in chalan shelfs attached to wall over writing platform made out of min 4 mm tk acrylic sheets with 6 mm tk ply back up. Each chalan shelf will be of size 6" height , 6" wide .The entire unit will be complete in all respect including materials ,labor etc to the satisfaction of Bank.	Rmt.	1.00		
43	**Notice/Soft Board:** Providing soft board covered with approved fabric with wooden frame work and decorative beading for display drawings and documents,with locking arrangementof the sliding shutter made up of 8mm th. flot glass. The work should be done including all labour and material.	Sqm.	1.00		
44	**Cheque drop box / Suggesion box**: Supplying and erecting cheque drop box (overall size 450 mm x 300 mm x 750 mm) made. of 19 mm thick MR Ply and the curved portion at top made out of 90 mm x 90 mm C.Pteak wood section. A slit opening of 10 mm x 150 mm is to be provided at the top of the box. An openable shutter of 259 mm x 262 mm size made of 19 mm thick MR Ply is to be provided at 1.50 mm above finished floor level. All the exposed surfaces to be finished with 1 rnm thick laminate sheet of combination shade .Inner faces of surfaces to be finished with two coats of synthetic enamel paint of approved shade and quality over a coat of approved primer.Rate .to include cost of necessary hardware fittings e.g. brass hinges, lock, knob etc. of approved.designand quality.	Nos	1.00		

45	**12 mm thick Glass for Table Top:** Providing and fixing in position 12 mm thick clear float glass of approved make in table top with required etching of SBI emblem & border on the glass as directed and with machine polish finish edges. All glasses should be clean, beveled edges and machine cut and machine moulded . No extra payment will be made on this account. Allowable tolerence for glass thick- ness is + 0.3 mm.The glass shall be clear float glass and should be ap- proved by the Engineer in Charge. It shall be clear, float transparent and free from cracks, flaws, Bubbles or Vision defects. The float glass shall conform to the IS 14900.	Sqm	2.83		
G	**PAINTING WORK.**				
46	Finishing the wall surface, gypsum ceiling and other locations with two or more coat of 1.5 mm thick putty to the finished surafce of JK / Birla or Eqv. After site preparation by cleaning or peeling existing paint/ mortar, filling undulations , grooves etc including curing as required and required staging/ scaffolding work.	Sqm.	653.30		
47	Applying Priming coat for interior wall of approved brand (Asian paints / Berger / Indigo /Nerolac) as directed by the engineer in charge	Sqm.	653.30		
48	Applying two coats Wall painting with acrylic emulsion paint of approved brand (ref :Asian paints - Apcolite premium emulsion/ Eqv shades of Berger paint/ Dulux paint/ Nerolac) on new surface to give an even surfaces free from mortar droppings and other foreign matters with roller brush finish.	Sqm.	653.30		
49	Providing & fixing wallpaper in the walls as per the direction of Bank.(basic cost Rs 1100 per Sqm)	Sqm.	9.90		
50	Supplying wooden Dining Table of size (1200x1200) with 32mm top and each leg of 100mmx100mm with necessary support, complete in all respect.	Nos	1.00		
	Total cost excluding GST				

Note: The estimate has been prepared considering the scope of work for the banking hall only and exclusive of scope of work of ATM/E-Corner, if any etc.
GST to paid extra as applicable.