

TENDER & SPECIFICATIONS FOR PROPOSED INTERIOR & FURNISHING WORK'S AT STATE BANK OF INDIA, MINI RACPC AT MANDIDEEP (M.P)					
S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
	Interior Works :				
	Mode of Measurements : Area of exposed and finished surfaces will be measured.				
1	GYPSON BOARD FALSE CEILING :				
	Providing, making and fixing Gypsum Board False Ceiling :- 12.5 mm thick G.I. Perimeter Channels of size 0.55mm thick. G.I. intermediate channels of size 45mm from the soffit at 900mm centres with ceiling angle of width 25mm X 10mm X 0.55mm thick intermediate channel at 450-600 mm c/c Two coats of primer + two or more coats of plastic emulsion paint Note -Including all fittings,material, labour,cut outs required for light fixtures, Speakers, screws and joint paper/fibre tape etc. complete.	Sqm	110		
2	MINERAL FIBRE GRID TILE CEILING :				
	Mineral Fibre Acoustic Ceiling Tiles : Providing, making & Fixing at all heights & in spirit level, Acoustical Ceiling System @ Office areas with Armstrong, Gyproc or equivalent make mineral fibre acoustical suspended ceiling system as per Manufacturer's specification with pin-hole tiles, tegular edge with 24 mm exposed grid. The tiles should have Colour White, in module size of 600mm x 600mm x 15mm. with providing and fixing Hot dipped galvanised Steel suspension system Grid frame with butterfly clips, for laying of Acoustical Ceiling Tiles as per manufacturer's specifications. The grid should be laid on Armstrong/Gyproc or equivalent stitched True lock 24 TL exposed grid systems with 24 mm wide T-section flanges color white, the tile will be laid on frame work made of Armstrong Prelude 32 with 24 mm wide T - section flanges or of equivalent make, colour white having rotary stitching on all T sections i.e. the Main Runner, 1200 mm & 600 mm Cross Tees with a web height of 32 mm and 27mm ,25 mm respectively. The cost shall include all fittings and materials complete including proper installation and provisioning etc. The work is to be completed as per manufacturer's specification .	Sqm	75		
3	COVE IN CEILING				
	Same as above but providing, making and fixing Gypsum cove (inside height 150 - 200 mm and border 75 mm) to hide strip/cove light in ceiling or to act as pelmet for roller blinds on windows or for projector screen, etc.	RMT	80		
4	PVC CEILING FOR TOILET AREA				
	Providing and fixing PVC Ceiling with Framing for Toilet area in approved pattern as per drawing and directions etc. [For Toilet Area.]	SQM	20.0		
	PARTITIONS :				
	Rate to be included of all kinds of planes/levels, profiles and cut outs, etc. required for light fixtures, trap doors and ACs, boards, provision for light fittings and diffusers have to be made at no extra cost supported with metallic section etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC Works for cabling, AC pipe works, etc.				
5	FULL HEIGHT PARTLY GLAZED/ SOLID WOODEN PARTITIONS (INCLUDING DOOR) :				

S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
	Providing and fixing full height partly wooden, partly glazed/ Solid partitions- specifications (Measurement shall be taken up to finished partition level & not of frame work and sal wood member shall go up to slab/beam soffit) Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways 8 mm thk. Commercial plywood Termite & Borer proof from both the sides 1.0mm thick approved shades of laminate 5 mm thick float glass (for Partly Glazed Partitions) Etching as per approved design including 32mm partly glazed/ fluse door with teak wood Beading 1 mm lamination on both sides 8 mm plain glass, (for partly Glazed Doors) with Frame of 100mm x 50 mm, Note -Including all fittings,material, screw, labour etc. Complete.	Sqm	75		
6	12.0MM TOUGHNED GLASS PARTITION WITH PATCH FITTINGS WITH WOODEN BOXING TOP & BOTTOM				
	Providing and fixing at site 12.0mm toughened glass of size 1200mm x 2400mm toughened glass panels to be fixed with patch fittings at bottom and top, and the gap between the two glasses shall have neatly filled silicon sealant, to form a partition wall the cost shall include all materials, labour, lifting of glass panels upto Third floor and fixing the same at site including transportation, breakage all labour, contingencies etc complete	Sqm	15.00		
7	LOW HEIGHT PARTITIONS WITH / WITHOUT GLASS :				
	Providing and fixing Half Height (approx-1200 mm ht.) partitions. Aluminium Frame Size -50mm X 50mm X 1.60 mm thick 450/600 mm c/c both ways(Horizontal/Vertical) 8 mm thk. Commercial plywood Termite & Borer Proof from both the sides 1.0mm thick approved shades of laminate, 12.00 mm thick float glass Etching as per approved design wicket gate wherever required with Godrej Night latch Note -Including all fittings,material, SS hinges, SS tower bolts screw, labour etc. Complete. (Making provision for items like softboards, white boards,etc. as & where required.	Sqm	35		
	PANELLING WORKS (WALLS , COLUMNS, ETC):				
	Rate to be included of all kinds of levels/planes, profiles and cut outs required for elevation and fixing of light fixtures, trap doors and ACs, provision for light fittings, boards and diffusers have to be made at no extra cost supported metallic sections, etc. suitably fixed all complete as per drawing and direction. ii) The contractor must co-ordinate with electrical & AC contractor for cabling, AC pipe works, etc.				
8	WALL/COLUMN PANELLING				
	Providing, making and fixing single skin paneling (Using 8 mm thick Commercial plywood), plain and/or curved in profile, on walls, front facia, boxing for rolling shutter, and/or columns and/or glazing soffits at various parts of the premises, upto 3 mt height and boxing of 0.10 – 0.45 mt. ht., as required, made out of 25 x 25 x 1.0 mm thk weighing 0.467 kg/rmt aluminum frame, vertical and horizontal sections placed at 450 mm c/c both ways or less as per site condition and finished with 6 mm thick Commercial plywood shall be fixed over the frame (either in one plane or at different levels) finished <u>with 1mm thick decorative laminate of approved made and shade</u> (in one or multi colour) shall be fixed with proper adhesive as directed. Top of the paneling edges / is to be provided with laminate or teak wood decorative beeding of 35mm x 20 mm finished with polish/painting as directed.	Sqm	130		
9	CABINET FOR ELECTRIC PANEL :				

S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
	Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thk MR grade plywood. All visible surfaces shall be laminated with 1 mm thick Laminate on external surfaces of approved make and shades & painting the internal surfaces with 2 or more coats of synthetic enamel paint, including providing teakwood lipping of size 20 x 6 mm on edges. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or ebco lock. (Measurement area = Measurement to be taken for the front surface area of the cabinet).	Sqm	3		
10	MAIN DOOR – TOUGHNED GLASS				
	Providing, making and fixing Thoughend Glass Door:- 12mm thk single/double shutter toughened glass doors, Including Floor springs make Hardwvn/ozone/Dorma or equivalent set, Upper patch, lower patch, lock key plate, provision of locking system, etc. One set of 25 mm dia S. S. brush finish pull handles (approx. 300mm length) "C" shaped, of appoved make Including Etching pattern, Note- Including, labour, transport, material, delivered and placed in position at site of work.	Sqm	9		
11	FLUSH DOOR / PARTLY GLAZED DOOR WITH FRAME				
	Providing, making & Fixing of partly Glass/ Flush door at site,-32 mm thk flush door with teak wood Beading at Edges 1 mm lamination on both sides 8 mm plain glass, (for partly Glazed Doors) The cost shall include Frame of 2nd class BTC/ Teak wood Frame of 100mm x 50 mm, Including all fitting like Mortice lock with 2 nos Handels , S.S. 125Mm Heavy duty Hinges 3 Nos. Door stoppers, 2 Nos Tower Bolts 200mm Note- Including all materials, labour, transport, taxes, delivered and placed in position at site of work.	Sqm	2.1		
	FURNISHING WORKS :				
	Providing multidrawer Godrej or Ebco single lock and approved brass handle for each drawer. Providing circular holes in table top for cables with PVC cable managers of 65 mm dia and cap. On the left side platform at bottom for CPU.The bottom compartment made up of 18mm thick. Commercial plywood. The exposed edges of the plywood to be provided with TW lipping of size 20x6 mm duly polished. One M S powder coated keyboard tray with mouse tray as manufactured by ebco (KBTM 45) or EGL (KBT-M-001) including sliding channel as per manufacturers specification to be provided below the working platform.				
	TABLES :-				
	Providing and supplying table detailed below : 1.-18 mm thick Commercial Plywood 2.- 1 mm thick laminate on external surfaces and 0.8 mm thick lamination on internal surfaces of approved make 3.- TW half round beading of sect 20 x 12 mm duly polished 4.- Drawer unit of width 350mm (clear internal), consisting of set of 3 nos. of drawer. 5.- Drawer made of 18 mm thk. Commercial Ply wood for the front and rear 12 mm commercial Plywood for sides and 6mm thk Commercial ply for the bottom sliding & teak wood beading of sect. 20 x 6 mm 6- EBCO Sliding Telescopic Rail +M S powder coated keyboard tray with mouse tray. Note all fittings, fixtures, locking arrangement, handles, etc. Complete.				
12	EXECUTIVES AGM TABLE :	Nos.	1		
	same as above but providing and supplying Executives Branch Manager of size -1.80 m x 0.90 m x 0.75 m ht.				
13	OFFICER / RELATIONSHIP MANAGER/ AUDITOR TABLES :	Nos.	10		
	same as item above but providing and supplying Officer / Relationship Manager/ Auditor Tables of size 1.65 - 1.50 m x 0.75 m x 0.75 m ht.				

S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
14	COUNTER : Counters : same as above item & Following specifications and per dimensions specified:- a. Size- 1500mm - 1350mm x 900mm - 800mm x 750mm height. The top drawer to have cash separation arrangement. b. 18 mm thick Commercial Plywood c. 1 mm thick laminate d. The table edges shall be double thick, outside surface shall be curved using 3 layers of 6mm flexible plywood e. Finished with 1 mm thick Plain or Textured Laminate Hidden areas like inside of drawers, cabinets, finished with 0.8 mm white laminate.including all fitting labour, material etc complete.	Rmt	1.5		
15	WALL MOUNTED WRITING DESK : Providing and fixing half round / rectangular customer voucher holders writing counter of width 900 mm and maximum depth 450 mm fixed to be wall or partition at a height of 1050mm made of 18 mm thk. Commercial plywood and 12 mm thick glass top, and sides and edges shall be finished with 1 mm thick plain or textured laminates including inlay etc if required, pigeon hole arrangement of min. 150 mm height and as directed . The cost shall be completed with lippings, mouldings, fittings,and accessories etc as per specification. as per the drawing and instruction given by the Bank Engineer.	Nos.	1		

S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
	STORAGES / CREDENZA :				
16	OFFICER STORAGE/SIDE CREDENZA/BACK CREDENZA : Providing, making and placing in position Side Credenza storage:- Size 375mm depth, height of 750 to 900 mm 18 mm Commercial grade plywood construction with 6mm thk. Commercial grade plywood backing complete. 2 no. of 125 mm deep drawers, equal size (min. 400 mm) wide wide on upper side and below to drawers, the cupboard unit shall be with openable shutter & adjustable shelf all along the full width of the credenza. 4- All drawers shall be fitted with telescopic channels and locking arrangement laminated with 1 mm thick plain external surfaces and 0.8 mm thick white lamination on internal surfaces Note- SS Hinge, SS handles, magnetic catchers Godrej or ebco lock & brass handles all approved make etc.	Sqm	25		
	GLASS WORKS :				
17	TOUGHENED GLASS FOR TABLE TOP Providing, making and fixing Toughened Glass :- a. 12mm thick toughened clear float glass b. Fixed with " D " brackets/ SS fittings as required. c. Etching film to be done as directed Note-The cost to include all materials, labour, hardware etc.,	Sqm	10		
18	DROP & COMPLAINT BOX : Providing & fixing at site drop & complaint box of size 300 mm x 400 mm to be made up of 1st class steam beach wood frame of size 25 mm x 25 mm wooden section, front 6 mm thk plain glass. The boxes shall have 12 mm py with approved shade of laminate and lockable shutter as per design 7 drawing, etc. complete.	Nos.	2		
19	NOTICE BOARD : Providing & fixing at site notice board of size 3' x 2' to be made up of kail/pine wood frame of size 2" x1" wooden section with 5.0mm plain glass The Notice board shall have 19.0mm soft board lining at back with approved shade of cloth, and lockable shutter strictly as per the design & drawing etc complete.	No.	2		
20	ETCHING FILM Providing and fixing at site approved design & pattern of etching film to be 3m 7725--325 Pressure sensitive film for permanent graphic fixed at site over the glazed area as per the given design & drawing including all materials, wastage etc complete.	Sqm	25		
21	Providing and fixing Door closers on doors of make Everite/Ozone/ Hardwyn/ Dorma or equivalent upon approval including all packing, levelling, etc. as required.	Nos.	6		
22	SOFA/SETTY Providing, making and fixing in position sofa set with side arms made for best quality badam/hillock wood framework and legs fitted with rubber nylon shoes fixing with 8mm thick commercial ply back side. Providing 150 mm thick high density (min 40) foam rubber of approved quality to seat of zigzag spring of approved quality over 12 mm thick phenol formaldehyde bonded approved quality commercial ply and 50 mm thick foam rubber of approved quality, density mini. 32 to back covered with upholstery of rate not less than Rs. 450/- per mt. finish of approved quality materials including polish finish complete of approved quality and make selected by the Engineer in Incharge. Rate inclusive of cost of material, transportation, loading/unloading, labour tools & tackles up to any lead and lift etc.Measurement : no. of seats	PER SEAT	13		
23	CORNER TABLE Providing at site Corner table as per design Made up of 18 mm thick Commercial Board 12.0mm thick Top Glass 1.0 mm thick laminate. Including All material , Labour etc Complete.	Nos.	2		
24	CENTER TABLE				

S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
	Providing at site Center table as per design Made up of 18 mm thick Commercial Board 12.0mm thick Top Glass 1.0 mm thick laminate. Including All material , Labour etc Complete.	Nos.	1		
25	ACP PANELING WORKS : Providing and fixing in position Aluminium Composite Panel (ACP) on wall, boxing, shutter panelling with framing:- 1.-M.S. Tube sections of min. 50 mm x 25 mm and 16 gauge, @ 600 mm c/c or less. 2.- thickness of 3 mm minimum. Alubond / Eurobond / Fujibond / Alcobond or equivalent Note- The cost shall include all fittings, scaffoldings, chase making, lifting, cutting, on site adjustments, plaster repairing, etc. complete.	Sqm	20		
26	ROLLER BLINDS : Providing & installing Roller Blinds of Trac / Vista or equivalent, 100 mm wide, in two colours, of medium range fabric (synthetic material), of approved shade and colour, pull cords shall be 1.7mm dia. Braided nylon with a core of rayon threads. The blinds shall be operate able in any direction with a flight upto 180 degrees and can slide to one side for opening purposes. All metal parts shall be corrosion resistant and rotating parts shall be self lubricating. The fixing of the top rail shall be with special GI brackets at approx 1meter c/c. complete as directed by the SBI	Sqm	25		
27	DISPLAY UNIT WITH FRONT 8.0MM GLASS SHUTTERS Providing & fixing at Display units 12" deep to be made up of 18.0 mm. Strictly as per the given design BWP ply with verticals & top, to be finished with matching shades of 1.0mm thick laminated finish having front 8.0 mm thick plain glass sliding shutters, all inside surfaces shall have 1.0 mm thick approved shade of matching laminates with teak wood/ wooden beading on all edges & SS handles with horizontal & vertical shelves as per the given design & site requirement strictly as per the given design The cost shall include all materials,locks, catchers, all labour etc complete.	Sqm	5		
28	MURALS/ PAINTINGS Providing and fixing at site wall paintings/ Murals as per the approval to be fixed at site, with necessary framing, including all labour, cost of transportation cost of Mural etc complete	SQM	2.0		
29	PLANTERS Providing and fixing at site decorative planter 400mm wide x 400-600mm in height and length as per design & drawing, to be made up of 19mm thick BWP ply finished with 1.0 mm thick laminate of approved colour standard make , including cost of Artificial plants, G.I Trough, sand & Marble Stone pieces etc complete strictly as per the drawing. With provision for providing different colour laminated skirting/ design as per drawing.	Nos	6.00		
30	12 MM GLASS SELF Providing and fixing at site 12.0mm thick toughened glass shelves to be fixed at site with necessary SS Brackets including all materials, round edged etc complete.	SQM	5.0		
31	WOODEN OPEN SELF Providing and fixing at site wooden open self as per design to be fixed at site with necessary fitting including all materials,labour etc complete.	SQM	5.0		
32	ACRYLIC/ SS LOGO & TEXT ON PARTITION. Providing and fixing SBI Acrylic Logo on partition including all material, labour, Fitting etc complete.	NOS	1		

S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE	AMOUNT
	PAINTING WORKS :				
	Rates to include cost of all materials, labour, curing, tools & machinery, transportation, scaffolding, ladders and all incidental and operational charges, at all heights, etc., complete and as directed by SBI. All glasses, surfaces to be cleaned of the paint marks/drops due to work/splashes.				
33	PLASTIC EMULSION PAINT :				
	Providing & applying Plastic emulsion paint on walls, ceiling, etc. Removing, scrapping & cleaning the existing color wash/distemper/oil bond distemper / plastic/ luster etc. paint by scrapping, washing and scrubbing and applying Birla putty nor equivalent. The surface shall then be allowed to dry for atleast 24 hours. It shall be then sand papered to give a smooth & even surface. Holes shall be filled with BIRLA putty, made with plaster of paris. Then first coat of primer to be applied. After this necessary leveling shall be done with putty and second primer coat shall be applied. The plastic emulsion paint of approved shade and make shall be applied in minimum 2 coats (finishing paint) including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete as per the instructions of the Bank / SBI.	Sqm	35		
34	ENAMEL PAINTS TO DOORS, WINDOWS, GRILLS, METALLIC SURFACES, WALLS :				
	Providing & applying Enamel Paints to Doors, Windows, Grills, Metallic Surfaces, walls, etc. Removing, scrapping & cleaning the existing enamel paint on doors, windows, grills, metallic surfaces, etc. paint by scrapping, sand papering and scrubbing. Then first coat of primer to be applied. After this necessary leveling shall be done with putty & second primer coat shall be applied. The enamel paint of approved shade shall be applied in minimum 3coats (finishing paint) including scaffolding, cleaning the floors, fittings, furniture's, ladders, glasses, removing of debris out of the compound etc. complete as per the instructions of the SBI. (The grills, metallic surfaces, etc. shall be finished with after scrapping, applying red oxide & finish with minimum 2 coats of enamel paint in two different shade).	Sqm	50		
	TOTAL AMOUNT FOR INTERIOR WORK				
35	COMPACTORS				
	<u>Providing and fixing Compactors as per given Specification in Below .</u>				
	Parameter- Specification				
	Height-2250 mm				
	Depth-450 mm (single) / 800 mm (double)				
	Width-915 mm per bay				
	Sheet Thickness-22 SWG CRCA steel				
	Shelf Load Capacity-60–70 kg UDL				
	Wheels-128 × 40 mm steel cast, pillow block bearings				
	Drive-Sprocket & chain, PU handle				
	Lock-6-lever IS 729:2021				
	Finish-Powder-coated, 40–45 micron film				
a	1 4 BAY MS4 MC SFS Unit with track+Additional	NOS	2		
b	2 4 BAY MS4 MC SFM Unit with track	NOS	2		
c	3 4 BAYMS4 MC DFM Unit with track	NOS	7		
d	4 1 BAY MS1 MC SFS Unit with track+Additional	NOS	1		
e	5 1 BAY MS1 MC SFM Unit with track	NOS	1		
f	6 1 BAY MS1 MC DFM Unit with track	NOS	2		
	TOTAL AMOUNT FOR COMPACTOR				