N.O.W. - REMOVING, REPAIRING, TESTING, INSTALLATION & COMMISSIONING OF EXISTING FAULTY DRY TYPE TRANSFORMER OF 500 KVA 11KV/433V INSTALLED AT STATE BANK OF INDIA MAIN BRANCH, CHANDIGARH

BILL OF QUANTITIES (ELECTRICAL INSTALLATION)

S. No.	Item	QUANTITY	Units	Rate	Amount
1	**SUB HEAD 1 (REPAIR WORKS)**				
1	Replacement ,Supply, Testing, fixing and commissioning of 11 KV / H.T Side Coil glass covered copper winding i.e 310 Kg in weight (approx) complete in all the aspects for Y Phase of the Faulty Dry Type Transformer.	1.00	Job		
2	Replacement ,Supply, Testing, fixing and commissioning of 433 V / L.T Side Coil glass covered copper winding i.e 190 Kg in weight (approx) complete in all the aspects for the Y Phase of the Faulty Dry type Transformer	1.00	Job		
3	Refurbishing,Testing,fixing and commissioning of 11 KV / H.T Side Coil glass covered copper winding and 433 V / L.T Side Coil glass covered copper winding complete in all the aspects for the R and B Phase of the Faulty Dry type Transformer	1.00	Job		
4	Supply, Testing, fixing and commissioning of of new high glass dry type insulation material. i.e Glass Sheet , Glass Tape , Glass Sleeves & Other material	1.00	Job		
5	Painting of Body inner and outer side of transformer complete in all aspects.	1.00	Job		
	TOTAL SUB-HEAD -1				
	SUB HEAD 2 (BUY BACK)				
1	Removal and buy back of old Copper winding on H.T Side and L.T side complete in all aspects.(approx 500Kg)	1.00	Job		
	G.S.T SHALL BE PAID EXTRA AS APPLICABLE				
	TOTAL SUB-HEAD-1 **(A)**				
	TOTAL SUB-HEAD-2 **(B)**				
	FINAL AMOUNT OF WORK (A-B)				
1	**G.S.T SHALL BE PAID EXTRA AS APPLICABLE ON TOTAL SUB-HEAD -1**				
2	**Transformer Testing Report is to be submitted from government approved A-class transformer Contractor Works.**				
3	**Transformer Repair Defect Liability Period shall be for 12 months as per Tender Terms & Conditions**				

SIGNATURE OF FIRM'S REPRESENTATIVE WITH SEAL