PRICE BID FOR INTERIOR FURNISHING WORKS OF MERCY COLLEGE BRANCH (NEW PREMISES) RBO-IV PALAKKAD

Sl.No	DESCRIPTION OF WORK	Qty	Unit	Rate	Amount
	SINGLE WINDOW SYSTEM : CORIAN TOP				
1	Providing and fixing of single window system without partitions as shown in drawings comprising of each counter size 1600 length or as per detailed drwing attached. Counter and writing top at front with 1000 mm width at 750 mm height. The top and the side supports shall be fixed with 19mm plywood (IS 303 grade) of approved make with curved bend in front modesty as per drawing and fixed with white corian top of 6 mm thick of approved brand. The front vertical portion of the counter is to provided with aqua blue shade of saint gobain glass 8 mm thick upto a height of 40 cm from the floor level. 12 mm thick clear float galss with etching fixed with SS D Brackets fixed at front (600mm) above the counter (height as per drawing). Modesty panel fixed with 12 mm thick toughened glass of aqua blue shade (Saint Gobain or equivalent) and height upto partition height (120cm), fixed with D Brackets. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm hight and 600 mm deep made of 18 mm ply wood (IS 303 grade) at bottom, sides and front with necessary lipping, telescopic drawer slides, locking arrangements , 100 mm long brush finish ss handles etc complete. Top most cash drawer should be arranged with provision for compartments of various denominations with 8 mm thick plywood (IS 303 grade). This drawer has to be provided with automatic lock. Key board tray of 600 x 350 mm size made of 18 mm thick plywood (IS 303 grade) finished with 1 mm laminate and MS wire manager of 50 mm dia of approved quality. Foot rest cum CPU stand of 1150 mm x 450 mm size with 18 mm thick plywood (IS 303 grade) finished with 1 mm thick laminate to shape as shown in the drawing. All the internal and external exposed surfaces including inside of drawers to be finished with 1 mm thick laminate . All exposed edges of plywood to be fixed with 2 mm thick matching edge banding. **12 mm thick clear float galss** with polished edges to be provided for table top as per the direction of engineer in charge	9	RM		
2	Single window system (With Out Front Glass). Specification same as im no.(1) but without front glass.	2	RM		

3	LOW HEIGHT PARTITION FOR SINGLE WINDOW SYSTEM:Providing and fixing of Low height partitions for Single window system of 1200/1350 mm height from finished floor level, as per the drawing. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL/ JINDAL make as internal frame structure vertically at about 60 cm centres and 3 nos horizontally of the same size of frame at floor level, 750 mm and at 1350 mm level fixed in position. 8 mm plywood (IS 303 grade) both sides of frame work finished with 1 mm laminate of approved color and shade with grooves on both sides upto 800 mm height. top of the partition finished with laminate of 1 mm thick. Clear float glass of 12 mm thickn ofapproved band with etching shall be fixed with SS D Brackets for a height of 500 mm above the solid partition. Partition on rear similar to side partition, but solid partition. One door shutter for each cabin for 680 mm width and 1350 mm height, similar to door shutter item, fitted with Godrej night latch at 500 mm from floor level, openable inside the cubicle shall be provided. **All exposed edges of plywood partitions shall be finished with with 6 mm thick HDHMR board lipping , glued and mechanically fixed with PU paint finish of approved shade.**	51	Sq.M		
4	Custom Made Low Height Partition: for CO cabinProviding and fixing in position of custom made low height partitions of the height 1200/1350/1500 mm (900mm solid partition and 600mm glass above) as per drawing attached. Aluminium sections of size 50 x 50 x 1 mm thick of INDAL / JINDAL as internal frame structure vertically and 3 nos horizontally of the same section at floor level 900 mm level and at 1500 mm level. 8 mm plywood of approved quality finished with 1 mm laminate with grooves on both sides of frame work. Top of the partition finished with laminate and 10 mm thick glass with etching is fixed over the partition with SS D brackets including a door as per the specification for door shutter item with Godrej or equivalent mortice lock, tower bolt hinges etc. complete**.All exposed edges of plywood partitions shall be finished with with 6 mm thick HDHMR board lipping , glued and mechanically fixed with PU paint finish of approved shade.**	13	Sq.M		

5	Custom Made Full Height Solid Partition:Supply and set in position of custom made double skin full height partitions as per shape and size shown in the drawing. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level. Alternate vertical frames to be fixed firmly to the roof ceiling slab. **8 mm plywood (IS 303 grade)** on both sides of frame work from the floor level to 15 cm above false ceiling level finished with 1 mm laminate on both sides including necessary grooves and steam beach beedings. Measurement for the partition area shall be considered from floor level to false ceiling level only**.All exposed edges of plywood partitions shall be finished with with 6 mm thick HDHMR board lipping , glued and mechanically fixed with PU paint finish of approved shade.**	57	Sq.M		
6	Partly solid and partly glazed door:- Providing and fixing door shutter using 35 mm thick solid block board finished with 1 mm thick laminate on both sides with grooves fixed with 8 mm glass 600 x900 mm fixed with beech wood beadings above 900 mm . Each door shutter to be provided with 4 nos. 150 mm SS hinges, a pair of 300 mm long SS handles, tower bolts, hydraulic door closer mortice lock etc of Dorma or equivalent make. **The edges of the exposed ply wood shall be finished with 1 mm thick PVC edge band of approved shade.**	11	Sq.M		
7	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) Measurement will be taken only upto solid partition level above.	7	Sq.M		
8	Providing and fixing of fixed glass partitions with 12mm thick toughened glass using **PT** Standard fittings like PT 90/PT 92 of **Dorma or equivalent make** at the top and bottom including cutting, making holes in glass and fixing the fittings in floors, ceilings etc and making the same good with necessary screws including etching as per approved patterns.	44	Sq.M		

9	Gypsum Board False Ceiling: Providing and fixing of M/F suspended false ceiling with G.I frame work and 12.5 mm tapered gypsum board panels to form grids of 45.7 X 122 cm as per manufactures specification including provision for stepped shaped ceiling for lighting trough comprisingFrame work of intermediate channels (M.F.T) at 122 cm centers along one direction M/F ceiling section MF5 at 45.7 cm center along other direction. Perimeter channels (MF 6A) along walls alround perimeter side of the ceiling. The intermediate channels suspended from ceiling,through strap hangers 25 X 0.5 mm (MF 8)at 122 cm centers connected to soffit cleats p534 (27 X 37 X 25 X 1.6mm) the cleats connected to ceiling through metal expansion rawl plugs 1/2" dia and 17/16" long with additional channels (MF 6A)for light fittings, air conditioners Ducts,vertical drops, offset etc. 12.5mm thick gyp board with tapered edges fixed to underside of suspended grid with 25 mm screws including 2 coats of plastic emulsion paint of approved color and over a coat of putty and a coat primer etc, complete.	321	Sq.M		
10	Providing & Fixing of Mineral Fibre Acoustical Suspended Ceiling System with 15mm Tiles and Exposed GRID. The tiles should have Humidity Resistance (RH) of 90% - 99%, NRC 0.5, Light Reflectance ≥87%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Colour White, Fire Performance UK Class 0 / Class 1 (BS 476 pt - 6 &7) in module size of 600 x 600 x 16mm , suitable for Green Building application, with Recycled content of 30% - 45% .	12	Sq.M		
	The tile shall be laid on Microline / Silhouette profile grid system with 15mm - 16mm white flanges incorporating a 6mm central reveal in white/black colour and with a web height of 38mm and a load carrying capacity of minimum 8 Kgs/M2 & minimum pull out strength of 100 Kgs. Microline / Silhouette, Main Runners & Cross Tees to have mitred ends & “birdsmouth” notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per M2 and need to be installed with Suspension system as per manufacturers details.				
	The Instalation to comprise main runner spaced at 1200mm centres securely fixed to the structural soffit using US Boral / Gyproc / Armstrong suspension system (specifications below) at 1200mm maximum centre. The First/Last suspension system at the end of each main runner should not be greater than 450mm from the adjacent wall.				

	Flush fitting 1200mm long cross tees to be interlocked between main runners at 600mm centre to form 1200 x 600 mm module. Cut cross tees longer than 600mm require independent support. 600 x 600mm module to be formed by fitting 600mm long flush fitting cross tees centrally between the 1200 mm cross tees. Perimeter trim to be Wall angles of size 3000mm x 19mm x 19mm, secured to walls at 450 mm maximum centres.				
11	BM Table (Branch): Providing and fixing Branch Manager's table of size 2000 x 800 X 750 mm high to detail as shown in drg. Comprising table top out of 18mm thick Plywood (IS 303 grade) finished with 1mm thick laminate of approved color and brand and side edges with 2mm thick band strip.12 mm glass with polished bevelled edges to be provided for the table top with necessary wire manager. Foot rest cum CPU stand with 18 mm plywood (IS 303 grade) finished with 1 mm laminate. All the internal and external exposed face of plywood (IS 303 grade) to be finished with 1 mm laminate and all the exposed edges of ply to be provided with 2 mm matching edge band. Keyboard tray 600 x 350 mm made of 18 mm thick plywood (IS 303 grade) finished with 1 mm laminate and 50 mm dia MS wire manager of approved quality. One set of 3 drawers of equal height, inside a drawer box of 450 mm width 712.5 mm height and 600 mm deep made of 18 mm thick plywood (IS 303 grade) at bottom, sides rear with necessary lipping telescopic drawer slides, locking arrangements, 100 mm long SS handles etc. complete. Additional horizontal support to be provided below the table top in order to avoid sagging.	1	No.		
12	Side Tables For BM: Providing and fixing side unit for Manager / BM table to detail as per drg. of size 1200mm x 600mm x 750mm made of 18 mm Plywood (IS 303 grade)finished with 1 mm laminate having covered with 2 mm matching edge band Two shutters fixed with Box Type hinges, Locking arrangement, 100 mm long S.S brush finish handles, tower bolt, ball catch etc,.complete. 12 mm glass with polished edges to be provided for the table top. All external internal exposed faces of Plywood to be finished with 1 mm laminate and the exposed edges of ply to be provided with 2 mm thick matching edge band.	1	No.		
13	Providing and fixing Officer's table of size 1500 x 750 X 750 mm high to detail as shown in drg. as per specification in item no.11 above. 12 mm thick glass with polished edges to be provided on table top.	1	No.		

14	Providing and fixing cash officer's table of size 2200 x 800 X 750 mm high to detail as shown in drg. as per specification in item no.11 above. 12 mm thick glass with polished edges to be provided on table top. **Additional horizontal support to be provided below the table top in order to avoid sagging.**	1	No.		
15	Side Tables For OFFICER - Providing and fixing side unit for Officer table to detail as per drg. of size 1000 x 450 x 750 mm as per specification in item no.12 above	1	No.		
16	Side table for counters - providing and fixing side unit of size 1500 x 450 x 750mm for counters as per spcification in item no.12 above	7	No.		
17	Low Level Storage :Providing and fixing low level storage to detail as shown in the drg. Size about 450mm wide, 750mm/90mm/ 1200/1350 mm high with openable shutters in front approx 450 mm wide fixed with box type hinges, locking arrangements 150 mm SS handles and tower bolts made of 18 mm Plywood (IS 303 grade) for top, bottom, rear sides and One intermediate member finished with 1 mm laminate of approved colour and brand and all the edges and sides fixed with matching 2 mm thick pvc band strip. All the exp[osed internal and external faces of plywood to be finished with 1 mm thick laminate of approved colour and shade. Measurement shall be taken for the front elevation area.	24	Sq.M		
18	Providing and fixing wall mounted writing desk of 1350 x 450 mm in 19 mm plywood (IS 303 grade) with 1 mm laminate on all exposed surfaces. Top portion is to be provided with 12 mm clear glass with polished edges, with shelves to keep slip books including frosting of approved design and exposed edges to be fixed with TW beeding with melamine polish. A provision to be made for keeping Banks printed Broachers for public etc complete.	1	No.		
19	Providing and fixing in position of Roller Blinds of approved Fabric (Fabric Cost - RS. 1,000/- per Sq. Meter) of Hunter Douglas / Mac / Vista make or approved equivalent of approved shade etc., as directed.	8.00	Sq.M		
20	Painting the walls/ ceiling with two coats of plastic emulsion paint of approved make and shadeover a coat of putty including cleaning the surface. The colour and shade shall be approved by the Bank prior to commencement of painting. **The paint shall be Low VOC (Volatile Organic Compound), green pro certified or equivalent. The Contractor shall submit the manufacturer's technical data sheet, VOC content certificate and green certification for approval before procurement and application.**	120	Sq.M		

21	Panelling with 3 mm thick aluminium composite panel of approved make and shade cut and bind using router machine and curved using roll over aluminium frame work not more than 600 mm c/c, with 50 x 25 x 1 mm sections of JINDAL/ INDAL as per site condition.	74.00	Sq.M		
22	Column/ wall Paneling: Providing and fixing columns/ wall panelling to detail as shown in the drawing with 18 mm thick plywood (IS 303 grade) finished with 1 mm thick laminate with necessary grooves, over the aluminium frame work. Anodised aluminium frame work with sections of size 50 x 50 x 1 mm thick of JINDAL/ INDAL @ 60 cm c/c vertically and horizontally at columns & wall ends and false ceiling level.	48	Sq.M		
23	Providing & Fixing 12mm thick polished toughened glass display stand for placing indoor plants, trophies ertc with SS angle support/ patch fittings etc complete as directed - 90x20cm	2	Nos		
24	Providing & Fixing 12mm thick polished toughened glass display stand for placing indoor plants, trophies ertc with SS angle support/ patch fittings etc complete as directed - 60x20cm	2	Nos		
25	Providing & Fixing 12mm thick toughened glass corner stand (with polished curved outer edge) stand for placing indoor plants, trophies etc with SS angle support/ patch fittings etc complete as directed - 30cm radius	2	Nos		
	Note: The contractor shall use only environmentally sustainable and green certified materials / products for all interior furnishing works, including but not limited to modular furniture, SWO counters, partitions, plywood, MDF/HDHMR boards, laminates, veneers, adhesives, paints, polish, sealants, gypsum boards, false ceiling materials, wherever green certified products are commercially available. Such products shall possess valid IGBC, Green Pro, or other equivalent certiifcations, acceptable to the bank. Copies of valid certificates shall be submitted for approval before procurement and installation.				
	TOTAL (Excluding GST)				
GST at applicable rates will be extra					