CIVIL WORKS FOR PAVEMENT OF COVERED PARKING SHED AT SBI STAFF COLONY, VIJAYNAGAR, JABALPUR

S No	Item Description	UoM`	Qty	Rate	Amount
1	Providing and laying hand packed Murrum of approved quality in layers not exceeding 15 cm including filling the voids, watering and compaction in complete as directed at site.	CuM	43.00		
2	Providing and laying 60mm thick faciory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	SqM	1860.00		
3	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge)	CuM	5.00		
	Amount (in Rs.) excl. GST				