STATE BANK OF INDIA
LOCAL HEAD OFFICE, GUWAHATI
PREMISES & ESTATE DEPARTMENT
GUWAHATI, ASSAM.

SHIFTING OF LHO DEPARTMENTS TO DISPUR BRANCH BUILDING

BOQ for Supply, Installation and Commissioning of Air conditioning system

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Excl. GST)	Amount (Rs.) (Excl. GST)
1	Supply of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split Ac having ISEER more than 5.2 with cordless remote and Copper Condensor Coil. **AC Make, Voltas/Bluestar /Daikin /LG/Hitachi** (For banking hall)	No.	5		
2	Supply of 2.0 TR Cassette type inverter air conditioners minimum 5 star rating with Copper Condensor Coil and refrigerant (R32 or R 410A), **(BTU per ton should be 12000) Indoor unit** ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. **Outdoor unit** comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. **AC Make, Voltas/Blue Star/Daikin /LG/Hitachi)**	No.	1		
3	Supply of 3.0 TR Cassette type inverter air conditioners minimum 5 star rating with Copper Condensor Coil and refrigerant (R32 or R 410A), **(BTU per ton should be 12000) Indoor unit** ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. **Outdoor unit** comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. **AC Make, Voltas/Blue Star/Daikin /LG/Hitachi)**	No.	2		

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Excl. GST)	Amount (Rs.) (Excl. GST)
4	Supply of 4.0 TR Cassette type inverter air conditioners minimum 5 star rating with Copper Condensor Coil and refrigerant (R32 or R 410A), **(BTU per ton should be 12000)** **Indoor unit** ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. **Outdoor unit** comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. **AC Make, Voltas/Blue Star/Daikin /LG/Hitachi)**	No.	18		
5	Installation charges of the **1.0/1.5 TR** Hi-Wall Split AC including supply of outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	5		
6	Installation charges of the **2.0/3.0/4.0 TR** Cassette Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	21		
7	**For 2.0/3.0/4.0 TR Copper Cassette type inverter air conditioners**: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages. Unit length of refrigerant pipe measurement consist unit length of each suction & discharge line	RM	410		
8	**For 1.0/1.5 TR Hi-Wall type split air conditioners:** Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages. Unit length of refrigerant pipe measurement consist unit length of each suction & discharge line.	RM	80		
9	**Additional Drain Pipe:** supply and fixing of 25mm UPVC drain pipe	Mtr.	200		
10	Supply and Installation of 4 KVA Stabilizer for 1.0/1.5 TR Split ACs	Nos.	5		
11	supply and fixing of Under deck insulation with 19mm thick class 'O' nitryl rubber	Sq mtr	1200		
	TOTAL-B (Excluding GST)				