

BOQ FOR FURNITURE WORKS OF VIP ROOMS AT SBILD CHHATRAPATI SAMBHAJI NAGAR

Sr No	Item	Unit	Qty	Rate	Amt
1	Providing and fixing of Wooden double Bed with non openable box of size 6.5 ft X 6 ft made with 18 mm thick plywood and 1.00 mica of approved make with designer headrest of appx. 1'6"- 2'X2.5" thick as per design approved by the bank. The rate shall include cost of required hardware, polishing to wooden beading, necessary transportation, execution of work at all height and locations including all lead, lift, wastage, statutory liabilities etc. complete job	Nos	5		
2	Providing and fixing of Wooden single Bed with non openable box of size 6.5 ft X 3.6 ft made with 18 mm thick plywood and 1.00 mica of approved make with designer headrest of appx. 1'6"- 2'X2.5" thick as per design approved by the bank. The rate shall include cost of required hardware, polishing to wooden beading, necessary transportation, execution of work at all height and locations including all lead, lift, wastage, statutory liabilities etc. complete job	Nos	5		
3	P & F false ceiling combination of gypsum and armstrong...as per approved specifications....complete job	Sqft	1020		
4	Providing and fixing in position wooden paneling to column / walls finished with laminate comprising as under:- (i) Framework:- Made out of 50 mm x 25 mm x 1.2mm thick extruded Aluminium hollow sections, placed not exceeding 600 mm centre to centre, bothways (horizontal and vertical), fixed rigidly on wall / columns in perfect line, level and plumb. (ii) Panel Finishing:- Providing & fixing 9 mm thick approved make MR plywood to Aluminum framework finished with 1.00 mm thick approved quality and shade laminate, using approved adhesive, in approved pattern & design, including providing grooves, decorative mouldings etc. as per Architectural drawings and as directed at site by the Engineer-in-charge. (iii) Providing approved quality, seasoned, full length, Teak Wood moulding 15 mm thick with adequate width as required at site, to all openings, cutouts etc duly polished with melamine polish complete as directed by the Engineer in-charge at site. (iv) The rate should include cost of necessary hardware, making cutouts / openings for electrical conduits / cables, Switch boards, AC ducts etc., including providing necessary wooden/aluminum section members support at cutouts, doors/windows openings etc. complete as per drawings and as directed by the Engineer-in-charge at site. (v) Applying 2 or more coats of wooden polish to exposed edges of panelling, moulded beadings etc. including preparation of surface, sealer coats etc. complete including wastage of material, if any, scaffolding for execution of work at all heights and locations etc. complete. Approved make:- (a) Aluminum extruded sections: Jindal, Hindalco or equivalent approved by the Bank. (b) Plywood:- Greenply, Century, Duro or equivalent approved by the Bank. (c) Laminate:- Greenlam/Century/Archid / Aerolam or equivalent approved by the Bank. (d) Adhesive: Fevical SH/Vamicol or equivalent approved by the Bank.	Sqft	855		
5	P & f Luggage table (appx. Size 5'X2') with 18 mm granite top double moulding made with 18 mm marine ply, 1.00 mm laminate from outside and 0.8 mm laminate from inside, lipping, etccomplete job	Nos	5		
6	P&F Study Table (appx size. 4'X2') as per approved specification and design approved by the bank, made with 18 mm marine ply, 1.00 mm laminate, wooden lipping, drawer with handle and lock, footrest, inside laminate....complete job	Nos	5		
7	P & F wooden wardrobe as per approved specifications with 18 mm marine ply, mica inside and 1.0 mm mica outside, with all accessories including handle, hinges, locks, latches, curtain rod, locker cabinet inside, polishing the edges, etc. The depth of wardrobe shall be 21".....complete job	Sqft	140		
8	P & Supplying mattresses for double bed (6" thick) as per approved make (Sleepwell, Duraflex, Curlon, etc) Basic rate Rs. 15000... complete job	Sqft	5		
9	P & Supplying mattresses for single bed (6" thick) as per approved make (Sleepwell, Duraflex, Curlon, etc) Basic rate Rs. 8000.... complete job	Sqft	5		

10	P & Applying plastic emulsion paint as per approved color and shade, minimum three coat after rubbing and cleaning the surface ...complete job	Rft	2565		
11	P & Applying putty as per site requirements and as per approved color and shade, minum three coat after rubbing and cleaning the surface ...complete job	sqft	2565		
12	P & Fixing Zebra rollar blind as per approved shade and color, Basic rate Rs. 130 per sqft....complete job	Sqft	120		
13	P & fixing 4 mm looking mirror in wooden frame on back side...complete job	Rft	50		
14	P & Fixing MS shed over balcony/window area with metro/designer sheet with sufficient MS frame as per approved design and color, painting, primer....complete job	Sqft	1600		
15	Salwage of old toilet items, flush door, etc	LS	5	-5000	-25000.00
			Sub Total		
			Discount if any		
			GRAND TOTAL		
				plus GST	

THE QUANTITIES CONSIDERED IN THE ESTIMATE ARE AN APPROXIMATE BASIS WHICH MAY VARY BOTH WAYS. THE CONTRACTOR SHALL HAVE NO CLAIM REGARDING THIS. BILL WILL BE PAID AS PER ACTUAL MEASUREMENT AFTER COMPLETION OF WORK SATISFACTORY.

<p>THE CONTRACTOR MUST VISIT THE SITE BEFORE QUOTING RATES. SO THAT THEY MAY FAMILIAR WITH THE MAKE AND MATERIAL USED AT SBILD. SIMILAR TYPE OF WORK HAD ALREADY BEEN DONE AT SBILD CSN. NOTHING EXTRA SHALL BE PAID AGAINST ANY WORK/ITEM. THE CONTRACTOR IF REQUIRED MAY PLEASE BE DISCUSS WITH THE ENGINEER INCHARGE OF THE PROJECT BEFORE SUBMITTING THEIR TENDER.</p>					
<p>FOR DETAILED SPECIFICATIONS AND MAKE OF MATERIAL, THE CONTRACTOR MUST SEE THE TECHNICAL BID BEFORE QUOTING RATES.</p>					