| | BOQ FOR ROOM RENOVATION WORK AT SBFI CHETANA, INDORE | | | | |
|---|---|---|---|---|---|
| **Sr. No.** | **Description of Work** | **Unit** | **Qty.** | **Rate ₹** | **Amount ₹** |
| 1 | Providing and laying Double charged vitrified floor tiles of approved make, size and shade, including tile adhesive, cutting, joint filling, laying, finishing and all necessary materials and labour, complete. (Make - Kajaria/Nitco) | Sq. Ft. | 2,000.00 | | |
| 2 | Providing and installing mixed gypsum board and PVC false ceiling, including necessary framework, suspension system, joint finishing, cutting and installation, complete as per approved design. | Sq. Ft. | 2,000.00 | | |
| 3 | Providing and fixing ceiling border/cove work, including necessary framing, supports, accessories and finishing, complete as per approved design. | Rft. | 800.00 | | |
| 4 | Providing and fixing decorative PVC louver wall panelling, including supporting framework, necessary accessories, cutting, fixing and finishing, complete. | Sq. Ft. | 1,300.00 | | |
| 5 | Preparing existing wall and ceiling surfaces, primer and approved-quality paint, including sanding, surface preparation and finishing, complete. Make Asian paints | Sq. Ft. | 7,000.00 | | |
| 6 | Preparing existing wall and ceiling surfaces, applying wall putty, complete. (Make JK white) | Sq. Ft. | 7,000.00 | | |
| 7 | Providing and fixing approved decorative laminate on the existing door shutter, including surface preparation, adhesive, edge finishing and labour, complete. Make Durian/AICA | Job | 10.00 | | |
| 8 | Removing loose or damaged grout from existing toilet tile joints and refilling with approved epoxy grout, including joint cleaning and finishing, complete. | Job | 10.00 | | |
| 9 | Providing and fixing Roller blinds for one window, including necessary brackets, operating mechanism, accessories and installation, complete. | Sq. Ft. | 300.00 | | |
| | **Total Amount** | | | | |

**PLUS GST**