STATE BANK OF INDIA
LOCAL HEAD OFFICE, GUWAHATI
PREMISES & ESTATE DEPARTMENT
GUWAHATI, ASSAM.

GORESWAR BRANCH, RBO-IV GUWAHATI RURAL

BOQ for Supply, Installation, Testing and Commissioning of Air-conditioners

Sl.No.	Description	UOM	Qty.	Rate (Rs.) (Excl. GST)	Amount (Rs.) (Excl.GST)
A	**High Side work: Supply of Machines**				
	Supply of 1.0 TR Capacity Hi Wall mounting 5-star (as per new rating in 2026) rated Inverter Split Ac having ISEER more than 5.0 with cordless remote and Copper Condensor Coil. **AC Make, Voltas/Bluestar / Daikin /LG/Hitachi** (For BM Cabin)	No.	1		
1	Supply of 1.5 TR Capacity Hi Wall mounting 5-star (as per new rating in 2026) rated Inverter Split Ac having ISEER more than 5.0 with cordless remote and Copper Condensor Coil. **AC Make, Voltas/Bluestar / Daikin /LG/Hitachi** (For BM Cabin)	No.	1		
2	Supply of 2.0 TR 5 star (as per new rating in 2026) Cassette type (12000 BTU/Ton) inverter air conditioners with Copper Condensor Coil and refrigerant (R32 or R 410A) Indoor unit ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. Outdoor unit comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. AC Make, **Voltas/Blue Star/Daikin /LG/Hitachi** (For Banking hall)	No.	6		
B	**Low Side Work: Installation & Commissioning work**				
1	Installation charges of the **1.0/1.5 TR** Hi-Wall Split AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	2		
2	Installation charges of the **2.0 TR** cassette AC including outdoor frame / stands to withstand the full load of outdoor units and making good all the damage.	No.	6		
3	**For 1.5/1.0 TR hi wall split type air conditioners:** Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	10		
4	**For 2.0 TR Cassette type air conditioners:** Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessaries and making good all the damages.	RM	60		
5	Supply and Installation of 4 KVA Stabilizer (90V to 290V) for 1.0/1.5 TR Split Acs	Nos.	2		
6	Supply and Installation of 5 KVA Stabilizer (90V to 290V)for 2.0 TR cassette Acs	Nos.	6		
7	Supply and Installation of addional drain water UPVC pipe for properly conecting to the drain point	RM	70		
GST will be extra as applicable.		**Total AMOUNT (excl. GST)**			