

(STATE BANK OF INDIA SURAT MAIN BRANCH, SURAT)					
PRICE BID (ESTIMATE)					
TENDER DOCUMENTS FOR INTERIOR & FURNISHING WORK					
AT SBI SURAT MAIN BRANCH.					
TENDER ID: AHMSAO2/26-27/42					
ARCHITECTS : SOPAN, 202,RIVER PALACE WING-B NANPURA SURAT-395001					
TELEPHONE NOS : 02612471302 (o) M: 09825117854					
E-MAIL : sopanrise@gmail.com, sopanssurat@gmail.com					
SITE ADDRESS : CHOWK BAZAR,SURAT					
BOQ – FURNITURE AND FIXTURE WORK , SBI SURAT MAIN BRANCH RBO 2,SURAT					
NO.	ITEM	QTY	UNIT	RATE	AMOUNT
Note :	Rate should be inclusive of material,labour,tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills				
	All rates are included of removing /dismantling of existing furniture /fixed partitions /ceiling etc as per site conditions and working facilities of branch ,disposal of debris from the premises within 24 hours,				
[A]	FURNISHING WORK				
1	SINGLE WINDOW COUNTER / CASH COUNTER SIZE 5'-0" X 2'-9" with White corian	9.50	RMT		
	Supplying, fixing and keeping in position single window counter complete as per design and drawing made out of 18 mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.				
	The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit with 18 mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following.				
[a]	size :				
	Description: L B Ht.				
	Writing Top 4'-9" 2'-9" 2'-6"				
	4 Drawers with				
	pigeon hole 2'-0" 1'-3" 2'-0"				
	Computer key Board with mouse				
	Supplying and fixing metal key Board of approved make in counter as per design and instructions.				
[b]	Working table top and edges shall be finished with 6 mm thick corian of DUPONT or equivalent approved make(shade as per selection) as per drawing and direction with all labour and material.				
[c]	Front Apron : 2 nos 6 mm thick flexy ply wood in round shape with 6 mm thick corian shall be provided at front as per design. All edges should be finished with corian of DUPONT make.or equivalent approved make				
[d]	Front pannel shall be finished with 3.50mm thick Teak veneer with PU Coating with necessary intermediate support and to be completed as per drawing				
[e]	Foot rest of 3" x 1.5" in C.P. Teak wood and CPU stand of 18 mm ply finished with 1 mm thick laminate of size 16" x 24"				
[f]	All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
[g]	All fittings like antique brass finish handle(as per selection) , Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make.				
[h]	Heavy duty telescopic full extension sliding channel of approved make shall be used in all drawers.				
[i]	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate(similar to veener tone) of approved shade etc. complete				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
[j]	Counter shall be made independent in Length of 5'-0" and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid (FOR DETAILS REFER DRG. NO- 1)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 6 mm thick approved shade(as per selection) of corian				
	2) Front Apron: Round corian and 3.5 mm teakwood venner finish as per drawings. 3mm ss pvd brush gold finish to be pasted on skirting with natural silicon.				
	3) Facing of Drawers: 3.50 mm thick veneer finish				
	4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate (similar to venner tone) of approved shade.				
[k]	Front Skirting shall be brush gold finish pvd on 2 .0 mm ss to be completed as per drawing				
[l]	3 mm thick ss pvd brush gold finish Emblem to be pasted with silicon on front pannel , to be completed as per drawing.				
					
1[b]	Providing and fixing 12 mm thick Toughened Glass partition on counter top, front side as follows.	6.50	SQMT		
	Providing and fixing 12 mm thick Toughened float glass with polished edges to be fixed with necessary antique brass finish brackets & support on wooden partition as directed with necessary cut out in glass. All edges of glass shall have Diamond cut polished edges as directed. [REFER DRG NO- 1]				
1[c]	Providing and fixing 12mm thick Toughened float Glass partition between Single Window counters as follows.	2.39	SQMT		
	12 mm thick Toughened clear float glass with polished edges shall be fixed with silicon and burma teak beading support on wooden partition as directed. All edges of glass shall be Diamond cut polished edges as directed complete. Wooden partition will be paid seperately. Maximum length and height will be measured for payment purpose, REFER DRG NO-1				
	TABLES				
2	MANAGER TABLE SIZE: 8'-0" X 3'-3" X2'-6" HT. with 3.5 mm thick Teak veneer with PU coating finish on front, sides & Edges and all other visible surfaces and 6mm thick corian(as per selection) on 40 mm thick top , etc complete as follows	1.00	NO		
	Supplying and installation of Table as per the following description : Size 8'-0" x 3'-3". Table top shall be made from 18 mm thick commercial ply wood with 3.50 mm thick Teak veneer with PU Coating with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Storage cabinet of 1'-4" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, antique brass finish Handle. Computer Key board of metal of approved make shall be provided. Exposed surfaces of the cabinet shall have Teak veneer with PU polish . Foot rest of 1 1/2" x 3" teak wood members shall be provided. All internal surface will have 0.60 mm thick balancing laminate similar to veneer tone.				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
	Apron (Modesty Panel) made from 18 mm thick ply wood finished with teak veneer PU Finish & burma teak moulding, ss pvd brush gold finish emblum as per drawing.				
	Table side made from 18 mm thick ply wood with 3.50 mm thick teak veneer with PU coating finish shall be provided with burma teak corner post,moulding as per drawing. Veneer to be provided on all visible surfaces.				
	Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing veneer on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long anique brass finish handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with lacquer				
	Table shall have stand for keeping CPU and metallic cable Manager shall be provided in table top. All exposed edges of plywood shall have veneer with smooth edges & corners				
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate similar to veneer tone ,of approved shade. Etc. complete.				
	All the surface without teak veneer / laminate / balancing laminate shall be lacquered polished of approved shade				
	As per drawing and instruction of Architect/Bank work to be Completed (FOR DETAILS REFER DRG. NO- 2)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 6mm thick corian (as per selection) on plywwod top total 40 mm thick ness.				
	2) Front Apron & Sides: 3.5 mm thick Teak Veneer with PU Coating and burma teak moulding,corner post as per drawing.				
	3) Facing of Drawers: 3.5 mm thick Teak Veneer with PU Coating				
	4) All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate similar to veneer tone.				
	Front Skirting shall be brush gold finish ss pvd on 2.0 mm ss to be completed as per drawing				
	3 mm thick ss pvd brush gold finish Emblem to be pasted with silicon on front pannel , to be completed as per drawing.				
					
2[e]	Same as above Item-no-2 but Size: 5'-0"x2'-6" with 4 Nos Drawer Unit with 3.5 mm thick veneer finish on all exposed surfaces	12.00	NO		
	1)Front Apron & Sides: 3.5 mm thick Teak Veneer with PU Coating and ss pvd brush gold finish emblum on front.				
	2) Table Top : 6mm thick corian (as per selection) on 25 mm thick top .				
	3)Front Skirting shall be brush gold finish ss pvd on 2.0 mm ss to be completed as per drawing				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
	3 mm thick ss pvd brush gold finish Emblem to be pasted with silicon on front pannel , to be completed as per drawing.				
					
4	GRAHAK MITRA TABLE OF 6'x 2'-3" Same as above item no 2 but Size 2'-3" wide . with storage unit in Table. All other exposed visible surface as per drawing and instruction of Architect/Bank For Grahak Mitra/Tech Mitra (Help Desk Table) Table top made from 18 mm thick ply wood + 6mm corian, 25 mm thick Apron (Front side) made from 18 mm thick ply wood +fluted teak finish panels. Both sides made from 18 mm thick ply wood +fluted teak finish panel. 2" thick Partition above working table top made from 18 mm thick+4 mm thick ply wood with necessary framing with 4mm thick MDF board + PU Coating finish as per drawing. Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width. Drawer Storage Unit- 1'-4" W x 2'-0" D, 2 Nos Drawer on top and rest 1 No shutter All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate (FOR DETAILS REFER DRG. NO-6) FINISHING DETAILS IN NUTSHELL: 1)Table top made from 18 mm thick ply wood + 6mm corian, 25 mm thick 2) Apron (Front side) made from 18 mm thick ply wood +fluted teak finish panels. 3)Front Skirting shall be brush gold finish pvd on 2.0 mm ss to be completed as per drawing 4)Both sides made from 18 mm thick ply wood +fluted teak finish panel.	1.83	RMT		
					
5	CUSTOMER WRITING DESK Writing Desk Size 3'-0" L x 1'-3" x (0'-6"+3'-0") ht. Verticle Sides and bottom shall be made out of 36 mm (2X18) thick Commercial plywood and back side 12 mm thick ply wood with veneer on Top and Edges on all sides including inside divisions. Top shall be made from 12mm th Toughend glass with polished edges making different divisions by 18 mm thick glass / plywood with laminate on both side for slips or forms as per detail drawing and inststruction complete. (Drawing as enclosed herewith) veneere to be provided on all visible surface [REFER DRG NO-07]	1.00	NO		

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
	All specifications as above, burma teak wall brackets with ss pvd brush gold finish studs instead of vertical sides.REFER DRG.NO-7				
	SIDE CREDENZA (SIDE TABLE)				
7	Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht./any lenth Openable shutter with 3.50 mm thick Teak veneer with PU Coating finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges with PU Coating. Veneer to be provided only on visible surface etc complete as follows. Only Front elevation will be measured for payment purpose.				
	Supplying and installation side cabinet for keeping computer and printer of size 1'-4" width 2'-6" height and 3'-6" length having openable shutters as directed. Cabinet shall be made from 18 mm thick commercial ply wood with 3.50 mm thick veneer with PU Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with veneer finished and approved make group lock, handle(as per selection), hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate similar to veneer tone.				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate similar to veneer tone.				
	(FOR DETAILS REFER DRG. NO- 2)				
7[a]	SIDE CREDENZA (SIDE TABLE) Same as above Item No-7, but all external surfaces to be finished with 3.5 mm thick veneer . Size shall be 3'-0"/3'-6" x 1'-4" x 2'-6" ht. with openable shutters as directed.	10.00	SQ.MT		
	FINISHING DETAILS IN NUTSHELL:				
	1) Top : veneer & Burma Teak beading on Edges with pilishade				
	2) Front Apron & Sides: veneer				
7[b]	SIDE CREDENZA (SIDE TABLE) For S.W Countwer Same as above item No-7 but Side Table Top and edges shall be finished with 6 mmThick White Corian on Top and Edges. All other visible surface shall be finished with veneer Size shall be 3'-0"x 1'-4"x2'-6" ht. With onenable shutter as directed	4.15	SQMT		
7[f]	STORAGE CABINET with Top & Front veneer finished. Storage of any height	26.00	SQMT		
	Same as above Item No-7, but all external surfaces to be finished with veneer.				
	FINISHING DETAILS IN NUTSHELL:				
	1) Top : veneer & Burma Teak beading on Edges with pilishade				
	2) Front Apron & Sides: veneer as per design & instructions				
7[g]	P/F ELECTRIC CUB BOARD	5.60	SQMT		
	Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamel paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-3". Height of shutter will be maximum 7'-0". Only Front elevation shall be measured for payment purpose.				
	LOW HEIGHT PARTITION WORK				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
8	P/F LOW HEIGHT BOTH SIDE VENEER PARTITION FOR IN BETWEEN S.W COUNTER WITH TOUGHENED GLASS	16.30	SQMT		
	Providing and fixing low height partition using 50mm x 25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 3.50 mm thick veneer of approved shade on both sides, fixing 12 mm thick transparent toughened glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed. Veneer to be provided only on visible surface [FOR DETAILS REFER DRG. NO- 1]				
	For Low height Single window and Cash cabin partition, Average height of partition shall be measured and paid.				
8[a]	PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE VENEER	2.00	SQMT		
	Same as item no 10 but P/F 30 / 32 mm thick flush shutter with both side laminate including SS hinges with countersunk SS screws, Approved make Night latch Lock, antique Handles,Door stoppers, doorstop etc complete as directed.				
8[b]	P/F LOW HEIGHT BOTH SIDE VENEER PARTITION WITH SOLID/CLEAR FLOAT GLASS	49.00	SQMT		
	Providing and fixing low height partition using 50mm x25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides. Fixing 12mm thick free clear float glass as directed. Applying lacquer polish on exposed teak wood members / edges as directed. veneer to be provided only on visible surface Providing pinup board of soft board covered with fabric and fixed in partition as per design/instruction complete as directed.				
	FULL HEIGHT PARTITION WORK				
9	P/F BOTH SIDE VENEER SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR		SQMT		
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides,1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter. All visible members shall have lacquer polished as directed.[REFER DRG NO-5]				
	For purpose of payment partition height up to bottom of false ceiling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.				
9.1	Same as above item no-9 specification but P/F ONE SIDE 3.50 mm thick Veneer up to 3'-6" ht. from floor with MDF above 3'-6" ht. finished with wall texture paint of appoved shade,4" veneer patta pannels with burma teak moulding and 12" /15" veneer patta from ceiling level. As directed as per design/drawing and as per instruction. OTHER SIDE LAMINATE SOLID FULL HEIGHT PARTITION	38.00	SQMT		
10	Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Laminate) with frame as follows.				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
	Providing and fixing 4"x2" teak wood member for frame and Flush door shutter made out of 32 mm thick flush door with 6 mm thick clear float glass vision panel secured with 12 mm thick steam beach beading, 32 x 12 mm thick teak wood periphery patti around shutter edges, 1 mm thick laminate on both sides, 35x12mm thick steam beach stopper patti on frame including 3 Nos 5" long SS hinges with countersunk S S screws, Approved make Dead Lock, S.S Handles, 150 mm long Door stoppers, doorstop of approved make etc. All exposed surface /edges not laminated be provided with lacquer polish. Work to be completed as per drawing & instructions [REFER DRG NO-5]				
	Providing and fixing Isolated flush door shutter (Partly Glazed and Partly veneer) with frame as follows.				
	Same as above item no.10 but Providing and fixing Isolated flush door shutter (Partly Glazed and Partly Veneer) with frame with antique brass finish handle and accessories as follows.	5.00	SQMT		
	GLASS DOORS AND PARTITIONS				
11	P & F FULLY GLAZED DOOR WITH PATCH FITTINGS for Entrance Door and A.T.M Door		SQMT		
	Providing & Fixing fully glazed main door at the main entrance and ATM. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings . The door will have patch lock, ptl pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides, (Ozone Make OGH-55P11-25X400), fixed with the glass by making necessary cutouts & holes. The glass edges shall be polished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push.				
	The patch fittings (Ozone make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.				
	P & F FULLY GLAZED DOOR WITH frame for Entrance Door and A.T.M Door				
11.1	Same as above item but Supply, Fabrication, and Installation of CS-40 CASEMENT <ul style="list-style-type: none"> • Profiles & Finish: 50mm x 46mm outer frame and 93mm moving shutter sash treated with premium, wear-resistant Sublimated Light Walnut coating. • Glazing: 10 mm clear toughened glass with polished safety edges, resting on structural setting blocks. • Hardware Set: 8 Nos. Corinzo S2 butt hinges with self-lubricating bushings, combined with heavy-duty commercial multi-point locksets, Euro-profile cylinders, and S2-morties Lock with key. • Weatherproofing & Sealing: Dual-durometer EPDM perimeter gaskets and non-reactive high-shore perimeter silicone sealants. • Execution: Precision laser alignment, anchorage into masonry sub-frames, hardware fine-tuning, and color-matched perimeter grouting. 	4.47	SQMT		
11.2	Same as above item no. 11.1 but ATM DOOR with S1 butt hinges, S1-morties Lock with key	2.98	SQMT		
11.3	Same as above item no. 11.1 but with fix portion	8.54	SQMT		
	PANELLING WORK				
12	P/F Wall panelling with laminate finishing for wall and Pillar etc				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
	Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx25mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete .As directed as per design/drawing and as per instruction.				
	P/F Wall panelling with vineer finishing for wall and Pillar etc				
12.1	Same as above item no 12 but Providing & Fixing 3.50 mm thick Veneer up to 3'-6" ht. from floor with MDF above 3'-6" ht. finished with wall texture paint of appoved shade asian paint royal play or equivalent with required no of coats asper company specificatins brand,4" veneer patta pannels with burma teak moulding and 12" /15" veneer patta from ceiling level. As directed as per design/drawing and as per instruction.	147.00	SQMT		
					
12.2	Same as above item no 12 but Providing & Fixing fluted teak finish panels. As directed as per design/drawing and as per instruction.	28.50	SQMT		
12.3	Same as above item no 12 but Providing & Fixing 3.50 mm thick Veneer finishing over aluminium framing shall be finish with LCD panel with 6mm glass on studs above lower panel and backpainted glass on back side with wooden moulding as per design. Lower front panel with 3 mm thick ss pvd brush gold finish Emblem and both sides with fluted teak finish panels. The panneling should have necessary grooves and sleeves for the profile lights.Skirting shall be finish with brass PVD. As directed as per design/drawing and as per istration.	33.00	SQMT		
12.4	Same as above item no 12 but Providing & Fixing 3.50 mm thick Veneer finishing over aluminium framing shall be finish with backpainted glass on front and back side with wooden moulding as per design. Lower front panel with 3 mm thick ss pvd brush gold finish Emblem and both sides with fluted teak finish panels.The panneling should have necessary grooves and sleeves for the profile lights.Skirting shall be finish with brass PVD. As directed as per design/drawing and as per istration.	68.00	SQMT		
					
12[j]	P/A WALL PAPERS on Digital wall	40.00	SQMT		

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
	Providing and applying Wall paper approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft				
12[k]	ALUMINUM COMPOSITE PANEL FOR FRONT SIDE ELEVATION for BRANCH AND ATM ROOM IN SIDE WALL AND OUT SIDE	51.00	SQMT		
	Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE - 117 or equivalent				
	FALSE CEILING WORK				
13	P/F GYPSUM BOARD FALSE CEILING		SMT		
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section of Gypsteel ULTRA (Gypsteel Ultra shall be used) supporting system in line and level. Finishing the surface and applying 3 coats of Plastic emulsion paint as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.				
	Note : (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in Rmt and paid in SqM (3) Only finished visible surface area shall be measured for payment.				
13.1	Same as above item but providing and fixing of wooden strip wpc false ceiling instead of Gypsum Board complete as per design and instruction. Only finished surface area shall be measured for payment.	25.00	SMT		
13.2	Same as above item but providing and fixing of Metallic Wooden finish ceiling providing and installing architectural linear fluted metallic false ceiling system using factory-finished aluminium or galvanised iron (GI)sections.The framework consists of hidden suspensions grid including GI perimetre channels ,intermediate runners,suspention angles and heavy-duty dash fastners anchored to the structural soffite.Panles shall be pre coated,roll-formed fluted linear slates or louvers of appoved peofile,pitch and metal thickness(typically 0.5mm to 0.7mm).Rate includes necessary carrier systems,clips,profile connectors,edges trims,providing cutouts for light fixtures/AC diffusers,completes scaffolding,alignment,and labour as per manufacturer specifications		SMT		
					
13[f]	P&F POP IN WALL				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
	providing and applying plaster of paris (POP) class1super fine with perfect plum at the exposed wall where needed for leveling purpose. before painting work. On lounge area back wall	250.00	SQMT		
14	SOFT BOARD	5.00	SQMT		
	Providing & fixing soft board for pin up using moulded teak wood frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. teak wood member shall have lacquer polish as directed.				
19	Supplying and installation 3'-0" x 1'-9"x 1'-6" height Center Tepoy as follows.	1.00	NO		
	same as above item no.19 but Providing and making round corner tepoy with tapered wooden legs and frame with brass gold finish PVD caps, 12 mm clear/tinted glass top as per deisgn and instructions.refer 3D image.				
	 <p>HERITAGE LOUNGE COFFEE TABLE</p> <p>SOPAN SURAT</p> <p>PROJECT: 1918</p> <p>ITEM: HERITAGE LOUNGE COFFEE TABLE</p> <p>SIZE: 42" x 21" x 18"</p> <p>DETAILS: 18" x 18" x 18" (FRONT, SIDE, TOP)</p> <p>LEG TOP DETAIL: 18" x 18" x 18" (FRONT, SIDE, TOP)</p> <p>LEG BOTTOM DETAIL: 18" x 18" x 18" (FRONT, SIDE, TOP)</p> <p>LEG DETAIL: 18" x 18" x 18" (FRONT, SIDE, TOP)</p>				
19.1	same as above item no.19 size 2'-6" x 1'-9"x 1'-6"	1.00	NO		
	same as above item no.19 but Providing and making oval center table with natural wood veneer top with bevelled & diamond polished edges 12mm thick glass top on it and wooden legs as per deisgn and instructions.				
	 <p>MANAGER CABIN TEPOY</p> <p>SIZE: 30" x 21" x 18"</p> <p>SOPAN SURAT</p> <p>PROJECT: 1918</p> <p>ITEM: MANAGER CABIN TEPOY</p> <p>SIZE: 30" x 21" x 18"</p> <p>DETAILS: 18" x 18" x 18" (FRONT, SIDE, TOP)</p> <p>LEG TOP DETAIL: 18" x 18" x 18" (FRONT, SIDE, TOP)</p> <p>LEG BOTTOM DETAIL: 18" x 18" x 18" (FRONT, SIDE, TOP)</p> <p>LEG DETAIL: 18" x 18" x 18" (FRONT, SIDE, TOP)</p>				
19.2	same as above item no.19 size 3'-6" x 1'-9"x 1'-6"	1.00	NO		
	same as above item no.19 but Providing and making oval center table with natural wood veneer top.tapered wooden legs and a clear glass top as per deisgn and instructions.				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
					
19.3	same as above item no.19 size 3'-6" x 3'-6"x 1'-6"	1.00	NO		
	same as above item no.19 but Providing and making square center table with gold finish metal frame,diagonal support and clear glass top. As per design and instructions.				
					
19.4	Supplying and installation 4'-0" x 1'-3"x 2'-6" Manager Console	1.00	NO		
	Providing and making console made out of 18mm thick plywood with 6mm corian top. Fluted wooden apron, wooden tapered legs with brass finish caps. fabrication and polishing complete.				
					
19.5	Same as above but size 1'-9" x 1'-9" x 1'-6" height for Corner Tepoy	5.00	NO		
	same as above item no.19 but Providing and making round corner tepoy with tapered wooden legs and frame with brass gold finish PVD caps, 12 mm clear/tinted glass top as per design and instructions. refer 3D image.				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
					
20	P & F SOFA SEATING 3/2 seater				
20.1	P & S of Visitors sofa. The seat shall be made out of 19 mm BB in a box form. The back shall be made out using internal wooden frame work of size 2"x1 1/2" covered with 6 mm ply. It shall be covered with 100 mm & 50 mm th. 40 density u foam in seat & back respectively. This should be again covered with 14 mm th. 40 density u foam with majarpatt cover on it & upholstered of suggested shade & finish in seat & back on all open visible sides with basic rate of Rs.1500/- per meter. It will have polished wooden visible frame and legs, as per drawing. outer length with armrest will be considered for measurement purpose.	17.00	R.MT		
					
					
34[a]	P/A ACRYLIC EMULSION PAINT (PLASTIC PAINT)				
	Providing and applying (with rollers only) Acrylic emulsion paint of required shade and approved make on old/new surface in two or more coats to give an even shade including the preparation of surface for painting, applying FULL primer and putty at all heights complete as per manufacturer's specification and as directed.	300.00	SQ.MT		
[B]	BUY BACK OF OLD FURNITURE				
	Dismantling of entire furniture and fixtures from existing premises and buy back of furniture which is not required by Bank, as Directed.	1	LOT		
[a]	In all furniture work, contractor shall make necessary cutout in panelling/partitions / wooden members to facilitate electrical/data cabling and No extra amount shall be paid for this				

NO.	ITEM	QTY	UNIT	RATE	AMOUNT
[b]	All internal surface (non visible surfaces) shall be provided with the 0.60 mm thick balacing laminate of aproved make & shade in the all S.W Counters/Tables/ Credenza,Storage Cup Board etc.				
	SUMMARY				
[A]	FURNISHING WORK				
					-
[B]	BUY BACK OF OLD FURNITURE				
					-
	NET TOTAL COST [A -B]				