

| BOQ FOR INTERIOR & FURNISHING WORKS OF STATE BANK OF INDIA, SME BRANCH AT BAWANA, | | | | | |
|---|---|------|-----|-------------|--------------|
| S.No. | Particulars | Unit | Qty | Rates (Rs.) | Amount (Rs.) |
| 1.0 | PARTITIONS & DOORS | | | | |
| | Measurement of height shall be taken from finished floor level up to the level of false ceiling, in case of varying heights on either side of partition, average height shall be considered. The rate to include provision of extra frame work as necessary for skirting and making openings for glazing & door etc., cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions. All wooden surface/ply with anti termite treatment properly. | | | | |
| | | | | | |

| | | | | | |
|---|--|--------|----|--|--|
| a | <p>P/F Solid Full Height Partition consisting of Aluminium hollow section of 65mm x 37mm size, 1.5mm thick of JINDAL / INDAL as internal frame structure at required spacing but not exceeding 600mm centre to centre in either direction vertical and horizontal direction and vertical member to be in one piece fixed to floor & ceiling by means of rawl plug/dash fasteners on both ends, 8mm thk. MR ply to be fixed on both sides till roof height. I/C P/F of 1mm thk. high gloss laminate on both side of partition till false ceiling level, P/making of 5mm thk. grooves as per instructions. Partition to have 100 mm high super gloss laminate band of different shade, as per appvd. shade, at skirting level on both sides of partition, Item includes melamine polish on the wood surfaces & finishing of grooves with polish etc. Rest of specifications same as main specifications of partitions, complete to the satisfaction of the Architect/Bank's Eng.</p> | Sq.Mt. | 48 | | |
| | | | | | |

| | | | | | |
|---|--|-------|------|--|--|
| b | <p>P/F Partly Glazed Full Height Partition consisting of Aluminium hollow section of 65mm x 37mm size, 1.5mm thk. of JINDAL/INDAL as internal frame structure at required spacing but not exceeding 600mm centre to centre in either direction vertical and horizontal direction and vertical member to be in one piece fixed to floor & ceiling by means of rawl plug/dash fasteners on both ends, 8mm thk. MR ply to be fixed on both sides till roof height. including P/F of 1mm thk. high gloss laminate on both side of partition till false ceiling level, providing & making of 5mm thick grooves as per instructions and Partition to have 100mm high high gloss laminate band of different shade as per appvd. shade at skirting on both sides of partition, Item includes melamine polish on the wood surfaces and finishing of grooves with polish etc. The rate to include P/f 10/12mm thk. etched plate glass to be fixed with wooden moulding as per design etching to be p/f with digital glass film as per appvd. design. Rest of specifications same as main specifications of partitions, complete to the satisfaction of the Architect/Bank's Eng.</p> | Sqmt. | 15.0 | | |
| | | | | | |

| | | | | | |
|---|---|--------|------|--|--|
| c | P/F 12mm toughend Fixed Glass Partition fixed with S.S. clamps on sides and top & S.S. u-channel in the ground as per detail drgs. and complete to the satisfaction of Architect/ Bank's Engineer. inclusive of P/f Digital Glass Film (3M) for etching as per design in all shapes including curve shapes etc. complete to the satisfaction of Architect/Bank's Engineer. | Sq.Mt. | 25.0 | | |
| | | | | | |

| | | | | | |
|---|---|--------|------|--|--|
| d | <p>P/F front Frameless Patch Fitting Door with 12mm thk.toughened glass with frame less glass fittings joining 2 glass & double action floor springs (Hettich/Dorma/Godrej) as per design. The item includes providing and fixing S.S. handle not less than 600mm long on both side of glass, locks and fittings (Haffle/ Hettich/ Ozone) as per the manufacturer's specifications etc. complete to the satisfaction of Architect/ Bank's Engineer. inclusive of P/f Digital Glass Film (3M) for etching as per design of Architect/Bank's Engineer.</p> | Sq.Mt. | 17.0 | | |
| | | | | | |

[illegible]

| | | | | | |
|---|--|--------|------|--|--|
| f | <p>P/F Partly Glazed Door with 75x50 mm teak wood frame (chaukhat). finished with 1.0mm thick high gloss laminate on both sides. Item includes P/fixing 6mm etched glass fixed with teak wood beading 14x12mm. The door is to be complete with 7 lever mortice door lock & a pair of S.S.handle ,S.S stopper, 4 No.s 125mm S.S. hinges (Hettich/ Dorma/ Ozone) etc. All wood surfaces to be melamine polished complete to the satisfaction of Architect / Bank's Engineer.</p> | Sq.Mt. | 12.0 | | |
| | | | | | |

| | | | | | |
|---|--|--------|-----|--|--|
| g | <p>Providing & fixing 35mm Water Proof Flush Doors with 1.0mm thk.high gloss laminate on both sides as per appvd. sample. The item includes providing and fixing chaukhat made from 100mmx50mm teak wood members. The Doors to have all hardware fittings such as 4 No.s 125mm SS hinges, SS handles, 150mm SS tower bolts,7 lever mortice locks with SS handles (Dorma/Hettich/Godrej) etc. complete to the satisfaction of Architects/ Bank's Engineer.</p> | Sq.Mt. | 4.0 | | |
| | | | | | |

| | | | | | |
|---|---|------|------|--|--|
| h | P/F Door Closers for existing door (Hettich/ Haffele/ Dorma/ Godrej) including cutting and fixing, covering plate and all associated hardware etc. complete to the satisfaction of Architect/Bank's Engineer. | Nos. | 10.0 | | |
| | | | | | |
| i | Laminate on Existing Doors. | | | | |

| | | | | | |
|------------|---|--------|------|--|--|
| | Extra for P/fixing 3mm thick MR ply on both sides of existing doors complete with T.W. Beading & edging 38x19mm finished with 1.0mm thick high gloss laminate on both side Complete with P/F Baby latch with S.S pair of handles of Godrej in toilet & pantry and 7 lever mortise lock of Godrej on all other doors as per approved Make. | Sq.Mt. | 13.0 | | |
| | SUB TOTAL : I : PARTITIONS AND DOORS | | | | |
| | | | | | |
| 2.0 | PANELLING | | | | |

| | | | | | |
|---|---|--------|------|--|--|
| a | <p>P/f Panelling consisting of Aluminium frame work with 50 x 25 mm of including fixed to wall,at a spacing of not more than 600 mm c/c in both ways or as per site inclusive of skirting which will have two member of 50x25mm, finished with 8mm thk. MR ply. The ply to be covered with 12mm thick designer 3D MDF Board panel with of rate not less than 350/- per sqft. complete with duco paint finish as per appvd.sample/shade complete with P/F T.W. beading , 100mm wide on sides,top & bottom i/c of beadings, grooves as per arch.drg.complete with melamine spray finishduco on wooden surface .</p> | Sq.Mt. | 21.0 | | |
| | | | | | |

| | | | | | |
|---|---|--------|------|--|--|
| b | <p>P/F Panelling with Laminate consisting of Aluminium frame work with 50 x 25 mm of including fixed to wall,at a spacing of not more than 600 mm c/c in both ways or as per site inclusive of skirting which will have two member of 50x25mm, finished with 8mm thk. MR ply. The ply to be covered with 1.0mm thk. high gloss laminate in two or more colour with 5mm thick grooves ,Panelling to have 50x35mm teak wood moulding on edges. Panelling to have 100 mm high teak wood DUCO painted Blue/Teak/high gloss laminate band at skirting including moulding and provision of extra frame work as necessary for skirting and making cutouts for electrical switch plates, switch boxes, light fittings light etc. making provision for laying conduits as per drawings & directions etc. complete to the satisfaction of the Architect /Bank's Engineer.</p> | Sq.Mt. | 80.0 | | |
| | | | | | |

| | | | | | |
|-----|---|--------|------|--|--|
| c | Providing and fixing in position Aluminium Composite Paneling (ACP) for Cladding with framing of aluminium tube section of min. 50mmx25mm and 20 gauge at a spacing of 600mm center to center both ways. ACP to be of approved shade in 600mm wide panels or distributed equally. ACP sheets to be fixed to the frame with 3M make adhesive along with mirror screws. Joints to be finished with silicon based sealant. ACP sheets (Aludecor/ Eurobond/ Fujibond/ Alcobond) to be min. 3mm thick with aluminum foil thickness to be min. 0.25mm on both sides. Item includes providing additional sections to fix indoor AC units which will be installed at the highest position etc. complete as per instructions of Architect/ Bank's Engineer. Item includes scaffolding as may be required etc. complete as per site conditions. (In Premises Front Area & ATM Internal Area) | Sq.Mt. | 60.0 | | |
| d | Extra for P/F 4mm plain lacquered glass as per appvd. Sample over item no.2 fixed and pressed with silicon. | Sq.Mt. | 2.0 | | |
| | SUB TOTAL : II : PANELLING | | | | |
| | | | | | |
| | | | | | |
| 3.0 | FALSE CEILING | | | | |

| | | | | | |
|--|---|--|--|--|--|
| | <p>Item includes providing False Ceiling in plane, curve shape and design . Suspending system and frame work shall match layout of A.C. ducts / grills, electrical / fire protection wiring / fixtures, return air grills etc. Rate to include provision of extra frame work, necessary scaffolding needed due to layout of other utilities refered above and fixtures etc.(Measurement shall be taken of the horizontal base area only nothing extra for cove design and verticle sections)</p> | | | | |
|--|---|--|--|--|--|

| | | | | | |
|---|--|--------|-------|--|--|
| a | <p>P/F of 12.5mm th.Gypsum ceiling board false ceiling in horizontal & vertical surfaces & moulded corners & offset as per arch.drg.which include P/F roll formed G.I.Perimeter channels of sizes 27x.5mm th.having one flange of 30mm along the perimeter of the ceiling fixed to the brick wall or partition with help of rawl plug or screw i/c ending of G.I.intermediate channels of size 45x9mm th.with two flanges of 15mm th.each from the soffit @ 1200 c/c with steel/G.I.hanger of with 25mm &0.5mm th.fixed soffit with G.I.cleat & steel expansion fasteners of 0.5mm thickness having knurle dwedge of 51.5mm & two flanges of 26mm each with tips of 10.5mm fixe to the intermediate channel with the help of converting clips in a direction perpendicular to the intermediate channel of 350mm c/c12.5mm taperededge gypsum plaster board(confirming to I.S.2095,1982)Screwed 230mm c/c screw fixing to be done mechanically with suitable attachment The tapered & squared edges of the boards(as recommended by the manufacturer)finish with P/A two or more coats of OBD paint over a coat of primer,extra frame work for necessary hatch doors/opening upto 600mmx600mm (or as per requirement)with 19mm th. comm.board wherever required i/c necessary S.S. hinges,screws finish</p> | Sq.Mt. | 197.0 | | |
| | | | | | |

| | | | | | |
|---|---|--------|------|--|--|
| b | <p>Providing and fixing False Ceiling with Mineral Fibre Acoustic Ceiling tiles of Armstrong with MICROLOOK edges and having noise reduction properties laid on exposed grid system with 15mm wide Silhouette type T-section flanges of white colour, main runners spaced at 1200 mm c/c securely fixed to the soffit of structure with approved hangers at 1200 mm maximum c/c. Flush fitting 1200 mm crossed tees to be interlocked between main runners at 600 mm c/c to form 1200 x 600 modules. 1200 mm cross tees to be crimped. 600 x 600 module to be formed by fixing 600 mm long flush fitting cross tees centrally between the 1200 cross tees. Ceiling tiles of Dune Premier of size 600 x 600 x 15 mm (thk.) to be placed in the grid. Rate to include making necessary cut-outs or openings for light fixtures, air conditioners and other utilities etc. complete to the satisfaction of Architect/ Bank's Engineer.</p> | Sq.Mt. | 50.0 | | |
| | | | | | |

[illegible]

| | | | | | |
|-----|--|--|--|--|--|
| 4.0 | COUNTER/ TABLES/ WORKSTATIONS | | | | |
| | <p>All Tables/ Counters/Work Stations/Running Counter to be fabricated out of 19mm thk. MR ply top front, rear and sides and finished with 1.0 mm thk. high gloss laminate finish on all exposed surfaces along with 0.8 mm thk. white laminate on inside surface of shelves & shutters & rear drawer units to be made from 12 mm thk. MR ply and FASCIA with 19mm MR ply, fascia to be finished with 1.0 mm thk. high gloss laminate finish (as per individual item). The drawers to run on telescopic drawer channels of Hettich make. Drawer units shall have two smaller and one bigger drawer with auto locking arrangement (Godrej). Footrest 75x50mm made of 2nd class teakwood member, to be fixed in each table. The rate shall include providing all hardware such as drawer channels, 6" S.S. handles, S.S. cable manager (Hettich/ Dorma/Haffele) etc. complete. The item also includes a tray for keyboard fabricated out of 12mm MR ply finished with 1.0mm th. high gloss laminate on all exposed surface running on telescopic channel of Hettich, finished with corian on top and rounded front of size 560x450mm, P/S & fixing readymade CPU trolley with castors etc. complete to the satisfaction of Architect/ Bank's Engineer.</p> | | | | |
| | | | | | |

| | | | | | |
|----------|--|------|---|--|--|
| a | <p>Providing and placing Table made of 19mm thk. MR ply top provided with approved 12mm thk. high density acrylic corian (Corian/LG/Merino) and sides and 1.0mm thk. high gloss laminate finish on exposed surfaces along with 0.8mm thick white laminate on inside surface, drawer units to be made from 19mm thick MR Ply with 1.0mm thick high gloss laminate finish. Modesty panel to be made of 19mm thk. MR ply finished with 1.0mm thick laminate high gloss laminate as per appvd.shade. Table top edges to be approx. 25mm thk. with corian finish as per design & details. The drawers to run on telescopic drawer channels. Drawer units shall have two smaller and one bigger drawer and auto locking arrangement (Godrej). Footrest 75x50mm made of 2nd class teakwood member to be fixed in each table. The rate shall include providing all hardware such as drawer channels, S.S. 6" handles, S.S.cable manager (Hettich/ Dorma/Haffele) etc. complete. The item also includes a tray for keyboard running on telescopic channel, finished with 1.0mm thick laminate on top and rounded front of size 560x450mm, readymade CPU trolley with castors etc. complete to the satisfaction of Architect/ Bank's Engineer.</p> | | | | |
| i) | Size (6'-6"x2'-9"x2'-6") FOR BM | Nos. | 1 | | |
| ii) | Size (5'-0"x2'-6"x2'-6") FOR OFF./CLK. | Nos. | 7 | | |
| iii) | Size (4'-9"x2'-6"x2'-6") FOR CASH INCHARGE | Nos. | 1 | | |
| iv) | Size (5'-0"x1'-10"x3'-0") FOR RECEPTION | Nos. | 1 | | |
| | | | | | |
| b | RUNNING COUNTERS 2'-0"/2'-3" WIDE | | | | |

| | | | | | |
|--|---|-----|-----|--|--|
| | <p>P/F 600/675mm deep & 750mm high Work Counter for Auditors fabricated out of 19mm th. comm.ply finished with 12mm thick corian on top with moulded edges side front /rear and all exposed external surfaces to be finished with high glosss 1mm thick laminate,including finishing all exposed internal surface front and exposed Leg & CPU space to be finished with 0.75mm th.Laminate complete with set of drawers 4 No's, key board drawer,shelves & shutter as per arch.drg. & P/F complete with necessary hardware,telescopic sliding channels of Hettich SS locks, Hettich/Godrej SS handles(150mm),key board tray & magnet catcher edges to be finished with 1.0mm thick high gloss laminate & painting the exposed all other internal surfaces with 2 or 3 coats of synthetic enamel paint & melamine finish on wooden surface inclusive of P/f Stainless Steel cable Manager and making good the surface.</p> | Rmt | 1.5 | | |
| | | | | | |

| | | | | | |
|-----|---|------|---|--|--|
| c | Providing and fixing Side Storage Tables made of 19mm thk. MR PLY having 450mm wide top provided with 12mm thk. high density acrylic (Corian/ LG/ Marino) and sides finished with 1mm thk. high gloss laminate. The side table to have 2 drawers on top with shuttered storage below. The inside of side table to be finished with 0.8mm thk. white laminate. The rate shall include providing all hardware such as auto closing hinges, 6" S.S. handles (Hettich/ Dorma/Haffele) and locks (Godrej) etc. complete as per design/drawing to the entire satisfaction of Architect/Bank's Engineer. | | | | |
| i) | Size (3'-6"X1'-4"X2'-6") FOR BM & OFF. | Nos. | 9 | | |
| ii) | Size (6'-0"X1'-4"X2'-6") FOR CASH INCHARGE | Nos. | 1 | | |
| | | | | | |

| | | | | | |
|-----|--|------|---|--|--|
| 5.0 | P/P in position Corner Tables in AGM Cabin made with 19mm thk. MR ply complete with table top finished with 12mm thk.high density acrylic Corian (LG/ Marino) as per arch.drg complete to the satisfaction of Arch./Bank's Engineer. Size: 2'-6"x2'-6"x1'-6". | Nos. | 2 | | |
| | | | | | |

| | | | | | |
|-----|--|------|---|--|--|
| 6.0 | P/F in position Centre Table as per selection having 12mm thk.toughened clear float glass top with bevel edge. The glass to be fixed to chrome finished supporting frame as per design with designed joinery. The vertical support should be of 50mm &chrome plated pipe with 600 mm dia. chrome plated base plate for support. Item to be inclusive of all accessories, fixing implements etc complete. Hardware - all 'butler/brushed steel' finish SS of 304 grade. Lipping - good grade teak wood tinted water based PU in 2 coats etc complete to the satisfaction of Architect/Bank's Engineer.Size: 2'-6" (diameter) | Nos. | 1 | | |
| | | | | | |
| 7.0 | MEETING TABLE | | | | |

| | | | | | |
|---|---|------|---|--|--|
| | P/F in position Meeting Table (Size:8'-0"x4'-0")fabricated out of 19mm MR ply with table top fixed over hardwood framework finished with 3mm ply complete with table top finished with 12mm thk. high density acrylic Corian (LG/ Marino)in two shades as per arch.drg along with all associated hardware etc. and 100mm laminate skirting etc. complete to the entire satisfaction of Architect/Bank's Engineer. | Nos. | 1 | | |
| SUB TOTAL : IV : COUNTER/TABLES/WORKSTATIONS | | | | | |
| | | | | | |
| 8.0 | STORAGE CUPBOARDS | | | | |

| | | | | | |
|---|---|--------|------|--|--|
| a | <p>P/F Full/Low Height Storage Cupboard 450mm deep & Ht.750/2100mm with frame, all sides,shelves to be made with 19mm thk.MR ply & 6m thk.MR ply fixed at the back.The shutters to be made with 19mm thk. MR ply Shutters,top & sides all exposed surface to be finished with 1mm thk.high gloss laminate on all exposed surfaces.All edges to have 19mm thk.H.W.edging as per details finished with 1mm thk.laminate,all shutters to to be made over lapping the frame and edges of shutters to have 19mm thk.H.W. edging as per details finished with 1mm thk.laminate, i/c S.S. 6" long handles,magnetic catchers,self closing hinges,locks(Godrej/Hettich/Haffele) etc.The item includes polishing the wood surfaces & grooves with melamine polish & all inside surfaces shutters/shelves to have 0.8mm thk white laminate finish etc. complete to the satisfaction of Architect/Bank's Engineer.The rates should be including with top P/F with 12mm thk. high density acrylic (Corian/ LG/ Marino) on top of low ht.storage cabinet & sides to be finished high gloss laminate The rates should be include glass shelves of 12mm thick plate glass on SS brackets with polished edge and i/c P/F T.W.moulding and beadings as per arch.drg.complete with 2-3 coats of melamine finish in BM & Meeting Room,Only</p> | Sq.Mt. | 28.0 | | |
| | | | | | |

| | | | | | |
|---|--|--------|-----|--|--|
| b | <p>P/F Over Head Storage made of FIRESAFE IS: 5509 plywood sheet inside laminate finish with required 19mm thk.aluminium profile shutters with back painted glass,required soft closing hinges (Hettich/Haffle/Dorma) & glass shelves.Item to be inclusive of all accessories,storage shelves,lift up sutters,design grooves,moulded edges,aluminum profile,soft close hinges etc.complete.Inner side of the storage to have 1mm thick high gloss laminate finish etc.complete to the satisfaction of Arch/Bank's Engineer.(in pantry)</p> | Sq.Mt. | 2.0 | | |
| | | | | | |

| | | | | | |
|---|--|--------|-----|--|--|
| c | <p>P/F Storage under Platform made of 18mm thk. FIRESAFE IS: 5509 plywood sheet finish with 1mm thk.high gloss laminate sheet on outer face & 1mm thk.white laminate sheets on inner face of the shutter; edge to be covered with aluminum profile section as per selection, shutters to have soft close hinges (Hettich/ Dorma/Haffele) with teak wood frame below platform. Item to be inclusive of 19mm thk.interal horizontal laminated shelves, joining cleats,accessories,ss hardware,soft close drawer with ss basket,aluminum profile handles etc.complete. Inside of storage to be finished with 1mm thk.laminate etc.complete to the satisfaction of Architect/Bank's Eng.(Measurement will be counted from front shutter's height & width, no extra measurement & payment will be given for S.S. basket & shelves).(below counter pantry)</p> | Sq.Mt. | 2.5 | | |
| | | | | | |

| | | | | | |
|-----|---|--------|-----|--|--|
| d | P/F cabinet for housing main electrical panel board,fabricated out of 19mm thk.MR ply finished with 1mm thick high gloss Laminate of as per appvd.Sheet on exposed side surfaces.Front shutters to have 304 grade perforated SS Panels 3 No's, on each shutters as per arch.drg.inside of shutters,vertical & horizontal and surfaces shall be covered.with 12mm thk.gypsum board item shall include providing applying 2-3 coats of melamine spray finish on wood surface & synthetic enamel paint in internal surface with all other specifications as per Item no.5a) above complete to the satisfaction of of Architect /Bank's Engineer. | Sq.Mt. | 4.0 | | |
| | SUB TOTAL : V : STORAGE CUPBOARDS | | | | |
| | | | | | |
| 9.0 | MISCELLANEOUS | | | | |

| | | | | | |
|---|--|------|---|--|--|
| a | P/F Box Notice Board fabricated with 19mm thk. MR ply with frame & sides finished with 1mm thk. high gloss laminate.Box to have 75x35mm teak wood shutters with 6mm thk. clear float glass.The back to have 6mm thk. MR ply & 12mm thk. soft ply covered with cloth of appvd.shade and fabric.The item includes polishing the wood surfaces with melamine polish etc.complete to the satisfaction of Architect/Bank's Engineer. Size :- of the Box Notice Board shall be 1200x600x150(D)mm. | Nos. | 1 | | |
| | | | | | |

| | | | | | |
|---|--|--------|---|--|--|
| b | P/F Pin-up Board with 12mm thk.MDF board with cloth of approved shade & fabric on top. MDF board to be fixed with teak wood moulding of 19x25mm size with melamine polish etc.complete to the satisfaction of Architect/Bank's Engineers. | Sq.Mt. | 2 | | |
| | | | | | |

| | | | | | |
|---|--|------|---|--|--|
| c | <p>P/F Bank Logo with acrylic sheet and S.S.304 grade 16 guage base. Logo to be provided with LED lights(Phillips/Havells/Wipro)as per Bank's instructions.The logo to be fixed on wall/panelling /partition as per details and instructions etc.complete to the satifaction of Architects/Bank's Engineers. Size of Bank Logo shall be 600x600mm</p> | Nos. | 1 | | |
| | | | | | |

| | | | | | |
|---|---|--------|-----|--|--|
| d | <p>P/A the walls, ceiling and elsewhere with Plastic Emulsion Paint (roller finish) after preparing the base by removing existing paint/ finish & applying 2-3 coats of birla white putty for making the surface plane & smooth & than applying 2 or more coats of plastic emulsion paint with final coat done with rollers as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer.The rate i/c of P/A approx.12mm thk.POP Punning on walls,ceiling & else where to give a clean smooth & plumb surface as per the instructions of Architect/Bank's Engineer.</p> | Sq.Mt. | 120 | | |
| | | | | | |

| | | | | | |
|---|---|--------|----|--|--|
| e | P/A approx. 12mm thk. POP Punning on walls,ceiling & else where to give a clean smooth & plumb surface as per the instructions of Architect/Bank's Engineer. | Sq.Mt. | 80 | | |
| | | | | | |

f

P/A Texture Paint (Okios/ Dulux/ Asian) in two or more shades as approved by Bank with roller & spray, after preparing the base for the same as per manufacturer's specifications etc. complete to the satisfaction of Architect/Bank's Engineer.(Base Price of texture paint to be used to be Rs. 60/ sq.ft. (without tax.)

Sq.Mt.

25

| | | | | | |
|--|--|--|--|--|--|
| | | | | | |
|--|--|--|--|--|--|

| | | | | | |
|---|--|------|---|--|--|
| g | P/F Dry Planters Boxes of avg. size 750x600x600(H); having Inner GI box core fixed within outer shell of FIRESAFE IS: 5509 ply boxing with avg. 1mm thk.high gloss laminate finish, lipping at edges and sides with by PU polished teak wood sections. Item to be inclusive of all accessories, fixing implements, materials, finished, installed, cleaned etc complete to the satisfaction of Architect/Bank's Engineer. | Nos. | 6 | | |
| | | | | | |

| | | | | | |
|---|---|--------|-----|--|--|
| h | P/F 18"X16" box for covering of Rolling Shutter fabricated out of 19mm th. BWR Ply finished with 3mm th. ACP of rate not less than Rs.1300/-Per Sheet as per appvd.sample | RMt. | 6 | | |
| | | | | | |
| i | P/F Box 0'-6" deep & 16" wide fabricated out of 19mm th. HDMR Ply with top finished with Ventura Moulding with duco finish as per arch. Drg. | Sq.Mt. | 3.0 | | |
| | | | | | |
| j | Wooden Flooring | | | | |

| | | | | | |
|--|--|--------|------|--|--|
| | P/L 8mm th. Euro/Vista laminate Flooring in BM & Meeting Room complete with 2mm th.Foam underlay & polythene fixed with toungue & groove joint finished with profiles (skirting,T-profile,& Reducer etc.) | Sq.Mt. | 35.0 | | |
| | SUB TOTAL : VI : MISCELLANEOUS | | | | |

TOTAL OF (PART-I+PART-II+PART-III+PART-IV+PART-V+PART-VI)