

PRICE BID FOR AC WORKS AT KUNGHER BRANCH GAO-3

Sr.No.	Description	Quantity	Unit	RATE	AMOUNT
[A]	AIR CONDITIONING WORK				
[I]	MACHINE PART				
[a]	AC EQUIPMENT WITH - INVERTER COMPRESSOR				
1	Supply & providing of 4 way Inverter Cassette Type AC ceiling mounted cassette unit with indoor and out door having eco friendly refrigerant. Including indoor unit outdoor unit. decorative grille and cordless remote Machine shall have copper condensor Unit , Make: Daikin/ Mitsubishi Heavy Industries/Toshiba. [Mini 5 Star rating as per BEE Guide Line 2022]				
1.a	Inverter 4-way Cassette of 3.00 TR.(3 Phase Compressor Only.)	1	NO		
1.a	Inverter 4-way Cassette of 4.00 TR.(3 Phase Compressor Only.)	1	NO		
2	Supplying & providing of Hi-wall Inverter Split Type AC with high wall mounted indoor and out door unit. having eco friendly refrigerant. Including indoor unit outdoor unit. and cordless remote Machine shall have copper condensor Unit , Make: Carrier/ Hitachi/ Daikin/ Mitsubishi Heavy Industries/ Toshiba/ Voltas/Blue star. [Mini 5 Star rating as per BEE Guide Line 2022]				
2a	Inverter Hi-wall Split AC of 1.0 TR	3	NO		
TOTAL FOR PART- I					
[II]	LOW SIDE WORK				
1	Installation of IDU & ODU of 4.00 TR/3.00/2.00 TR ceiling mounted cassette unit with first oil & gas charge & commissioning etc. Rate including ceiling mounted suspension Kit etc complete	2	NO		
2	Installation charges for above 2.0TR/1.50TR/ 1.00 TR Split A/C including 5.0 Rmt copper tubing and electrical wiring connection etc. complete.	3	NO		
3	Refrigerant piping - insulated 0.80mm wall thickness copper tube of Mandav/ Totalline make between indoor to out door unit of 4.00/3.00/2.00 TR ceiling mounted cassette unit with 4 Sqmm 4 Core copper flexible cable of Finolex / R R Kable/Havells/CEI make. The copper piping shall be insulated with 13mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make	28	RMT		
4	Refrigerant piping - insulated 0.80mm wall thickness copper tube of Mandav/ Totalline make between indoor to out door unit beyond 5 Rmt dist. Of 1.0 TR/1.50TR/2.00 TR Hiwall split unit with 2.5 Sqmm 3 Core copper flexible cable of Finolex/R R Kable/Havells/CEI make. The copper piping shall be insulated with 9 mm thick Nitrite rubber insulated of 'O' Class of K Flax/Armaflex/ Superlon Make (copper pipe concealed in inside wall)	10	RMT		

Sr.No.	Description	Quantity	Unit	RATE	AMOUNT
6	25/32 mm Dia UPVC drain pipe with insulation of Dutron/Supreme/Astral make - schedule 40 pipe, white in colour, joint properly glued with UPVC adhesive for water outlet from indoor unit. (drain pipe concealed in inside wall)	30	RMT		
7	Providing and Fixing M.S Powder coated stand for keeping outdoor unit of cassette and split A/C. (Redy made)	5	NO		
8	MISC. CIVIL WORK LIKE MAKING ZARI IN WALL, WALL OPENING TO PASS DUCTS & PIPES, CORE CUTTING, PLASTERING & RE-FINISHING OF THE SAME TO THE ORIGINAL FINISH AS PER THE SITE REQUIREMENTS.	1	JOB		
	TOTAL FOR PART- II				
	GRAND TOTAL (I + II)				