

BOQ FOR INTERIOR WORK OF					
SBI, DHING BRANCH (CODE NO. -02050) ,DHING , ASSAM.					
SI.No	Description of items	Unit	Qty	Rate(Rs.)	Amount(Rs.)
SI.No	Description of items	Unit	Qty	Rate(Rs.)	Amount
1	Remodelling of existing COUNTER : Removing of existing laminate and fixing of approved make. as per new uniform layout of branch. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make.	EACH	9		
2	Remodelling of existing Table : Removing of existing laminate and fixing of approved make. as per new uniform layout of branch. All inner surface to be finished with mat finish enamel paint of approve brand. The works to include all hardwares such as: castors, brass hinges, ball catchers, fully extendable drawer slides, auto locks, handles etc. of Godrej or approved make.	Each	8		
3	Remodelling of column/wall paneling of BM Chamber with not less than 0.8 mm thick laminate as per new uniform layout of branch. Design and detail shall be as per direction of EIC and Bank’s new uniform colour, layout & elevation policy.	SQM	80.00		
4	Remodelling of full height Semi glazed partition , fixing of 6 mm ply approved brand both side and to be finished with not less than 0.8 mm thick laminate as per new uniform layout of branch. Frame should be firmly fixed to the ceiling. All exposed edge shall be covered with teakwood bidding/lipping of required size with polishing complete in all respect.	SQM	78.00		
5	Remodelling of low height semi glazed wooden partitions fixing of 6 mm ply of approved brand in both side and to be finished with not less than 0.8 mm thick laminate as per new uniform layout of branch.	SQM	45.00		
6	Remodelling of full height SOLID partition , fixing of 6 mm ply approved brand both side and to be finished with not less than 0.8 mm thick laminate as per new uniform layout of branch. Frame should be firmly fixed to the ceiling. All exposed edge shall be covered with teakwood bidding/lipping of required size with polishing complete in all respect.	SQM	55.00		
7	Remodelling of low height storage and removing of existing laminate and fixing of approved make as per new uniform layout of branch.	RM	60.00		
8	Providing and fixing Solid doors shutter made up of 38 mm thick block board of approved brand and quality, finshed both side with not less than 0.8 mm thick laminate of approved brand, colour and shade. Door shall includes Godrej Mortise lock, two nos of 125 mm brass handle, 250 mm long tower bolt, brass door stoper, three nos 125 mm brass heavy hinge, hydraulic door closer of Godrej or approve make. All exposed edge shall be covered with teakwood lipping with polishing complete all respect. Rate shall includes etching of glass as requierd by bank.	SQM	7.28		
9	MAIN GATE : Providing and fixing glazed door made of 12 mm thick float glass with frosted film fixed in between top & bottom rail and side stile of plywood framework of size 125 mm x 50 mm. The framework to be finished with not less than 0.8 mm thick laminate on both side. Glass to have acid etched design pattern with logo as directed. Doors to be mounted on heavy duty floor spring/door closer. Rate shall includes all hardwears such as: Two nos S.S. finish handle, lock, door stoper, hinge, tower bolt etc. of approved make.	SQM	3.35		
10	Providing & fixing in place 100 mm. Vertical blinds with scotch guard of approved make, quality and colour shade & pattern. Rate shall include necessary fittings, scotch guard treatment on both sides etc. complete. The overlaps should be uniform & adequate.	SQM	45.00		
TOTAL =					
Rupees			+ GST		
NOTE :The estimated cost is exclusive of statutory taxes (GST)on work contract					