

**TENDER FOR PROPOSED CIVIL AND INTERIOR WORKS OF WEALTH MANAGEMENT AND PREMIER BANKING -
VIRTUAL RELATIONSHIP MODULE(VRM) AT FIRST FLOOR OF SULTANIA ROAD BRANCH, BHOPAL**

BOQ

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
1	Dismantling - Carefully Breaking and Removing the Existing Tiles (WALL AND FLOOR)/ Cement plaster Kitchen platform(including pedestal of platform with stone) and mosiac skirting from the Walls including floor also & without disturbing the structure including cement mortar to get a smooth wall including concealed pipe line etc. and carting away the debris to a place approved by Bank Engineer or Architect. with required manpower, tools & tackles. Note:- Working levels are first floor level .	365.00	SQM.		
2	Dismantling Toilet floor and removal of entire filling material including concealed pipes, traps, Wash basin, W. C. seat, brick bat coba etc and cleaning the surface to make ready for proposed works. Disposal of waste material to approved dumping area with required manpower, tools & tackles. Note:- Working levels are First Floor level.	51.00	SQM.		
3	Dismantling and Removing BRICK WORK / R.C.C. WITH STEEL REINFORCEMENT any thickness including all debris removed from site(All dismantled material remove from site in vendor scope, distance any) including manpower, machinery, transportation, safety equipments etc.. Note:- Working levels are first floor level.	70.00	CUM.		
4	REMOVING AND RE-LOCATION OF ELECTRICAL/LAN/CCTV CABLES ANY SIZES. Existing Electrical/LAN/CCTV cables removing safely & re-laying as per directed by Engineer Incharge. For required man power, tools & takles, required electrical cables, glands, joint connectors etc. Work complete in all respect. Note including Light fitting, CCTV Camera removing and refixing as per directed by Engg. In-charge. Note:- Before removing and re-location of electrical cales and other cables shut down alignment with SBI Electrical Engineer should be must.				
a)	3 x 6.0 + 1 x 4.0 sq. mm. cable	30.00	RMT.		
b)	3 x 10.0 + 1 x 6.0 sq. mm. cable	30.00	RMT.		
c)	other Electrical Cables sq. mm cables & LAN cables etc.	30.00	RMT.		
d)	ARMOURED cables any types of sizes	30.00	RMT.		
5	Excavation for foundation of walls, column footings, pile caps, raft, foundations, plinth beams, steps, water tanks, cess pits, etc., in all types of soil including soft or hard moorum, boulders (upto 0.10 cum) shoring the sides wherever necessary, bailing out of water and keeping the foundation trenches and pits dry including back filling the pit or trenches by selected earth in layers not exceeding 25 cm., watered and consolidated, spreading the surplus material within plot and carting away the surplus materials out of site, all complete as directed depth of pit below paver lvl. 1.50 m.				
	Depth upto 1.5m from NGL	59.85	CUM.		
6	Providing and laying P.C.C. 1:3:6 levelling course with 40 mm down gauge aggregate, in foundations, pits, raft material in the plinth and leap concrete etc. including required form work, consolidation, curing etc., complete.	7.00	CUM.		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
7	Providing and filling in plinth with hard murrom/ hard copra under floors including watering ramming consolidating in layer not exceeding 20cm in depth & dressing complete.	20.00	CUM.		
8	Providing & casting in 1: 1.5: 3 concrete in footings, raft slabs, retaining wall, Pedestal, strom water drain wall with raft, chambers etc. as per design and drawings, including the form work, mechanical compaction, etc. completed with curing (rate exclusive of reinforcement). Note:- All concreting work below plinth to first floor slab level.	41.00	CUM.		
9	Supplying and placing in position by cutting, bending & fabricating tested quality steel reinforcement for R.C.C. work, including dowels of required diameters and lengths as per design & as directed, including typing using good quality binding wire and/or welding, providing required cover with concrete briequests, spacer pieces, chairs, etc. as required complete.				
	a) High Tensile deformed bars Fe-500	5125.00	kg		
10	BRICK MASONRY : Providing and constructing Brick masonry in cement mortar 1:6 with best quality locally available approved bricks in superstructure, at all height & levels, including striking joints, scaffolding, curing, etc. complete as directed. Note:- Wall thickness 200mm / 100MM THICK AS PER SITE CONDITION OR DIRECTED BY ENGINEER INCHARGE. NOTE:- WORKING LEVEL UPTO FIRST FLOOR SLAB LEVEL.	5.00	CUM.		
11	INTERNAL/EXTERNAL PLASTERING(INCLUDING CEILING + WALL OR OTHER SURFACES) Providing and applying 12/15mm avg. thick smooth finish cement Plaster in cement mortar 1:4 to all internal walls, ceiling using fine sand. Rate includes providing chicken mesh/glass fiber mesh to all joints of RCC members with Brick walls in all positions in line, level & plumb at all levels and heights with necessary scaffolding, cleaning of surfaces, raking out joints, roughening of surfaces ,curing etc complete as directed at site. NOTE:- Match line with existing plaster line.	465.00	SQM.		
12	WALL & CEILING PUTTY (BIRLA WHITE) Preparing wall surface by rubbing with sand paper, Removing all dirt, smoke, grease, loose plaster & Existing Paint, Putty remove as per Directed by Engg. In-Charge than after applying two or more coats of Birla white Putty to all internal walls duly rubbed with sandpaper to ensure smooth finished plain surface ready for applying plastic emulsion paint. The rate to include necessary scaffolding etc. complete as directed by the Bank.	1400.00	SQM.		
14	APCOLITE PREMIUM EMULSION FOR CEILING AND INTERNAL WALL Providing and applying two or more coats of approved quality Apcolite Premium Emulsion paint of approved manufacturer like Asian, Nerolac, ICI, Berger of approved colour, shade, and pattern to internal walls including necessary scaffolding etc. complete as directed by the Bank. Apcolite Premium Emulsion or Equivalent.	1400.00	SQM.		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
15	SYNTHETIC ENAMEL PAINT Cleaning the surface thoroughly and removing the external elements (On surface of Door Shutter, Windows, grill etc.), if any , such as dust, dirt, grease etc. providing and applying two coats of primer, rubbing upto finished level and three coats of 1st grade synthetic enamel paint of approved manufacturer in approved colour and brand. All complete including scaffolding , cleaning the site etc. Note:- Applied area Door Shutters, Channel gate, grill & Window Shutter area.	80.00	SQM.		
16	VITRIFIED FLOOR TILES (Size:-1200mmx600mm) WITH 3/4mm SPACER AND REQUIRED EPOXY ROUTE MATERIAL. Providing and laying VITRIFIED FLOOR TILES Multi/Double Charged (Minimum top layer thickness 2.0mm) , in different sizes with water absorption less than 0.05% and conforming to IS : 15622 of approved make in all colours & shades, 1st quality/ premium in flooring , laid on 20 mm thick cement mortar 1:4 (1 cement : 4 sand) or over existing flooring by rubbing the floor with rush abressives to make the floor rough and then using approved adhesive(Make:- MYK LATICRETE, Sika India, Gresbond or approved by Engineer only) specified for tiles over tiles flooring in all shapes and patterns including grouting the joints with epoxy groute matching a pigments etc complete. NOTE:- Sample approved by Bank Engineer. Mode of Measurment is Floor area. Mode of Measurment Skirting are also in SQM. Skirting Ht. 100MM. Basic price 650/- sqm. Note:- Make of Tiles are in RAK, Kajaria, Marbito, Nitco only and spacer grout material Ultratech / Gresbond or equivalent or as per approved by Bank Engineer only)	765.00	SQM.		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
17	<p>ANTI-SKID FLOOR TILES FOR TOILET Providing and laying Antiskid Floor Tiles of any sizes of 600x600 with 3 to4mm spacer including epoxy groute, 9mm to 10mm thickness with water absorption's less than 0.08% and conforming to IS: 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (l cement :4 sand) including grouting the spacer with epoxy based grout material(make:- Ultratech / Gresbond or equivalent or as per approved bank Engineer) with matching pigments etc., complete..</p> <p>Make Kajaria, Marbito, Nitco, RAK approved only. The work should be carried out in toilet floors with adequate slope including cutting holes for Nahani Trap grating etc. complete.(Sizes are 600mmx600mm). NOTE:- Sample approved by Architects or Site In-charge. BASIC PRICE OF TILE 600/- SQM. Note:- Make of Tiles are in RAK, kajaria, Marbito, Nitco only and spacer grout material Ultratech / Gresbond or equivalent or as per approved by Bank Engineer only)</p>	66.00	SQM.		
18	<p>VITRIFIED WALL TILES (SIZE:- 600x600) WITH 3/4mm SPACER AND REQUIRED EPOXY ROUTE MATERIAL. Providing and laying VITRIFIED FLOOR TILES Multi/Double Charged/Digital (Minimum top layer thickness 2.0mm) , in different sizes with water absorption less than 0.05% and conforming to IS : 15622 of approved make in all colours & shades, 1st quality/ premium in flooring , laid on 20 mm thick cement mortar 1:4 (1 cement : 4 sand) or over existing plaster surface with rush abressives to make the floor rough and then using approved adhesive specified for tiles over tiles flooring in all shapes and patterns including grouting the joints with epoxy groute matching a pigments etc complete. NOTE:- Sample approved by Architects or Site In-charge. Mode of Measurment is Floor area. Mode of Measurment in SQM. Basic price 600/- sqm. Note:- Make of Tiles are in RAK, Kajaria, Marbito, Nitco only and spacer grout material Ultratech / Gresbond or equivalent or as per approved by Bank Engineer only)</p>	221.00	SQM.		
19	<p>GRANITE STONE (JET BLACK) Providing and fixing Granite Stone 16 to 18mm thick gang saw cut mirror polished (premoulded and prepolished) machine cut for kitchen platforms, vanity counters, window sills , facias and similar locations of required size of approved shade, colour and texture laid over 20mm thick base cement mortar 1:4 (1 cement : 4 sand) with joints treated with white cement , mixed with matching pigment , epoxy touch ups, including rubbing, curing moulding and polishing to edge to give high gloss finish wherever required etc complete at all levels. samples approved by Enginner-in-Charge. Basic price 1800/-per sqm.</p>				
	Granite fine grained dark black/ dark red / white with self design/ pattern/ crystal of other colours or glitters	29.00	SQM.		
20	<p>HILTI Chemical ReBaring in Existing R.C.C. Structure</p> <p>Providing and fixing at site chemical ReBaring make Hilti-HIT-RE-500 / HY-200R including proper drilling, Cleaning, chemical, equipments as required, manpower and pull test. Excluding reinforcement only, complete in all respect. Works as per directed by In-Charge. NOTE:- ALL SAFTY EQUIPMENTS, SCAFFOLDING & WORKING PLATFORM UP TO REQUIRED HEIGHT IN VENDOR SCOPE.</p>				
	Dia. 16mm	12.00	Each		
	Dia. 12mm	50.00	Each		
	Dia. 10mm	80.00	Each		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
21	Providing and laying water proofing treatment in sunken portion of WCs, bathroom & Wall surfaces(W.C., Bath, Kitchen) etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : a) 1st course of applying cement slurry @ 4.4 Kg/sqm mixed with water proofing compound conforming to IS 2645 in recommended proportions including rounding off junction of vertical and horizontal surface. b) 11nd course of 20mm cement plaster 1:3 (1 cement : 3 sand) mixed with water proofing compound in recommended proportion including rounding off junction of vertical and horizontal surface. Note:- In water proofing work chemical used Dr. Fixit Pidifin 2K / Sunanda Polyalk WP / Sika Top 107 Seal AE only.	60.00	SQM.		
22	WALL HUNG WASH BASIN Providing and fixing Wall Hung WASH BASIN including Full Thread waste coupling (Waste Coupling 32mm size full thread with 80mm / 130mm height), Brackets as per required , all fitting Hindware or equivalent, proper fixing line & level, testing etc.works as per directed by Engg. In-Charge. MAKE:- Hindware Cat-91248 OR Equivalent.	6.00	EACH		
23	PILLAR COCK Providing and Fixing PILLAR COCK with Aerator (Make Hindware or Equivalent) , proper fixing line & level, testing etc.works as per directed by Engg. In-Charge. MAKE:- Hindware Cat.-730001 OR EQUIVALENT.	6.00	EACH		
24	ANGULAR STOP COCK Providing and fixing heavy duty CP brass ANGULAR STOP COCK with wall flange of Jaguar make OR equivalent . Make:- Hindware OR Equivalent. Sample approved by Architects or Site In-charge. MAKE:- Hindware Cat.-850077 OR EQUIVALENT.	19.00	EACH		
25	BOTTLE TRAP Providing & Fixing BOTTLE TRAP (with internal partition) 32mm size with 250mm / 300mm and 190mm long wall connection pipes & wall flange. Make:- Hindware OR EQUIVALENT. MAKE:- Hindware Cat.-850072 OR EQUIVALENT.	10.00	EACH		
26	HOSE PIPE Providing and Fixing HOSE PIPE (Suitable for Basin), 450mm / 600mm Long Braided Hose with m10x1 nipple, 15mm nut, O-Ring and Rubber washer. Make:- Jaquar-ALD-803AB / 801B OR EQUIVALENT.	3.00	EACH		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
27	HEALTH FAUCET Providing and fixing Health Faucet / Hand shower with flexible water connection 1.0 mtrs. Long easy flex tube in chrome finish and wall hook in the toilet. Make:- Hindware OR EQUIVALENT. MAKE:- Hindware Cat.-160193 OR EQUIVALENT.	6.00	EACH		
28	ORISSA SQUATTING PANS Providing and fixing ORISSA SQUATTING PANS (Indian Type W.C. pans) size 580mmx440x300mm with 100mm sand C.I. 'P' or 'S' trap, low level, flushing cistern (PARRYWARE, HINDWARE, JAQUAR or equivalent) with fitting 32mm diameter galvanized, stainless steel flush pipe with fittings and clamps, 20 mm GI with spacers etc complete. including cutting and making good the walls and floors. MAKE:- Hindware Cat.-60003 OR EQUIVALENT.	1.00	EACH		
29	EUROPEAN W.C. Providing and fixing white vitreous china type water closet pedestal (Floor mounted European Type W.C pans make:-HINDWARE, JAQUAR or equivalent) including cistern for coupled WC with PP soft close seat cover, Hings, Accessories & fixing accessories. Any colour with matching superior quality seat Cover overcutting and making good the walls and floors. Make:- Hindware Cat. Cleo-20050 complete set or equivalent WITH CISTERN FOR COUPLED WC WITH PP SOFT CLOSE SEAT COVER, HINGS, ACCESSORIES AND FIXING ACCESSORIES.	5.00	EACH		
30	NAHNI TRAP Providing and fixing 100 mm dia heavy quality approved make PVC Nahani trap with 75 mm dia outlet , embedding the trap in cement concrete using 1: 3 : 6 mix with 20 mm metal complete including joining effluent pipe etc, and fixing 125 mm dia CP brass grating etc. complete.	14.00	EACH		
31	BIB-COCK WITH FLANGE Providing and fixing heavy duty CP brass BIB-COCK of Jaguar, Parryware or Equivalent with wall flange, extension Nipple etc. in all complete. Bib cock with wall flange, make:- Hindware cat. F730003 or equivalent. Sample approved by Architects or Site In-charge	2.00	EACH		
32	2-WAY BIB-COCK WITH WALL FLANGE Providing and fixing heavy duty CP, 2-WAY BIB COCK WITH WALL FLANGE of Jaguar make or equivalent, all work complete in all respect. Make:- Hindware cat. F730054 or equivalent. NOTE:- SAMPLE APPROVED BY ARCHITECTS OR ENGG. IN-CHARGE.	5.00	EACH		
33	STAINLESS STEEL TOWEL RAIL Providing and fixing STAINLESS STEEL TOWEL RAIL , 600 mm long HEAVY DUTY, including SS make screw or fasteners proper line and level as per directed by Engg. In-charge . Make:- Hindware cat. 880005 or equivalent	6.00	EACH		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
34	STAINLESS STEEL TOWEL RING ROUND WITH ROUND FLANGE Providing and fixing STAINLESS STEEL TOWEL RING ROUND WITH ROUND FLANGE HEAVY DUTY , including SS make screw or fasteners proper line and level as per directed by Engg. In-charge . Make:- Hindware cat. 880007 or equivalent	2.00	EACH		
35	TOILET ROLL HOLDER Providing and fixing TOILET ROLL HOLDER, HEAVY DUTY , including SS make screw or fasteners proper line and level as per directed by Engg. In-charge . Make:- Hindware cat. F102009 or equivalent	5.00	EACH		
36	SINK COCK Providing and fixing SINK COCK WITH REGULAR SWINGING SPOUT(WALL MOUNTED) , make of Jaguar /Parryware or equivalent approved make. Make:- Hindware cat. F730024 or equivalent	2.00	EACH		
37	SENSOR URINALS(AC/DC) WITH PARTITIONS Providing and fixing SENSOR URINAL (make:- Jaguar/Hindware or Equivalent. Wall mounted Urinal pot with indian sensor, size:- L290mm/W360mm/H690mm. Stylish ceramic urinal pot in white color with embedded sensor for automatic flushing, Deodorize feature of 24 hours voluntacily flush if no use. False flush protection with line indicator to representing sensing & flush ready modes. Including Division Partition, Required sensor electrical cable or Battery Operated with conduit pipe as per guide by company, Plumbing work:- Angle valve, urinal Domed waste coupling etc., all fitting, proper fixing line & level, testing etc. Works as per directed by Engg. In-Charge. Make:- Hindware cat. Urinal Flow Cat. No. 60021, Partition-Division Plate-61001 or equivalent	4.00	EACH		
38	PVC PIPES Supplying and fixing approved quality of rigid SWR (TYPE-B) PVC pipes(All Vertical Pipes on Wall SURFACES used PUSHFIT AND HORIZONTAL SURFACE USE SOLFIT PIPE AND FITTINGS) of Astal / Ashirvad make or equivalent , jointing the pipe and including required Fittings(Bend, Elbow, Y-shape with Door, Coller, Socket, etc.) with suitable solvent as per manufacturers specifications, laying the pipes under floor , ceiling or on the walls as per the required gradient including providing necessary support, clamps, scaffolding etc. conveying the materials to all floors making holes in masonry or concrete cutting the pipe to required length, testing to a head of 1.8 m for horizontal pipes and for vertical pipes by filling with water etc. complete including necessary scaffolding at all levels as required. Note:- Including Existing Pipe removing and placing as per directed by Engg. In-Charge.				
	(a) 40/50 mm Dia.	10.00	Rmt		
	(b) 63 mm Dia.	10.00	Rmt		
	(b) 75 mm Dia.	30.00	Rmt		
	(d)110 mm Dia.	80.00	Rmt		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
39	Providing and fixing Steel Kitchen sink-Glossy (Nirali make:- Eureka Deluxe Small or Equivalent) Over all size are 625mmx445mm(24.5" x 17.5") Bowl size are 21"x14:x8" on the kitchen platform including providing and fixing base coupling and Drain Pipe up to Trap etc. complete with cleaning and finished as per directed by Engg. In-Charge.. Make:- Nirali Sink / Nilkhantah or Equivalent, Sample approved by Architects or Site In-charge.	2.00	EACH		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
40	Providing and fixing G.I. Pipe ('B' Class) complete with G.I. fittings(Reducer, Union, socket, Elbow etc.) and clamps, including cutting and making good the walls, required excavation on ground, back filling etc. All works as per directed by Engg. In-Charge. Note:- Connecting to existing or New line.				
	40mm Dia. ('B' Class)	5.00	Rmt		
41	CPVC PIPE-SDR-11 Providing and fixing in position Chlorinated Polyvinyl Chloride(CPVC) SDR-11 pipes and fittings having thermal stability for hot and cold water supply including all CPVC plain and Brass threaded fittings i/c fixing the pipes with clamps at 1.00 M spacing . This rate includes jointing of pipes with one step CPVC solvent cement, cost of cutting chases in wall/floor etc. and making good the surface for Concealed piping work etc.complete.				
a	20 mm dia. nominal bore	36.00	METRE		
b	25 mm dia. nominal bore	250.00	METRE		
c	32 mm dia. nominal bore	0.00	METRE		
42	Providing and fixing CPVC Schedule80 BALL VALVE approved quality, including necessary fitting and required for connections. NOTE:- BRASS THREADED (TWO SIDE)				
a)	For 20mm NB	2.00	EACH		
b)	For 25mm NB	5.00	EACH		
c)	For 32mm NB	1.00	EACH		
43	Providing and laying average 65mm thick CC 1:2:4 for base concrete for Toilets in proper slope. All works as per directed by Engg. In-Charge.	10.00	SQM.		
44	BEVELLED EDGE MIRROR Providing and fixing 750x600mm bevelled edge Mirror of superior glass approved quality complete with SS stud fitting OR C.P. brass screws and washers, complete in all respect as per instruction of Engg. In-Charge.	5.00	EACH		
45	WPC DOOR FRAME(90MM X 45MM) Supply and Installation factory made 100% solid wood plastic composite(WPC) Door Frame 90mm x 45mm made from wood plastic composite (single extruded process) material with density 780kg / cbm and manufacture by Rajshri plastiwood or Equivalent. Door frame should be water proof, Termite proof, Fire Retardant and having good screw holding capacity etc., complete in all respect. Standard make Rajshree or equivalent . Note:- Including existing Door frame and Shutter remove all debris dump as per directed by Engg. in-Charge.	83.00	RM		
46	28MM THICK WPC DOOR SHUTTER Providing and fixing Rajshri Brand or Equivalent factory made 100% solid WPC Flush Door Shutter 28mm thick, made fromco-Extruded WPC smooth finish foam sheet as per stander density and manufacturing by an ISO-9001-2015 certified company. The cost of include all fitting, accessories etc., complete in all respect. Note:- Sample approved by Architects or Engg. In-Charge.	28.00	SQM.		
48	CEMENT FIBER BOARD PARTITIONS UPTO SLAB BOTTOM FROM FLOOR LVL. HEIGHT (PARTITION THICKNESS 75MM TO 80MM APPROX.)				

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
	Providing and Fixing 12mm Everest cement fiber board is non-combustible and has an A1 fire rating, meaning it will not ignite and does not contribute to the spread of fire. It is designed to withstand fire and offers superior fire protection, though a specific fire rating in hours (like 1 or 2) partition in double skin partion with under framing of 50 mm x 50 mm X 2.6mm THICK @ 3.76kg/metre M.S. PIPE Frame @ 1.0M C/C BOTHWAYS(including required base plate, fastners etc.) placed with 12mm thick CEMENT FIBER BOARD fixed on both faces with 2 COAT WALL PUTTY WITH JOINT TAP AND 2-3 COAT EMULSION COLOR IN ANY SHADE on all exposed faces. Necessary slots to be made for cable management in co-ordination with electrical contractor. complete as per drawing and direction of Bank engineer & Architect. (Working as per detailed drawing). Note:- Gap between partition wall filled by namda or as per directed by bank engineer.	90.00	SQM		
49	PARTIALLY GLAZED FULL HT. PARTITION (PARTITION THICKNESS 80MM TOP 90MM APPROX.)				
	Providing & fixing wooden partitions (double skin) full height with under framing of Aluminium section rectgular pipe(heavy duty) Frame @ 1.0M C/C BOTHWAYS INCLUDINGCLEATS, SCREWS, FASTNERS ETC. and 12 mm thick MR PLYWOOD fixed on both faces , with laminate 1.0 mm thick on all exposed faces. The panels shall be equally divided and shall have provision of openable door 800/900/1000 mm wide with butt hinges, Door Closer, Handles, locking arrangement etc. complete. The glass panels 6 mm thick shall be fixed with mouldings/ leaping and film as per design. The under frame shall be properly anchored with the beam bottom/ ceiling fitting with anchor fasteners for a strong and sturdy partition. The surface shall be painted or fixed with laminate as per architects drawings. Necessary slots to be made for cable management in co-ordination with electrical contractor for required cabling and switch socket fixing. The rates shall include all material, hardware, wastages, labour, cost of polishing & painting etc complete. Mode of measurement is only one side surface area not including above false ceiling. (Working as per detailed drawing.) NOTE:- LAMINATE SHADE APPROVED BY ARCHITECTS. ALL WORKS EXCUTE AT SITE AS PER WORKING DRAWINGS GIVEN BY ARCHITECTS.	160.00	SQM		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
50	ACOUSTICAL WALL PANELING				
	Providing and installation of acoustical wall panelling wood finish Slats made out of MDF board , Melamine / veneer laminated finish, perforated wooden grooved slats (2mm grooves @ 8mm centers) / (2mm Slats @16mm pitch) / (2mm grooves @ 32mm centers) / (2mm grooves @ 64mm centers), backlined with black acoustical fleece, tongue-groove edge for a seamless look, FR grade, of lineal dimension size 128mm x 2440mm x 16mm thick having density 1000Kg /m3, weight 12.8Kgs/m2 installed by using GI strut system. The GI strut system includes GI Cross channel having thickness 0.45mm, length 3600mm, knurled web 40mm, depth 10mm and equal flanges 15mm is fastened vertically/horizontally at every 600mm centers. Aluminium core cross channel having thickness 0.5mm, length 2400mm, web 15mm and 27mm, depth 18mm and flanges of 7mm with suitable edge and centre brackets is then fixed perpendicular to the cross channel with the help of fasteners at every 400mm centers. Contractor to Provide expansion joints of 3mm at every 5mts both ways. Make. Armstrong / Gyptek / Calsi.	32.00	SQM		
51	Providing & Fixing Hi-Acoustic Fabric Wall Panelling with 25mm thick stretch half wrap/ full wrap rigid vinyl tracks to be fix on existing surface with pvc insert and screws as required pattern in panel as required module. 25mm thick acoustic rockwool pad of 100kg density to be fill in panel fixed by rubber adhesive approved Hi quality fabric to be grip in stretch track by tucking tools to make panel in proper line and level along with wrinkle free. The stretch track create V groove / Butt joint in each panel maximum width of the panel is not more than 1200mm in width and length as required size. Fabric to be selected from standard shade card. Including 12mm thick(Fire retardant plywood conforming to IS: 5509) panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25mm to 40mm thick.Make:- Ecotone, Armstrong, MMT-Acoutix or equivalent, sample approved by architects or Engg. In-Charge.	170.00	SQM		
52	Veneer Wall Panelling:-Providing & Fixing wall panelling consisting of 4mm thick veneer ply fixed over 12/18mm thick Commercial Ply Fixed by Fevicol SH with Hardware etc. Complete. Including Melamine polishing PU FINISH on Doors /Windows by preparing the surface applying putty base course. Prepare the surface smooth by sand papering and then applying melamine polish with air compressor. Two or more coats on new works including a coat of wood filler. Including materials, Labour etc.	21.00	SQM		
53	MORTISE LOCK				
	Providing and fixing Mortise Lock (Make:- Godrej or Equivalent as per approved) in position 6 Lever Night Latch Lock(Inside Opening) to doors. I/c all labour, hardware and providing Door handles of Brass/Stainless Steel as approved. etc. complete The job shall include all material,labour, wastages etc. complete. Make:- Godrej, Yale.	6.00	SQM		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
54	WALL PANELLING				
	Providing & fixing upto false ceiling height panelling on existing walls with under framing of 80 mm x 60 mm X 1mm THICK ALUMINIUM PIPE Frame & covered with 12mm thick MR Plywood screwed over the frame(treated for termite painted with fire retardant paint).All finished faces shall be provided with laminate (1.0 mm thick) of approved shade & quality. The top moulding shall be 50mm x 50mm first quality T.W. as per architects drawings. The panelling shall have provision for power cabling at sill level (75 cm from FFL) and communication cabling at skirting level, by providing T.W. removable section 19mmx150 mm as per architects detailed drawings. The rates shall include all necessary hardware, material, labour wastage etc. complete. NOTE:- Design and details shall be as per directed by Engg. In-Charge or Architects and Bank's new uniform colour, layout and elevation policy.	35.00	SQM		
55	TOUGHNED GLASS FOR PARTITION ABOVE 300MM WOOD PARTITION (Manager Cabin).				
	Providing and fixing 12mm thk. Toughened Glass for Door panels including required fitting as per approved, Floor spring, Door handle, Door Lock, Etching as per design and the glass shall have necessary required fitting around teak wood moulding/beading/cornices as per requirement with polish. The cost shall include all labour,, transportation to site, fixing etc. complete in all respect.	2.00	SQM		
56	WEATHER COAT EXTERIOR EMULSION PAINT(APEX ULTIMA)				
	Providing and applying two or more coats of Apex Ultima or equivalent make weather proof exterior emulsion paint of required shade after thoroughly brushing the surface free from mortar dropping and other foreign matter, including one or two coats of primer, applying two coats of Birla White putty including preparing the surface even and sand papered smooth etc. necessary scaffolding at all level, complete as directed at site. NOTE:- ALL SAFTY EQUIPMENTS IN VENDOR SCOPE & Existing painting area proper removing.	823.17	SQM.		
57	M. S. FABRICATION WORK FOR TRUSS, PURLIN, GRILL DOOR, Channel gate etc. & RETROFITTING WORK ETC.				
	Providing and fixing at Site M.S.Fabricated Steel structure made out of M.S.Sections, Pipes, Channels, Angle etc. as specified by the Architect in the drawings /details for Truss, Purlin, Gate, Channel Gate, Grill etc. . Made out of ISA, Sq. M.S.Bar, Flat, Square & Round M.S. Pipes etc. supported on Concrete Bed Blocks casted over Brick Walls as specified in the Drawings/Details . The structure shall be Welded by Arc Welding of superior quality using best quality Electrodes and Standard Welding Equipment, Chisel cutting, bending, grinding, drilling etc. hammering excess deposits and then finishing with surface grinders. The Rates includes Cost of Anchor Bolts, Washers, Nuts, Cost of Scaffolding , 2 or more coat Painting with Superior Quality Steel Primer (Asian ,Narolac, Deluxe)or Equivalent approved by the Architect and the Cost of All Material , Wastages, Labour , Cost of T&P etc Complete.	5750.46	KG		
58	PUF Sandwich Galvanised Panels for Roofing & Cladding				

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
	Providing , Fabricating and fixing in position PUF /PIR Sandwich Panels with Prepainted Galvanised Sheets on both faces.Top sheet 0.5 mm and Bottom sheets 0.5mm thick prepainted with PUF insert 50mm thick actual width 1.06 M but effective width 1.00 M with tongue and groove arrangement for water tight arrangement. The Top sheet shall be corrugated profile with minimum core thickness 40 mm of Green Colour and Bottom sheet off white colour with groove pattern 2mm thick 62.5 mm C/C. It shall be fixed over existing M.S.Structure Purlins with self drilling self tapping screws of suitable length and superior quality. The Sheets shall be painted with Polyester primer 5 micron , Non toxic food graded standard polyester finish paint.RAL 9010 Colour-20 micron , Resistant to saline mist and resistant to moisture .The rates includes cost of all material, wastages, cost of scaffolding , all T&P etc complete. Manufacture:- RINAC INDIA LIMITED, VIRAT INDUSTRIES, Alfaa PEB Limited or Equivalent	226.00	SQM.		
58-a	G.I. Gutter, Providing and fixing G.I.Sheet Gutter in C-shape as per drawing, thickness of sheet 1.5mm including proper fixing as per given slope required water tight fastners, proper over lapping with water tight, zinc coating primer on both side (specification given as per above item) and providing down take pipe slot and fixing as per drawing or Engg. In-Charge. complete in all respect.(C-Shape Gutter over all Girth up to 900mm)	12.00	RM		
58-b	Providing & fixing Precoated L-FLUSHING (400mm WIDE)galvanised steel sheet roofing accessories 0.50mm + 0.05% total coated thickness, zinc coating 120 gsm as per IS:277 in 240 mpa steel grade, 5-7 micron epoxy primer on both side of the sheet and polyester top coat 15-18 micron using self drilling / self tapping screws etc. complete. Note:- Top coat colour match to roofing sheet colour	30.00	RM		
59	SUSPENDED FALSE CEILING (Armstrong Silhouette Grid)				
	Supply & fixing of tiles false ceiling system open cell tile of size 600x 600mmx12mm thk. manufactured out of glass reinforced gypsum with non combustible to gypsum casting plaster reinforced with glass fibre. Tiles to be installed on a standard 600 x600 mm grid made up of main runner at 1200mm and cross tees of 600mm armstrong Silhouette Grid so as to be provided with slab in couplings for installation. the grid is to be suspended from the roof with GI butter fly rods or quick adjustment suspension hanger at maximum 1200mm distance along with main runners. Armstrong approved brands tiles as per Silhouette ceiling grid shall be laid in mounting from below on the standard grid. Hanger to be fixed to roof by steel expansion fastners etc all complete.The rates includes the cost of making necessary cut-outs for lights / Air-Conditioning Grills as per design, all material labour ,wastages cost of scaffolding etc complete. NOTE:- Sample approved by bank engineer.	697.03	SQM		
60	GYPSON FALSE CEILING				

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
	Providing and fixing Gypsum Board suspended false ceiling, which includes providing and fixing G.I. Perimeter channels of size 0.55mm thick having 1 flange of 20mm another flange of 30mm & a web of 27mm along with perimeter of ceiling, screw fixed to brick wall / partition with the help of nylon sleeves and screws, at 610mm centres. Then suspending G.I. intermediate channels of size 45mm, 0.3mm thick with two flanges of 15mm each from the soffit at 1220mm centres with steel expansion fasteners. Ceiling section of 0.55mm thickness having knurled web of 51.5mm and two flange of 26mm each with lips of 10.5mm are then fixed to the intermediate channel only gypsteel frame work to be used at 457mm center 12.5mm tapered edge Gypboard screw fixing is done mechanically either with screw driver or drilling machine. All jointed and finished so as to have a flush look which includes filling and finishing the tapered and square edges of the board with jointing compound, paper tape and two coats of primer. Provision for light fittings, grills and other fixtures to be made as per standard arrangements. Painting of the ceiling of approved shade and quality as desired. Make:-	20.00	SQM		
61	HYDRAULIC DOOR CLOSER-DORMA, Providing and fixing Hydraulic Overhead Door Closer Ts-71, make:- Dorma. Including required tools & takles, fastners, technician, manpower etc. Sample approved by architect or engg. in-charge.	4.00	EACH		
62	TOUGHNED GLASS DOORS IN 12mm THICK Providing, and fixing 12mm thk single/double shutter <u>Toughned glass doors, at entrance</u> , etc. (each door shutter counted individually) of size 2.10 m ht x (0.75 m - 1 m wide) (approx. as per site measurment) as demarcated, swing type door openable both sides made out of 12 mm thk. clear toughened float glass, edge polished, fixed in wooden top & bottom rails of approved colour & finish, fixed on Everite/ozone/ Hardwyn/ Dorma or equivalent floor springs set, upper patch, lower patch, lock key plate, provision of locking system, etc. as per approval. One set of 25 mm dia S. S. brush finish pull handles (approx. 300mm length) "C" shaped, of appoved make & design on both sides. Including providing "PUSH" * "PULL" sticker lables of approved design & make. The rate to include all materials, labour, transport, taxes, delivered and placed in position at site of work. Each door shall be treated individually with complete set of accessories to be provided on each door.	14.00	SQM.		
	FURNITURE ITEMS (ALL MODULAR FURNITURE MAKE IN AFC, IMPRESSION FURNITURE INDUSTRIES, GODREJ, DURIAN, NILKAMAL OR EQUIVALENT OR AS PER DIRECTED BY ENGINEER IN-CHARGE. SAMPLE APPROVED BY ARCHITECT / BANK ENGINEER.				
63	Supply and Installation of factory finished made furniture of Reception counter, Overall Table Size:- Length (In mm) 1800 Width (in mm) 600 Height 1 750/H2 1000mm Table Top Made From 25mm Thick Prelam Particle Board Gable End Made From 18mm Thick Prelam Particle Board Modesty Made From 18mm Thick Prelam Particle Board Modesty Height Will be 600mm All open Edge covered with 2mm/0.8 Thick Edge Band As per Design Requirement. Including all exposed surface finshed by laminated. Note:- Before supply the item sample approved by bank engineer or architect should be must.	1.00	EACH		
					

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
64	Supply and Installation of factory finished made furniture of Meeting Table, Overall Table Size:- Length (In mm) 3600 Width (in mm) 1650 Height 1750 Table Top Made From 25mm Thick Prelam Particle Board with 36mm of Edge Effect Gable End Made From 18mm Thick Prelam Particle Board Modesty Made From 18mm Thick Prelam Particle Board Modesty Height Flapper would be available for better electric switch board, LAN point slote connectivity. Note:- Before supply the item sample approved by bank engineer or architect should be must.	1.00	EACH		
					
65	Supply and Installation of factory finished made furniture of Conference Table, Overall Size of Table -5700X2100x750mm with 3 Electric Box on Top, Table top made of 18mm Thick PLMDF Board with PU Paint. Edge Covered with 2 MM /0.8mm Thick PVC Edge Band As per Product and design requirement, with 4 Box Assembly in Understructure made up of 25mm Thick PLMDF. Modesty are made up of 18mm Thick PLMDF with 9mm Decoratives Panels .Overall Product as per image.Finish-Swede. Note:- Before supply the item sample approved by bank engineer or architect should be must.	1.00	EACH		
					
66	Supply and Installation of factory finished made furniture of Meeting Table, Overall Table Size:- Length (In mm) 4500 Width (in mm) 1650 Height 1 750 Table Top Made From 25mm Thick Prelam Particle Board with 36mm of Edeg Effect Gable End Made From 18mm Thick Prelam Particle Board Modesty Made From 18mm Thick Prelam Particle Board Modesty Height Flapper would be available for better electric connectivity. Note:- Before supply the item sample approved by bank engineer or architect should be must.	1.00	EACH		
					
67	Supply and Installation of factory finished made furniture of CM Cabin Table, Overall Size of Table -1500X750x750mm, Table top & Gable made of 25mm Thick PLMDF Board and modesty made from 18mm Thick PLMDF BOARD. with Aluminium profile in side of main Table. Edge Covered with 2 MM /0.8mm Thick PVC Edge Band. Overall Product as per image.Finish-Swede. Side Unit-Overall Size -L-900xD-450XH- 690mm, Made from 18mm Thick PLMDF Board.. Note:- Before supply the item sample approved by bank engineer or architect should be must.	5.00	EACH		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
					
68	<p>Supply and Installation of factory finished made furniture of CM Cabin Table, Overall Size of Table -1800X750x750mm, Table top & Gable made of 25mm Thick PLMDF Board and modesty made from 18mm Thick PLMDF BOARD. with Aluminium profile in side of main Table. Edge Covered with 2 MM /0.8mm Thick PVC Edge Band.</p> <p>Overall Product as per image.Finish-Swede. Side Unit-Overall Size -L-900xD-450XH- 690mm, Made from 18mm Thick PLMDF Board.. Note:- Before supply the item sample approved by bank engineer or architect should be must.</p>	1.00	EACH		
69	<p>Supply and Installation of factory finished made furniture of Round Table for Cafétaria area , Size of Table -Dia. 1000mmx750mm(Ht.), Top-Made From 25mm PostLam MDF, Edge Covered with 2 MM /0.8mm Thick PVC Edge Band As per Product and design requirement. Metal Legs 76 OD , Base Plate 6mm Thick MS Sheet. Overall Product as per image.Top Finish- Swede.Understructure Black Powder Coated. Note:- Before supply the item sample approved by bank engineer or architect should be must.</p>	6.00	EACH		
					
70	<p>Supply and Installation of factory finished made furniture of 8 seater Workstation Back to back , Overall each seating size would be W1050mm*H1200/750mm(Top Height)*D600mm Table top made of 25mm thick Prelam particle board 60 mm Powder coated front Alluminium partation and size L1050mm*H1200*60mm would be available with 32 mm writtern partation size W600*H1200*32mm with combination of pinup fabric board with acoustical material and clear glass with out pedestal, Including slots/space for electrical switch board, LAN point, Telephone point etc. Note:- Before supply the item sample approved by bank engineer or architect should be must.</p>	11.00	EACH		
					

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
71	Supply and Installation of factory finished made furniture of 3 seater Liner Workstation , Overall each seating size would be W1050mm*H1200/750mm(Top Height)*D600mm Table top made of 25mm thick Prelam particle board 60 mm Powder coated front Alluminium partation and size L1050mm*H1200*60mm would be available with 32 mm writtern partation size W600*H1200*32mm with combination of pinup fabric board and clear glass with out pedestal. , Including slots/space for electrical switch board, LAN point, Telephone point etc. Note:- Before supply the item sample approved by bank engineer or architect should be must.	3.00	EACH		
72	BLACKOUT ZEBRA BLINDS FOR WINDOWS				
	Providing and fixing Vertical Blinds manufactured by VISTA / HUNTER DOUGLAS or equivalent to the following specifications:				
	Basic rate 225/- per sqft.				
	<p>1. Blinds Type Sheer Dimout Zebra Blinds.</p> <p>2. Fabric 1. Composition: 100% Polyester. 2. Min. Fabric Thickness: 0.6 mm. 3. Min. Fabric Weight: 200 GSM 4. Stripe Size: Solid-10cm /Sheer-7cm. Control Unit To be made of high strength reinforced plastic; clutch to be made of high carbon steel of wrap spring design to transmit motion from the driven mechanism. Clutch is to be operated directionally by the use of beaded endless chain to raise and lower the blind smoothly to decide height.</p> <p>4. Idler To be made of high strength reinforced plastic, consisting of an outside sleeve and center shaft.</p> <p>5. Valance Rail Made of aluminum extruded section of high strength Al. alloy and powder coated in white. Size: 84 mm Width; min. weight 320gms/running mtr.</p> <p>6. Ceiling Rail Aluminum Extruded Rail made up of High Strength aluminum alloy and powder Coated in White. Size: 75 X 12mm; Min. Weight= 480gms/running mtr.</p> <p>7. Roller Tube Made up of High Strength Anodized Aluminum alloy Extruded grooved tube. Size: 40mm outside diameter, min. weight = 220gms/running mtr</p> <p>8. Bottom Rail Round type and made up of high Strength Aluminum alloy extruded tube and power coated in white. Size: 14mm outside dia.; Min. weight: =220gms/running mtr</p> <p>9. Operating chain To be made of 4.5 mm plastic beads molded on 2.0 mm thick</p>	38.40	SQM		
	Note:- Sample approved by Engg. Incharge or Arcitects.				

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
73	Providing and fixing of Composite perforated MDF board with Glass wool Fiber panel of Size 595x595x18 mm 10mm Square Perforation tiles (Square /Tegular Edge) false ceiling in true horizontal level suspended on interlocking metal grid of hot dipped galvanized steel section (Galvanized @ 120 gms/sqm both sides inclusive) consisting of main "T" runner with suitably spaced joint to get required length and of size 24x32 mm made from 0.30 mm thick (minimum) sheet spaced joints to get required length and of size 24x26 mm made of 0.30 mm thick (minimum)sheet spaced at 1200 mm long spaced between main "T" at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.4 mm and laying false ceiling tiles of approved Perforation in the grid including, wherever required, cutting/ making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors, etc. Main "T" runners to be suspended from ceiling using GI slotted plates of size				
	27x37x25x1.6 mm fixed to ceiling with 12.50 mm dia and 40 mm long dash fasteners, 4 mm GI adjustable rods with galvanized butterfly level clips of size 85x30x0.80 mm spaced @ 1200mm centre to centre along with main T, bottom exposed width of 24mm of all T-sections shall be pre painted with polyester paint all complete at all heights as per specifications and drawings and as directed by Engineer-in-Charge.	250.00	SQM		
74	Providing and fixing Thermal insulation of ceiling (under deck insulation) with Resin Bonded Rockwool conforming to IS: 8183,density 48 kg/ m3, 50 mm thick, wrapped in 200 G Virgin Polythene bags fixed to ceiling with metallic cleats (50x50x3 mm) @ 60 cm and wire mesh of 12.5mm x 24 gauge wire mesh, for top most ceiling of building. Make:- Neo-Thermal Insulation(India) Pvt. Ltd., Aerolam, Patidar or Equivalent. Sample approved by Engg. In-Charge.	250.00	SQM		
75	Buy-back of existing wooden glazed partition wall including removing at site, transportation, manpower etc.	-45.00	SQM		
76	Buy-back of existing false ceiling with grid including removing at site, transportation, manpower etc.	-120.00	SQM		
77	Buy-back of existing shed inside the premises, including removing of structural steel, roof sheeting, wall dismantling, floor area dismantling etc. all floor surface area proper clean and manpower, transportation in vendor scope. All work as per directed by engineer incharge.	-1.00	LS		
78	For Site Development Cement Concrete paver blocks 60mm thk. (Grade M-35) Providing and laying factory made coloured chamfered edge Cement Concrete paver blocks of required strength, thickness & size/shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of fine sand or Stone Dust, compacting and proper embedding/ laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with jamuna sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in footpath, parks, lawns, drive ways or light traffic parking etc. complete as per manufacturer's specifications & direction of EngineerinCharge. 60mm thick C.C. paver block of M-35 grade with approved colour, design & pattern. Note Sample approved by Architect with Engg. In-Charge.	150.00	SQM		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
79	Dismantling and Removing R.C.C. ROAD WITH STEEL REINFORCEMENT any thickness including all debris remove from site(All dismantled material remove from site in vendoe scope, distance any) including manpower, machinary, transportation, safety equipments etc.. Note:- Working levels at road level.	15.00	CUM.		
80	Excavation for foundation of walls, column footings, pile caps, raft, foundations, plinth beams, steps, water tanks, cess pits, etc., in all types of soil including soft or hard moorum, boulders (upto 0.10 cum) shoring the sides wherever necessary, bailing out of water and keeping the foundation trenches and pits dry including back filling the pit or trenches by selected earth in layers not exceeding 25 cm., watered and consolidated, spreading the surplus material within plot and carting away the surplus materials out of site, all complete as directed depth of pit below paver lvl. 1.50 m.				
	Depth upto 1.5m from NGL	50.00	CUM.		
81	Providing and laying P.C.C. 1:3:6 level ling course with 40 mm down gauge aggregate, in foundations, pits, raft material in the plinth and leap concrete etc. including required form work, consolidation, curing etc., complete.	15.00	CUM.		
82	Providing and filling in plinth with hard muram/ hard copra under floors including watering ramming consolidating in layer not exceeding 20cm in depth & dressing complete.	25.00	CUM.		
	filling also in porch area				
83	Providing & casting in 1: 1.5: 3 concrete in footings, raft slabs, Retaining Wall, Pedestal, Strom water Drain Wall with Raft, Chambers etc. as per design and drawings, including the form work, mechanical compaction, etc. completed with curing (Rate exclusive of reinforcement). Note:- All concreting work below plinth to first floor slab level.	25.00	CUM.		
84	Supplying and placing in position by cutting, bending & fabricating tested quality steel reinforcement for R.C.C. work, including dowels of required diameters and lengths as per design & as directed, including typing using good quality binding wire and/or welding, providing required cover with concrete briequests, spacer pieces, chairs, etc. as required complete.				
	a) High Tensile deformed bars Fe-500	2750.00	kg		
85	Providing and laying 110mm thk. Perforated R.C.C.(M-25) Drain Cover, size 1000mm x 800mm, provision of removing hook, proper size and finishing as per directed by bank engineer. Including steel reinforcement as per given drawing, centering & shuttering, outer frame made by M.S. angle.	50.00	Each		
86	Providing and laying 300mm Dia. R.C.C. Humepipe-NP2 garde , including excavation, base P.C.C.(50mm thk.), Coller joint with cement mortar, slope maintain, backfilling. Complete in all respect. As per directed by bank engineer.	35.00	RM		
87	Brick masonry manhole(Including excavation, P.C.C. 200mm thk. Brick Work, Internal & External Plaster and R.C.C. Top cover) Constructing brick masonry manhole in cement mortar 1:4 (1cement: 4coarse sand) R.C.C. top cover in M-25), foundation concrete 1:4:8 mix (1cement: 4coarse sand: 8graded stone aggregate 40mm nominal size) inside plastering 12mm thick with cement mortar 1:3 (1cement: 3coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1cement: 2coarse sand: 4graded stone aggregate 20mm nominal size) finished with a floating coat of neat cement complete as per standard design. Note:- Including Inside size 90x80cm and 60/45cm or more deep including R.C.C. cover. Bricks in 1st class well burnt chimney.	5.00	Each		

S.NO.	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
88	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and mirror polishing	40.00	SQM		
89	Providing water proofing treatment over roof, walls, chajjas, balcony with rubberized elastomeric cold applied liquid waterproofing mambrane blend of special resin and rubber with more than 1300% elongation (confirming ASTM-D2370-98) at leakage / seepage area consisting of the following operations--:- a). Removal of damaged waterproofing treatment if, any like bituminous membrane/ plaster / brick bat coba / screeding etc. b). Surface preparation: Roughening of surface by scrubbing with steel wires / nylon brush / removing all dust particles and washing with adequate water to clean completely, opening of cracks in 'V' groove and repair. Providing and applying 1st coating of rubberized elastomeric liquid membrane as primer (ratio 1:2, one part liquid membrane and 2 part water by brush / roller / spray having minimum thickness of 70-80 microns. Allow the coating to set in natural air for minimum 2 hours, then put reinforcement by laying 45 GSM fibre glass mess and applying two or more coat required as per site conditions of rubberized elastomeric liquid membrane (Ration 1 part membrane and 20% water) with minimum thickness 100-120 microns allow the coating to set in natural air for minimum 12 hours complete in all respect.	963.00	SQM		
TOTAL AMOUNT OF CIVIL AND INTERIOR WORKS					

GST Extra as applicable

Seal and Signature of the Vendor