



STATE BANK OF INDIA  
LOCAL HEAD OFFICE PATNA

DATE : \_\_-12-2025

ADMINISTRATIVE OFFICE MUZAFFARPUR

Name of the work:- INTERIOR DECORATION & FURNISHING WORK OF PARSAUNINATH BRANCH UNDER RBO  
MUZAFFARPUR

PRICEBID

Sl.No	Description	Unit	QTY	Rate (RS)	Amount
1	<b>BACK CABINET of BM, CABINET BELOW GRANITE COUNTERS IN PANTRY AREA 750MM HT</b>	Sqm	3.00		
	Making and fixing low type storage cabinet with drawer and cupboard with shelf as per the drawing / design all made of 19 mm thick BWR block board of Green/Century /Mayur/aSEAN/Tajpuria or equivalent/ Exterior Grade MDF board of Green/Century or equivalent top and front laminated with 0.8 mm thick blue / white high glosive laminate of Green/Marino /century/Durian or equivalent . Drawer shall run of 'Z' type drawer slides with PVC rollers. All inside portion shall be painted with matt finish enamel paint and all wooden surface shall be melamine/sprit polish. All work to be completed work with necessary and required hardware of standard quality as per approved materials Colour laminate and specifications. This includes cabinets as per requirement in kitchen. Shutters shall be hinged to the framework and finished with 0.8mm thk. PVC Laminate of approved shade for kitchen cabinets from outside, applied with approved oil paint from the inside and edges of shutters with steam beach lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				
2	<b>FRAMED GLASS DOOR/FIXED GLASS WITH PATCH FITTING MAIN ENTRY/CM CABIN</b>				
2.1	Providing and fixing framed fully glazed 12mm thk <b>toughened</b> glass fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall <b>include</b> necessary etching film / LOGO, approved patch fitting locking systems, 1 pair of 12" long S. S. (C Shape) Handles of approved make, floor springs, and any necessary hardware items.(ABOVE MENTIONED MAKES Top Pivot , Top Patch Fittings, Bottom Patch fittings , Floor Spring , Corner lock with strike plate and Euro Profile Cilinder, C Shape Handle 25mm dia X 300mm length) AND/ OR FRAMED FIXED GLASS TOUGHENED WITH WOODEN FRAME	Sq.M	15.00		
3	<b>FROSTING FILM ON CLEAR GLASS</b>	Sq.M	14.50		
	Providing and fixing Non-reflective matte, frosted, scratch resistant, high performance resin coated polyster film with required frosting pattern on the glass surface complete as per the directions of EIC/ Architect (Payment shall be made for the finished area of the film actually provided. No deduction shall be made for openings upto 0.1 Sq.m. area each and nothing shall be paid extra for making such openings.) 3M - CRYSTAL GLASS FINISHES 7725 SE325				

<b>4</b>	<b>GYPSON FALSE CEILING</b>				
	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS : 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with				
	wedge of 80 mm with tapered flanges of 26 mm each having clips of 10.5 mm at 450 mm centre to centre shall be fixed in a direction perpendicular to G. I. channel with connecting clips made out of 2.64 mm dia x 230 mm long G. I. wire at every junction including fixing the gypsum board with ceiling section and perimeter channels				
	including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge including the cost of putty and painting with				
	Plastic Emulsion paint on gyp board false ceiling: Wall/ceiling painting with plastic emulsion paint of approved brand and manufacture to give an even shade in Two or more coats on new work. White cement based putty on false ceiling: Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.				
	Rate includes cutting, adjusting the existing 2'x2' false ceiling alignment etc so that its aesthetic look shall be retained.				
A	12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) For the area where vertical design etc to be done measurement shall be made in running metre for the verticals and shall be payable additional to plan area.	Sq.M	50.00		
<b>5</b>	<b>OFFICER'S TABLE</b>				
	Providing and fixing the Officer's table made out 19mm BWP ply board (10yrs warranty) with 0.8mm laminate as per drawing detail enclosed, storage unit with 3 drawer, and keyboard and pencil drawer on channels, cable manager, and laminated apron to match decor. Drawer unit and verticals made out of 19mm BWP ply board with keyboard drawers, PC stands for PC below worktop and 12mm ply board for footrest. All Drawers to be provided with Godrej lock & SS handle of approved make. The exposed side of front facade, drawer front shall be finished with 0.8mm laminate as per drawing. the inside surface also finished with white/blue colour paint as per approved A/E/I/Bank.				
	<b>OFFICER TABLE</b>				
a	(6'0"X3'X2'6" ) LXWXH WITH 3'6"X1'6"X2'6" CREDENZA	Nos	1		
b	(5'0"X2'6"X2'6" ) LXWXH WITH 3'X1'6"X2'6" CREDENZA	Nos	1		

6	<p><b>FALSE CEILING (GYPSUM TILE GRID)</b></p> <p>Providing and fixing of Gypsum tile false ceiling tile of size 600mm x 600mm x 9mm with square / tegular edge at all heights laid on Prelude XL Hot dipped galvanized exposed grid with 15 m with T-Section exposed flingers which shall be powder coated white. The framework will comprise of main Runner made from 0.33 mm thick GS sheet and of size 24 mm x 38mm x 3600 mm and spaced at 1200 mm centre securely fixed to the structural soffit by approved hangers at 1200 mm maximum centre. Hangers (GI wire of 4.0 mm diameter) to be fixed by approved Rawl plug, level adjusters and screws etc. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. The last hanger at the end of each main Runner should not be greater than 450 mm from the adjacent wall. Flush fitting of 1200 mm long cross tee (with double stitching) to be inter-locked between main Runners at 600 mm centre to form 1200 mm x 600 mm modules. Cut cross Tees longer than 600 mm to be supported independent-ly. 600 mm x 600 mm modules top be formed by fitting 600 mm x 600 mm modules to be formed by fitting 600 mm long cross Tee centrally between the 12 mm cross Tee. Perimeter wall Angle shall be of 0.45 thick GS Steel and of size 22 mm and 3000 mm long of white color. The work shall be as per standards and specifications laid down by the manufacturers. Full provision of weight of a/c ducting (if provided) and light fittings, wiring for any use, including co-coordinating with all trades and making any cutouts required for the same, all complete with a minimum of 2 coats of premium quality Acrylic emulsion paint and full finishing for light fittings all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.</p>	SqM.	20		
7	<p><b>FULL/LOW HEIGHT SEMI/FULLY GLAZED/SOLID PARTITION</b></p>				
	<p>Providing and fixing double skin partly paneled &amp; partly glazed or solid full /lowheight partition with frames of 50 mm x 38 mm (finished size) seasoned hardwood members at maximum intervals of 450 mm x 450 mm with provision of bigger members at skirting, fixing to false ceiling (if provided) fixing to RCC Slab, Beams etc. all wood work to be treated with 1st quality anti-termite paint and covered with 6 mm thick MR grade plywood/ of Green/Century/Asean/ Tajpuria (9yrs warranty minimum) and .8 mm thick (Greenlam / century/merino/ /durian) blue / white high gloss laminate with grooves / small / panels cut and pasted in the same as per typical design, on both sides so as to form double skin partition to level 900 mm and with 5.50 mm clear float toughen glass of approved make as above at item-1 of Modi float or equivalent above, etched / etching film pasted as per design fixed in wooden frame and with teak wood beading as per detail design, which is to be of 1st quality teakwood (all visible wood to be of 1st quality teakwood) and shall be polished and protected with melamine polish. The wooden frame of the partition shall continue right up to the ceiling as shall be firmly fixed to the ceiling and ground by means of Rawal Plugs etc necessary fasteners so as to form a stable system / partition all . <b>Panel box</b> shall be measured in partition</p>	SqM.	40.00		
8	<p><b>LOW HEIGHT SINGLE WINDOW COUNTER</b></p>				
	<p>Providing and fixing low height Single Window counters / Case Manager's table with a maximum width of 3'0" in required shape as per typical design. The main structure of the counter is to be made of 19mm thick BWR block board of Green/Century / Mayur /Asean/Tajpuria with 0.8mm sunmica of greenlam.marino/durian on exposed surfaces. The width of the counter should have 5'0" (with disc credenza / cabinet of 1'4" wide and maximum 3'6" length / depth (in-cluding width of counter). The vertical supporting members of counter are to be made of 19 mm thick BPW Phenol Formaldehyde block board of Green/Century /Asean/Tajpuria don-8 box shall be provided by the bank would be fitted properly in right hand side. The key board pullout tray of to be provided in addition to key board drawer with lock and key make arrangement of standard make to be decided by the Bank. The left hand side should have cabinet made of 19 mm thick BWRplywood and cavity keeping CPU as per design / drawing. The counter top have a neat hole to be made in the table for connecting the wires which is to be covered with a dark colored PVC insert (wire manager) with moveable parts to put the wires and sockets to cover the hole neatly. The exposed block – board/ plywood to be covered with 1.0 mm thick blue / white high gloss laminate of Greenlam /</p>	Rmt	6.8		

	to be covered with 1.0 mm thick blue / white high gloss laminate of Greenlam / Marino / Century or equivalent of approved shade and colour. Exposed portions to be also covered with 0.8 mm thick blue / white high gloss laminate of approved shade and colour. The internal and non-visible side of all drawers, cabinets and counter table shall be painted with 3 coats of enamel paint over one coat of primer on the internal side. Glass portion made of 12 mm thick toughen glass of approved make as per design and specification securely fixed in toughen section as per design and details and all necessary standard quality of fittings, hardware, locks (make or equivalent & its payment on measurement basis). Door shutter of 19 mm BWR board to be fixed at the rear side of counter with automatic locking system from Godrej or equivalent. Lock to be paid in lock items.				
<b>9</b>	<b>CORIAN WORK ( TABLE TOP )</b>				
	Providing and fixing 6mm corian sheet on the top of CM table with credenza and top of back low ht cabinet with all polishing work including 50 mm front fascia, colour shade as per selection of Bank and Architect. Make marino	Sq.M	14.50		
<b>10</b>	<b>Column / Wall Panelling (upto false ceiling ht)</b>				
	Providing and fixing in position panelling made out of GI /BWR PLY frame with intermediate spacing of 600mm c/c horizontally as well as vertically. Frame to be covered with 8mm thick BWR Grade ply/ 12mm thick MR GRADE MDF board (of approved/equivalent make). The surface so prepared shall be pasted with 0.8 mm thick blue / white high glossive/matt finish laminate (of approved or equivalent make). Measurement will be done upto false ceiling only. All work to be completed as per drawing, design, specification and direction of Engineer-in-charge /Bank. All electrical wires, accessories, telephone wires, etc, shall be run in the panelling as per Electrical Drawings and designs. Nothing extra shall be paid for the coordination of the same. All items necessary for completing the above mentioned work are deemed to be included in the scope of work, whether or not they are specifically mentioned in the B.O.Q / tender documents / drawings. All complete as per drawings, designs, specifications and directions of Engineer-in-Charge.				
	Wall And Column panelling (BM Chamber, SWO Back and Column)	Sq.M	60.00		
<b>11</b>	<b>GRAHAK MITRA</b>				
	Providing Grahak Mitra Counter of size 3'-0" x 3'6" with side credenza of 2'3" x 6'0" in approved shape as per design of Bank made up of 19 mm thick BWR grade block board of Green / Century brand/ Exterior Grade MDF board/Asean/Tajpuria ply of Green/Century or equivalent and make as above mentioned at item – 1 above, top laminated with 1.0 mm high glossive laminate with all complete work as per drawing, design., specification and direction of Engineer-in-charge /Bank.	No.	1.00		
<b>12</b>	<b>LOCKS</b>				
	S/F/F Godrej mortise locks/ Night latches including cost of labor & materials etc. to complete job.	No.	7.00		
<b>13</b>	<b>FOOT REST</b>				
	Providing and placing foot rest made of 19 mm BWP grade block board with wooden lippings top clad with rubber mat. All inner portions shall have a coat of mat finish enamel paint all complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank. Materials shall be above at item	No.	6.00		

<b>14</b>	<b>HYDRAULIC DOOR CLOSER</b>				
	Providing and fixing hydraulic Hardwyn, Everite or approved make equivalent door closures of Hardwyn, Everite or equivalent approved brand and sample – all complete as per instructions of the Bank. All complete work as per drawing, design. Specification and direction of Engineer-in-charge /Bank.	No.	4.00		
<b>15</b>	<b>ROLLING SHUTTER BOX COVER/PANELLING/PARTITION OF ACP</b>				
	Providing and fixing ACP for panelling, partition, ACP panelling for branding and cover box: Providing and fixing of ACP cover, panelling, partition for rolling shutter/ATM/Washroom set within inner box section cover frame sections placed at suitable spacinfng not exceeding 600mmc/c. The work is to be finished with 3mm thick exterior grade Aluminium Composite Panel (ACP) cladding of approved make and shade with grooves duly treated with silicon sealant. The work is to include all necessary materials, ac-cessories, labour, tools & tackles. Executed covered area shall be measured for fin-ished work.	SqM.	7.00		
<b>16</b>	<b>DTEL BOX</b>				
	Providing D-Tel depository cabinet of Godrej/equivalent/approved make in counters of size-691mm x 460mm x 460mm of weight 33.00 kg of automatic locking including of cost of labors & materials etc. to complete job as per specification & direction of E/I.	No.	2.00		
<b>17</b>	<b>SHOWCASE RACK</b>				
	Supplying and fixing of award or achievement showcase in BM Chamber of minimum size 5ftx4ftx8"deep of wooden/plyboard with glass shutter on the elevation area as per the requirement of branch or direction of EIC.	No.	1.00		
<b>TOTAL in INR Excl. GST</b>					
Note:-Rate is for delivery at Site along with transportation cost.					
1) Extra members, wherever required for stability / otherwise, to be provided with the required finish without any extra charges.		<p>ALL PLY/MDF MAKE -Green ply /Century/Austin/ACTION TESA/Green panel/ASEAN/Tajpuria/equivalent as per technical specs. Use of MDF as per direction of EIC. Vendor shall not be allowed to use the MDF at any place without prior permission by EIC in the layout.</p> <p>Laminate/Mica - Greenlam/Marino/Century/Europrateck/Durian/ as per technical specs</p> <p>Hard ware and fitting as mantioned in specification refer technical specs/item description</p> <p>Rate is exclusive of GST GST payable as per Bank rule.</p>			
2) Any damages caused to the walls, ceilings, floors, etc. shall be made good by the Contractor by refinishing the same in exactly the same manner, so as to leave the surfaces in a good-as-new condition. A final coat of paint on all painted surfaces shall be deemed to be included in the occupation, so as to leave the premises in a suitable condition for occupancy.					
3) Contractor shall made and get approved shop drawings of all items prior to fabrication / manufacturing of the same.					
4) In case of partitions / panelling / etc., if any corbellings, cornices, etc. are called for, these shall be done as shown in the drawings, designs, etc., or as per the requirement of the Employer / Architect, and these shall be paid for at the square foot rate quoted by the contractor. Nothing extra over and above the square foot rate shall be payable to the contractor					
5) The contractor shall extend full co-operation to the other contractors viz. Electrical, Airconditioning, and any others who may be working in the said premises.					

(Signature)  
Authorized Signatory