

PRICE BID

NAME OF THE WORK: INTERIOR WORKS OF STATE BANK OF INDIA ,VRM, 3RD FLOOR, PRAGATI BHAWAN, URBAN ESTATE PHASE-III, PATIALA (PB)					
S.NO.	SPECIFICATIONS	QNTY.	UNITS	RATE	AMOUNT
1	FALSE CEILING -(MINERAL FIBRE TILE):				
	Providing & fixing Armstrong false ceiling RH-99 with 600x600x16 mm Fine Fissured Beveled Tegular Edge false ceiling laid in Armstrong silhouette grid system. The frame work comprises of main runner spaced at 1200 mm centres securely fixed to structural soffit by approved hangers at 1200 mm maximum centres. Hangers (G.I. wires 4.0 mm dia) to be fixed by approved roof plug, level adjuster, screws etc. The last runner should not be more than 450 mm from the adjacent wall. Flush fitting 1200mm long cross tee(with double stitching) to be inter locked between main runners at 600mm centres to form 1200x600mm module. Cut cross tees longer than 600mm to be supported independently. 600x600mm module to be formed by fitting 600 mm long flush fitting cross tee centrally between 1200mm cross tees. Perimeter trim to be Armstrong wall angle secured to wall @ 450 mm maximum centres. The rates include making opening for electric fixtures, A.C units etc. Rates include dismantling existing false ceiling and removal of malba from site, complete in all respect.	380.00	sq.m.		-
	MAKE: Armstrong, St. Gobain (India Gypsum)				
2 (a)	GYPBOARD FALSE CEILING INCLUDING PAINT				
	Providing and fixing suspended false ceiling including steps as per design with 12.5mm tapered edge Gypsum Board to the grid comprising of cold rolled galvanized metal section to the required line and level.The grid consists of a perimeter channel (MF6a of dimensions 20mm x 27mm x 37mm x 3.5M) fixed round the perimeter to receive and of the ceiling section (MFS) and the outer edges to gypboard. The intermediate channel (MF7) of dimensions 15mm x 45mm x 0.9mm x 3.6M) at 1200mm c/c in the one direction and the ceiling section (MFS of dimensions 80mm x 26mm x 0.5mm x 3.6M) at 450mm c/c in the other direction are connected by a connecting clip (MF9). The grid is suspended with an adjustable strap hanger (MF9). The grid is suspended with an adjustable strap hanger (MF8) of dimensions 25mm x 0.5mm) at 1200mm c/c on both ways from the structural soffit using a soffit cleat and expandable bolts/fasteners Nut and bolts are used to connect strap hangers to soffit cleats and for joining ends of channel sections together.	430.00	sq.m.		-
	The gypsum board layers are screwed to the M/F ceiling sections with gypboard drywall screws. Jointing and screw spotting are then carried out as per manufacturer's standard recommendations. Perimeter Channels (MF7) to be used around the cut outs for light fittings. AIC ducting etc. The work includes painting with 2 coats of plastic emulsion to give an even & finished surface. The payment area will be the visible area only The work should be complete as per instructions of Architect or Engineer in charge.				
	MAKE: St. Gobain(India Gypsum), Lafarge				
2b	GI METAL CEILING				

Signatures of Contractor with Seal

	Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc.				
	Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be prepainted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.				
	GI Metal Ceiling Lay in plain Tegular edge Global white color tiles of size 595x595 mm, and 0.5 mm thick with 8 mm drop; made of G I sheet having galvanizing of 100 gms/sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	45.00	sq.m.		-
	Makes: Armstrong, MAC, ALSTRONG				
3	COVE IN CEILING:				
	Providing and Fixing of Cove (3"x6") in Gypsum Board with specifications same as item No.2	122.00	mtr		-
	MAKE: St. Gobain(India Gypsum), Lafarge				
4	EXTRA FOR PROVIDING VENEER WITH POLISH IN CEILING				
	Providing and fixing 4mm thk. VENEER in ceiling over 12mm thk. commercial ply screwed(IN PLACE OF GYPBOARD) to GI ceiling sections work as item number 2 above .The work includes providing grooves as per pattern, spirit polished of approved shade on the veneer surface. Payment shall be made for the visble finished area. The work should be complete as per instructions of Architect or Engineer in charge.	111.00	sq.m.		-
	Basic Rate of Veneer: Rs. 75/- psft				
	MAKE: Greenply, Century, Timex, Duroply				
5	WALL PANELLING				
	Providing and fixing paneling over the existing wall made out of framework of 50 mm X 25 mm - 18 gauge section un annodised Aluminium (as per requirement) frame work @ 16" to 24" c/c vertically & horizontally. The frame work to be clad with 8.0 mm thick commercial ply and following finishigs as per drawing and instructions.				

	All exposed surfaces to be clad with teakwood moulding of size 30 mm X 12.0 mm made to shape. The work should be complete in all respects including provisions of grooves duly designed & finished. All wood to be treated with wood preservatives of approved ISI quality. All exposed teak wood shall be spirit polished with matching pigment. The rate shall include for providing grooves in laminate & wood. Payments shall be made only for exposed surfaces & actual measurement at site, no payment shall be made for paneling behind furniture such as tables, Credenza, storage etc.				
a)	Panelling with 4.0MM thick veneer with polish (basic rate: 75/- psft)	81.00	sq.m.		-
b)	Panelling with laminate (1.0mm thick)	60.00	sq.m.		-
	Makes:				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
	<i>Veneer: Greenply, Century, Timex, Duroply</i>				
6	FULL HEIGHT PARTLY GLAZED WOODEN PARTITIONS & DOORS				
(a)	Full Height partly Glazed (with etching) & partly both side laminated Partitions: Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be clad with 8mm thick commercial ply and 1.0mm thick laminate APPROVED make in specified pattern as per interiors details on both sides. Also 1-1/2" x5/8" teak wood beading shall be provided on both sides of 8mm thk. glass with etching work as per interior details where ever specified. The rate shall also include for providing grooves in laminate & wood.	113.00	sq.m.		-
	Wherever applicable, the doors shall be a part of full height partitions & shall be provided with 35mm thick commercial block board, with laminate 1.0mm thick on both side, as per pattern & with grooves as per design. 38mmx6mm thick teakwood lipping shall be provided all around the edges of the door & finished with spirit polish, complete in all respects. Basic hardware like mortice lock/dead lock/handles, hinges, door stopper shall be a part of the door & will not be paid extra,				
	<i>Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.</i>				
b)	Extra for providing 4.0MM thick veneer instead of Laminate as above, as per pattern with grooves & melamine polish, complete in all respects	12.00	sq.m.		-
	<i>MAKE: Greenply, Century, Timex, Duroply</i>				
c)	WOODEN RAFTER(4"x4")				
	Providing and fixing partition made out of wooden rafter 4"x4" fix on floor or ceiling with gap of 6-9" in between two rafters. The rafter shall be made up of 19mm commercial ply providing with 4.0mm thk veneer all round with polish finish, complete in all respects.	30.00	rmt.		-
	Makes:				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				

	VENEER: Greenply, Century, Timex, Duroply				
7	LOW HEIGHT WOODEN PARTITION WITH LAMINATE (PARTLY GLAZED/SOLID) 4'-3" high				
	Providing & fixing partition made of 44 mm X 44 mm X 16 Gauge aluminium extruded sections frame @ 2'-0" to 2'-0" c/c vertically & horizontally. The frame shall be fixed rigidly at floor level as well as ceiling with rawl plugs. The frame work to be clad with 8mm thick commercial ply and 1.0mm thick laminate APPROVED make in specified pattern as per interiors details on both sides. Provision for softboard panels with fabric to be made as per details & drawings, fixed with 20mmx20mm wooden beading all around with polish. Also 3"x5/8" teak wood section shall be provided on the exposed edges of the partitions, including providing groove for 12mm thick glass wherever specified. The rate shall also include for providing grooves in laminate & wood and also to include 12mm th. glass with etching.	280.00	sq.m.		-
	Note: (i) All ply to be sprayed with anti termite and anti borer spray. (ii) Rates to include all necessary supports and as per details (iii) Measurements to be recorded up to finished false ceiling level.				
	Makes:				
	Commercial ply: Century, Greenply, Archid ply				
	Laminate: AICA, Greenlam, Merino, Formica				
8	STORAGE CABINETS				
	Providing & fixing storage cabinets, 18" deep & height as specified, made out of 19mm thick commercial plywood, including the inner shelves & shutters. The visible external surface shall be provided with 1.0mm thick laminate of shade specified, whereas internal surface including both sides of shelves shall be provided with balancing laminate of 0.8mm thickness. All the exposed edges of shutters & shelves shall be provided with beechwood lipping 5mm thick with clear polish finish. The shelves shall be spaced at approx. 15" vertically/as per drawings. The cabinets shall be complete in all respects with handles, catchers, locks, tower bolt(inside) etc.				
	In low height / back storages, drawers shall be provide as per design, running on telescopic channels. Internal surfaces shall be provided with 0.8mm th. Balancing laminate., whereas the visible top shall be provided with 1.0mm thick laminate				
a)	FULL HEIGHT STORAGE	50.00	sq.m.		-
b)	4'-3" HIGH STORAGE	38.00	sq.m.		-
c)	2'-6" to 3'-0" BACK STORAGE	18.00	sq.m.		-
	Makes:				
	Commercial ply: Century, Greenply, Archid ply				
	Laminate: AICA, Greenlam, Merino, Formica				
	Locks: Godrej, Ozone, EBCO				
9	TABLES & WORKSTATIONS				

	Providing & Fixing tables / workstations made of 19 mm thk. Commercial ply with front and side visible vertical surfaces to be finished with laminate 1mm thick (of approved shade); with 40 mm X 6 mm thick beech wood beading all around, as per drawing. The front of the table top shall be projected as per drawing. Provision for 3" dia. round / 3" square cable manager for computer/ electrical cables at appropriate place will be made in the top surface of the table. 2.0 mm Thick PVC edge banding tape will be provided on all the edges of the table,. The table shall have a keyboard tray of size 600 X 270 fixed on channels. A full depth CPU shelf 15" wide shall be provided at one side of table underneath the working top, which will be made of 19mm thick commercial ply finished with laminate 1mm thk. 15" wide drawer cabinet with one lockable drawer running on side mounting drawer slides (channels)& one shutter below, made of 19 mm thick commercial ply with 1mm thick laminate on front face, handle / knob shall be provided. The sides of the drawer shall be made of 12 mm thick plywood , bottom of 6 mm thick plywood. A full length foot rest made of hard wood 3" x 1½" section shall be provided at 4" above floor level. Inside of drawers & Non-Visible/ inside surfaces i.e. inside / leg-space of table, inside of cupboard will have white coloured 1mm laminate. Teak wood edges / lipping / beading shall be Spirit polished.				
a)	CM desk of size 7'x3'x2'-6" with side return of size 4'-0"x1'-9"x2'-3"	1.00	no.		-
b)	Officer Table 5'-6" x 2'-6"x 2'-6"	6.00	no.		-
c)	Workstation 5'-3" x 2'-6" x 2'-6", without drawer cabinet. A full length platform/footrest, 1'-6" wide shall be provided below the table. Size of the keyborad shall be 3'-6" wide (suitable for 2 keyboards side by side). The edges of table shall be provided with 2.0 th. PVC edge banding tape, complete in all respects.	79.00	no.		-
d)	Meeting Room /VC table: 24'-0" x 4'-0"	1.00	no.		-
e)	Reception Table 5'-0" x 2'-3"	1.00	no.		-
	Makes:				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
	<i>Telescopic Channels: Godrej, EBCO, Ozone</i>				
	<i>Drawer Locks: Godrej, Ozone, EBCO</i>				
	<i>PVC Edge banding Tape: REHAU, Dorby, E3,</i>				
10	SIDE CREDENZA:				
	Providing & fixing Side credenza 3'6" long & 15" deep, made of 19 mm thick commercial ply (ISI marked- GREEN (Ecotech)/ CENTURY (Sainik) and 6 mm thick plywood on back side & 1mm thick laminate of approved shade on top horizontal surface & vertical visible side only, with teak wood lipping on all edges including bottom touching floor. The credenza will have two drawers on top, horizontally running on side mounting drawer slides (channels) of EBCO/ GODREJ make, & inner surfaces finished with 1mm thk. white/off white laminate. The remaining part of the credenza will have cupboard with shutters and one shelf, with handle /knob and magnetic catcher. Drawers & shutters shall be provided with locks. All non visible/inside surfaces shall be finished with 1mm thk. white/off white laminate and teak wood edges/ lipping/ beading shall be Spirit polished with matching pigment.				

	Officer's & Staff side credenzaas per Drawing & specification mention in item above. Size - (W X D X H)				
a)	SIZE: 3'-6" X 1'-6" X 2'-3"	65.00	sq.m.		-
	Makes:				
	Commercial ply: Century, Greenply, Archid ply				
	Laminate: AICA, Greenlam, Merino, Formica				
	Telescopic Channels: Godrej, EBCO, Ozone				
	Drawer Locks: Godrej, Ozone, EBCO				
11	12mm THICK FIXED TOUGHNED GLASS IN PARTITIONS				
	Providing & Fixing 12mm thk. Toughned Glass Panels with SS glass connectors of 304 Grade / Wooden beading, fixed in position, with etching / filming, as per interior details/instruction of the Achitect/Engineer in charge.	38.00	sq.m.		-
	Make: Asahi India, St. Gobain,				
12	12MM THICK TOUGHNED GLASS DOORS WITH PATCH FITTINGS & ETCHING/LOGO:				
	Providing & fixing frameless fully glazed 12 mm thk. toughend glass doors, single leaf glazed Toughned door of size approximately, 1200mm (to750mm) X 2100 mm all sides edge grainded, polished to be fixed on patch fittings. The glass door shall be provided with patch fittings such as PT 40, 10, US 10, PT 24, pull handle 450 x 38 and floor spring conforming to DIN EN 1154. The cost including cutting, making holes, cutouts in glass of required shape and size to accomodate fitting etc. the rate shall be include nessessery etching film / logo all inclusive, complete	13.00	sq.m.		-
	NOTE: Rates include Top pivot, Top patch fitting(s), Bottom patch fitting(s), Corner / Central lock(s) with strike plate, Floor spring, 1'-6" SS door handle (both sides) etc. all complete.				
	Makes: GLASS: Asahi India, St. Gobain,				
	Hardware (patch fittings etc): Godrej, Ozone, Dorma				
12(b)	WCP (Wall Connecting Profile):				
	Providing & fixing aluminium extruded WCP, comprising of frame profile, clamping profile and two contact rubber extrusions (PVC), suitable for 12mm thick glass, fixed to wall/partition, on top & bottom of the glass, using suitable screws / fasteners, complete in all respects	64.00	rmt		-
	Make: Dorma/Ozone / Enox (EAPS 1032)				
13	WOODEN BOXING AT MAIN ENTRANCE				
	Providing & fixing wooden boxing on wall/columns as per details, using 19mm thick commercial ply, with 1 mm thick laminate fixed as per pattern, complete in all respects.	60.00	sq.m.		-
14	DOOR CLOSER:				
	Providing and fixing silver colour (or matching with colour scheme as per site) hydraulic door closer Godrej /Dorma / Hardwyn make, to Doors complete in all respects.	5.00	no.		-
	Make: Godrej, Dorset, Ozone				
15	ROLLER BLINDS (ZEBRA BLINDS)				

	Providing and fixing Rolling Zebra blinds made of fabric, design and shade, as approved by the Architect, including rolling channels and other fitting complete in all respect, as per manufacturer's specifications. Make : FARRARI/ VISTA/ MARVEL.	110.00	sq.m.		-
	<i>Make: Vista, Ferrari, Marvel</i>				
16	WOODEN BOXING FOR ELECTRICAL PANEL (18mm FIBRE CEMENT BOARD)				
	Providing & fixing at site cabinet 8'-6"height having overall depth of 1'-6".the carcase shall be made of <u>18mm thk Fibre Cement Board</u> . The shutters shall be made of 18mm thk Fibre Cement Board. with 1.0mm thk laminate on outer surfaces using suitable adhesive. The shutters shall be mounted on <u>heavy duty overlap type SS hinges</u> & provided with magnetic catchers, lock & towerbolts as required with 5mm thk teak wood lipping on all the exposed edges, duly spirit polished. All internal surfaces, & back of shutters shall be painted, complete in all respects. MAKE : ZYKRON (Century Ply) / SHERA Board / Equivalent	9.00	sq.m.		-
	Makes:				
	<i>FIBRE CEMENT BOARD: Zyrcon(Century), Shera Board, Gyproc (St. Gobain)</i>				
	Laminate: AICA, Greenlam, Merino, Formica				
17	LACQUERED GLASS				
a)	Providing & fixing 6mm lacquered glass (St. Gobain "Planileque" or equivalent), in panelling / partition, fixed using clear silicone adhesive, complete in all respects.	10.00	sq.m.		-
b)	Panelling with 6mm lacquered glass (Custom painted in blue color with white lines as per design), fixed to walls over a layer of 12mm thick commercial ply/mdf using clear silicone adhesive, complete in all respects.	2.00	sq.m.		-
	Makes:				
	<i>Lacquered Glass: St Gobain (SGG Planilaque), AIS</i>				
18	BANK LOGO & LETTERS				
	Providing , making to shape and size using CNC Cutting (as per the design provided) and fixing to position SBI bank logo & letters made out of 19mm thick HDHMR sheet, finished in PU paint (to be done as per manufacturer's specifications)as per colors specified (Blue/White/Metallic gold) fixed over laquered glass with suitable adhesive (nail-free or silicone etc.) etc complete in all respects				
a)	SBI logo 10" dia / English letters 10" high	4.00	no.		-
b)	English letters 6" high	7.00	no.		-
	Make:				
	<i>HDHMR Sheet: Geenpanel, Action-Tesa, Centurey Ply</i>				
	<i>PU Paint: Asian (PU Palette), Birla Opus, Nippon</i>				
19	WOODEN PELMET				

	Providing & fixing in ceiling, wooden pelmet 6"x6" made out of 19mm th. Commercial ply, with 1.0mm th. Laminate on visible surfaces. All the edges will be provided with wooden margin with polish / matching PVC edge banding tape. All other inner surfaces shall be provided with enamel paint of shade as approved.	26.00	mtr		-
	Makes:				
	<i>Commercial ply: Century, Greenply, Archid ply</i>				
	<i>Laminate: AICA, Greenlam, Merino, Formica</i>				
20	LOUVERED PANELLING				
	Providing & fixing WPC louvered panelling of approved design & shade, using suitable clips, adhesive etc. Ends of the panelling shall be properly finished by providing corner profile asrequire, complete in all respects	20.00	sq.m.		-
	Makes:				
	LEBEN/EURO PRATIK/Dorby/equivalent				
	TOTAL				-
	GST EXTRA @ 18%				