

**SEPON BRANCH, ASSAM**  
**BOQ FOR AIR CONDITIONING INSTALLATION WORK**

| Sl. No. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Unit        | Qty. | Rate (Rs.)(excluding | Amount (Rs.) (excluding GST) |
|---------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------|------|----------------------|------------------------------|
| 1       | Supply Installation testing and Commissioning of 1.5 TR Capacity Hi Wall mounting 5-star rated Inverter Split AC with cordless remote and Copper Condensor Coil. AC Make, Voltas/Bluestar /Carrier/Daikin /LG/Godrej( INCLUDING 3 M COPPER PIPES)(refrigerant (R32 or R 410A)                                                                                                                                                                                                                                                                                                                                                                                                                                                      | Nos.        | 1    |                      |                              |
| 2       | Supply Installation testing and Commissioning 2.0 TR 4-way Cassette Type Inverter AC, 5 STAR with Copper Condensor Coil and refrigerant (R32 or R 410A) Indoor unit ceiling hung comprising cooling coil, evaporator fan with motor, filters, insulated drain pan, drain pump, expansion valve, refrigerant filter drier with codeless remote control unit, etc. Outdoor unit comprising single phase hermetically sealed scroll / rotary compressors, condenser coil with fan & motor, starters / controls / cutouts / relays etc., mounted inside a powder coated sheet metal cabinet of 2mm thick, duly treated for corrosion protection complete, mounted on ribbed rubber pads. AC Make, Voltas/Blue Star/Carrier/Daikin /LG" | No.         | 5    |                      |                              |
| 3       | <b>For 2.0/3.0 TR Copper Cassette type split air conditioners:</b> Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessities and making good all the damages.                                                                                                                                                                                                                                                                                                                                                                                          | RM          | 115  |                      |                              |
| 4       | For 1.0 TR/1.5 TR Hi-Wall type split air conditioners: Supply and laying of copper pipes, drain pipes (covered with GI pipes wherever necessary), copper wiring in GI conduits neatly drawn in professional manner from power points to outdoor / indoor units complete with all necessities and making good all the damages.                                                                                                                                                                                                                                                                                                                                                                                                      | RM          | 15   |                      |                              |
| 5       | Supply and Installation of 5 KVA Stabilizer for 1.0/1.5/2.0 TR Split type Acs(voltage range 120V to 270V)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Nos.        | 6    |                      |                              |
| 6       | Electronic Timer for alternate operation of Air Conditioning unit                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Nos.        | 1    |                      |                              |
| 7       | MS structure catwalk for maintenance of Air conditioner outdoor unit 750mm width and 5000 mm length with hand rail FOR AC.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | LOT         | 1    |                      |                              |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Grand Total |      |                      |                              |