BILLS OF QUANTITIES FOR PROPOSED INTERIOR FURNISHING WORK (LOOSE & FIXED FURNITURE) OF STATE BANK OF INDIA FOR SME NARODA BRANCH, DIST. AHMEDABAD

SN	Description	Quantity	Unit	Rate	Amount
	Note: Rate should be inclusive of material, labour, tools, machinery, scaffolding, final disposal of debris, cleaning cutting wastage etc. All taxes, transportation etc. complete. (Excluding GST) GST will be paid as Applicable at the time of payment of Bills.				
	FURNISHING WORK				
	Note : for all work stations				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 6 mm thick white corian				
	2) **Front Appron:** Round Corian and 6 mm thick blue lacquered glass fixed with Natural Silicon				
	3) **Facing of Drawers:** 1.00 mm thick laminate finish				
	The W.S. should have Ready Made Foot Rest. High impact polystrene with chrome plated metal structure of approved make. **C.P.U. trolly with castors/roller supports/ Nylon castors.**				
	There should be provision for cable manager(Metal Cable Manager) system with necessary cutouts in top surface				
	Key board tray with mouse pad made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete				
	Heavy duty *telescopic full extension* sliding channel of approved make shall be used in all drawers.				
1	**SINGLE WINDOW COUNTER / CASH COUNTER SIZE 5'-0" X 2'-9" with White corian & blue lacquered glass finishing**	4.70	RMT		
	Supplying, fixing and keeping in position single window counter complete as per design and drawing made out of 18 mm thick commercial ply wood of approved make, complete with 19 mm. C.P. Teak wood lipping on all edges wherever required.				
	The cost shall be inclusive of S & F of a drawer unit or drawer & shelf unit with 18 mm thick commercial plywood and with approved make multipurpose Auto Lock in drawer and shelf unit. The cost shall also be inclusive of the following.				
[a]	size :				
	Description: L B H				
*	Writing Top 5'-0" 2'-9" 2'-6"				
*	4 Drawers with				
	pigeon hole 2'-0" 1'-3" 2'-0"				
*	Side Crdenza 3'-0" x 1'-4" x 2'-6" x 4 Nos				
*	Side Credenza(Side Rack/Storage):For S.W Countwer Same as above item but Side Table Top and edges shall be finished with 6 mmThick White Corian on Top and Edges. All other visible surface shall be finished with 1.00 mm th laminate. Size shall be 3'-0"x 1'-4"x2'-6" ht. With openable shutter as directed				
*	Providing and fixing **12 mm thick Toughened Glass partition** on counter top, front side as follows. The counter will have additional 1 no. 12 mm th. Clear toughen glass of size: 5'-0"x 2'-6" with one number half round cutout for cash transaction and one number circular cutout (5" dia) for communication fixed with side partition with S.S. bracket. **Provide Round cutout in the glass partition, tapering to a 6" diameter toward the bottom.** (for four counters) **Provide Semi circle cutout in the Side glass partition from bottom**				
[b]	**Table Top:** Working table top and edges shall be finished with 6 mm thick white corian of DUPONT or equivalent approved make as per drawing and direction with all labour and material.				

SN	Description	Quantity	Unit	Rate	Amount
[c]	**Front Appron :** 2 nos 6 mm thick flexy ply wood in round shape with 6 mm thick white corian shall be provided at front as per design. All edges should be finished with corian of DUPONT make.				
[d]	Front pannel shall be finished with 6 mm thick 18" high blue lacqured glass of approved make and fixed on 18 mm thick commercial ply wood with Natural Silicon gum as per manufacturer's specification and to be completed as per drawing				
[e]	All wood work shall be laquer polished to a smooth and uniform finish of choice colour and shade.				
[f]	All fittings like S.S. handle, Auto Lock to each drawer and cabinet doors, piano / auto hinges, ball catcher, stopper, metal cable manager etc. should be fixed of approved make.				
[g]	Counter shall be made independent in Length of 5'-0" and properly placed between two partitions. Counter will be measured in RMtr between two partition and paid.				
1(a)	**Same As item No.1 But Without Front Glass**	1.50	RMT		
2	**Providing and fixing 12mm thick Toughened float Glass diaphragm partition between Single Window counters as follows.(For Curve shape glass between single windows & ATM dividers)**	2.00	SQMT		
	12 mm thick Toughened clear float glass with polished edges shall be fixed with silicon and T.W beading support on wooden partition as directed. All edges of glass shall be Diamond cut polished edges as directed complete. Wooden partition will be paid separately. Maximum length and height will be measured for payment purpose.				
3	**TABLES**				
	Note : for all work stations				
	FINISHING DETAILS IN NUTSHELL:				
	1) Table Top : 1.0 mm thick Dark laminate & Burma Teak beading on Edges with polished				
	2) **Front Appron & Sides:** 1.0 mm thick Dark Laminate				
	3) **Facing of Drawers:** 1.00 mm thick laminate finish				
	The W.S. should have Ready Made Foot Rest. High impact polysterene with crome plated metal structure of approved make. C.P.U. trolly with castors/roller supports/ Nylon castors.				
	There should be provision for cable manager(Metal Cable Manager) system with necessary cutouts in top surface				
	Key board tray with mouse pad made from CRCA steel duly powder coated. It must have built-in slides which, must have a soft palm rest and a stow-away design of mousepad mounted underneath it.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate of approved shade etc. complete				
	Heavy duty *telescopic full extension* sliding channel of approved make shall be used in all drawers.				
3A	**MANAGER TABLE SIZE: 7'-0" X 2'-9" X2'-6" HT. with Side Credenza & Laninate finish on Table Top , sides and all other visible surfaces etc complete as follows**	1.00	NO		
	Supplying and installation of Table as per the following description : Size 6'-0" x 2'-9". Table top shall be made from 18 mm thick commercial ply wood with 1.0 mm thick Laminate with necessary intermediate support. Table top shall be supported by 18 mm thick commercial ply wood with wooden framing. Drawers of size of 1'-3" x 2'-0" x 2'-6" shall be provided using 18 mm thick commercial ply wood having 4 Nos drawers as directed with heavy duty telescope sliding channel of approved make , grouplock, S.S. Handle. Ready made metal Key board with mouse pad of approved make shall be provided. Exposed surfaces of darwers shall have laminate, All internal surface will have 0.60 mm thick balacing laminate				

SN	Description	Quantity	Unit	Rate	Amount
3.1	**Apron (Modesty Panel) made from 18 mm thick ply wood finished in patten with fluted texture laminate of trapezoidal shape at middle and rest portion plain laminate of dark shade as per drawing**				
	Table side made from 18 mm thick ply wood with 1.0 mm thick Laminate finish shall be provided in a pattern as per drawing. Laminate to be provided on all visible surfaces.				
	Drawer Fascia made out of 18 mm thick Plywood. The sides/back/base of drawers be made of 12 mm thick Ply wood & Bottom of drawers shall be of 6 mm thick ply wood. fixing laminate on front side and all the internal surfaces shall be 0.60 mm thick balancing laminate. The drawers to be fitted with Telescopic sliding channel with SS Group locks of approved make and 100 mm long brush finish Stainless Steel handles for each drawer. All the edges of Drawer Fascia be provided with teak wood edge bending with laqucer polished etc complete as directed.				
	All exposed edges of teak wood shall have polished with smooth edges & corners				
	Exposed edges of Table Top, Leg panel & Side Shelf shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the surface without laminate / balancing laminate shall be lacquered polished of approved shade				
	Side Credenza Size 3'-3"x1'-4" x 2'-6"/3'-0" ht. Openable shutter with 1.00 mm thick Laminate finish on Top , front, sides, shutter and 35 mmx6 mm thick Burma Teak beading on Top Edges. Laminate to be provided only on visible surface etc complete as follows. Rest Description same as item 2[b]				
3B	Same as above Item-no-3 & 3A but Size: **4'-6"x2'-6" with side credenza** & with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces & front appron with 1mm th. Laminate finish of white shade except pattern as in item 3.1	6.00	NO		
3C	Same as above Item-no-3 & 3A but Size: **4'-6"x2'-6" without side credenza** with 4 Nos Drawer Unit with 1.0 mm thick Laminate finish on all exposed surfaces & front appron with 1mm th. Laminate finish of white shade except pattern as in item 3.1	2.00	NO		
3D	Meeting Table of **rectangular shape with round corners** and size **8'-0"x3'-0" without Drawer Unit** with 1.0 mm thick Laminate finished on all exposed surfaces	1.00	NO		
	Top shall be made from 18mm th Commercial plywood with 1 mm thk laminate of light shade rested on necessary intermediate supports having both side laminate of dark shade as directed. Providing Aluminium finish cable port 2 nos for installing Audio and computer system as directed complete. All visible surfaces of Table shall have lacquer polish as per instructions of Architects. All the non visible Inside and bottom portion of table should be 0.80 mm thick balancing laminate. Rate includes TW beading on edges of table with lacquer polish. All complete as directed.				

SN	Description	Quantity	Unit	Rate	Amount
4	**GRAHAK MITRA TABLE OF 4'6" x 2'-3" WIDE with Laminate finish**	1.00	NO		
	Same as above item no 3 but 4'0" Length & 2'-3" wide with storage unit in Table with 4mm thick MDF board + Blue and white Laminate finishing on all exposed visible surface as per drawing and instruction of Architect/Bank For Grahak Mitra/Tech Mitra (Help Desk Table)				
	Table top made from 18 mm thick ply wood + 4mm thick MDF board with Laminate finish				
	Apron (Front side) made from 18 mm thick ply wood + 4mm MDF board with Laminate finish				
	Both sides made from 18 mm thick ply wood + 4mm MDF board with Laminate finish				
	3" thick Partition above working table top made from 18 mm thick+6 mm thick ply wood with necessary framing with 4mm thick MDF board + Laminate finish as per drawing.				
	Exposed edges of Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	Drawer Storage Unit- 1'-4" W x 2'-0" D, 2 Nos Drawer on top and rest 1 No shutter				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
5	**CUSTOMER WRITING DESK**	1.00	NO		
	Writing Desk Size 3'-0" L x 1'-3" x (0'-6"+3'-0") ht.				
	Verticle Sides and bottom shall be made out of 36 mm (2X18) thick Commercial plywood and back side 12 mm thick ply wood with Laminate on Top and Edges on all sides including inside divisions. Top shall be made from 12mm th Thoughend glass with polished edges making different divisions by 18 mm thick glass / plywwod with laminate on both side for slips or forms as per detail drawing and inststruction complete. (Drawing as enclosed herewith) Laminate to be provided on all visible surface)				
6	**STORAGE CABINET (LHS/FHS) with Top & Front laminate finished. Storage of any height**	19.50	SQMT		
	Providing & Fixing Low/Full Height Storage cabinet of size 1'-4" width having Partly openable shutters as directed. Storage Cabinet shall be made from 18 mm thick commercial ply wood with 1.00 mm thick Laminate Finish. Back shall be made from 6 mm thick commercial plywood. Openable shutters shall be made from 18 mm thick commercial ply wood with laminate finished and approved make group lock, handle, hinges, magnet catch. , Rate includes all necessary provisions for installing computers. All the internal surface, back side shall have 0.60 mm thick balacing laminate.				
	Exposed edges of Sides, Table Top shall be made 36 mm thick by providing additional 18 mm thick ply wood patta of required width.				
	All the internal surface (non visible surface) shall be provided with 0.60 mm thick balancing laminate				
	all external surfaces to be finished with Laminate (approved shades)				
	FINISHING DETAILS IN NUTSHELL:				
	1) Top : Dark Laminate & Burma Teak beading on Edges with pilishade				
	2) **Front Appron & Sides:** Dark Laminate/Frosty white Laminate as per design & instructions				
	Cabinate shall be measured as (Length x Height) for the purpose of payment				

SN	Description	Quantity	Unit	Rate	Amount
7	**P/F ELECTRIC CUB BOARD**	2.15	SQMT		
	Providing and fixing Electric cup board using 18 mm thick Bison board for inside verticle division, shelves and shutter. Aluminium framing of 50x25x1.20mm thick with 6 mm thick Bison board on both side for outer partition with 1.0 mm thick laminate on all exposed surface and polishing/ synthetic enamal paint on all internal surface. Shutter will have approved make lock, handle, hinges, ball catches & S.S Perforated jali etc.complete as directed. Depth of cup board will be around 1'-3". Height of shutter will be maximum 7'-0". **Only Front elevation shall be measured for payment**				
8	**P/F PANTRY PLATFORM CUB BOARD SHUTTER**	1.50	SQMT		
	Providing and fixing cupboard shutters below pantry platform using 1 1/2" x 2 1/2" second grade T.W members for frame, 18 mm Tk plywood with 1.0 mm lamiante for shutters. Providing 1/2" th T.W beading all around shutter. Providing S.S hinges, Handles, stoppers and magnetic catch as directed. All the without lamiante surface shall be polished/ synthetic enamal paint as directed complete.Providing and fixing 0.60 mm thick balancing laminate on internal shutter surface				
	LOW HEIGHT PARTITION WORK				
9	**P/F LOW HEIGHT BOTH SIDE LAMINATE PARTITION FOR BACK SIDE AND IN BETWEEN S.W COUNTER AND CASH CABIN WITH TOUGHENED GLASS**	31.00	SQMT		
	Providing and fixing low height partition using 50mm x 25mm x 1.50mm thick Aluminium members maximum in grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply of approved brand on both side of aluminium framing and fixing 1.0 mm thick laminate of approved shade on both sides, fixing 12 mm thick transparent thoughened glass as directed. Applying polish on exposed steam beach members with lacquer polished edges as directed. Laminate to be provided only on visible surface.				
	For Low height Single window and Cash cabin partition, Average height of partition shall be measured and paid.				
10	**PROVIDING AND FIXING WICKET GATE WITH BOTH SIDE LAMINATE**	1.70	SQMT		
	Same as item no 9 but P/F 30 / 32 mm thick flush shutter with both side laminate including SS hinges with countersunk SS screws, Approved make Night latch Lock, S.S Handles,Door stoppers, doorstop etc complete as directed.				
	FULL HEIGHT PARTITION & DOOR WORK				
11	**P & F FULLY GLAZED PARTITION WITH PATCH FITTING**	10.50	SQMT		
	Providing & Fixing fully glazed Partition. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings.Bottom of Glass shall be fixed to ground and Top shall be fixed to wooden partition. The glass edges shall be polished on all sides. The entire Partition shall be erected in complete line & level. The patch fittings (Ozone make) shall be of aluminium with s,s, matt finish coating. The entire Partition complete in all respect should be installed in positions as required. The gap shall be filled with silicon fro packing as directed				
12	**P & F FULLY GLAZED DOOR WITH PATCH FITTING**	4.00	SQMT		

SN	Description	Quantity	Unit	Rate	Amount
	Providing & Fixing fully glazed door. The Item includes fixing of 12 mm th. Toughened glass with the help of top patch & bottom patch fittings. The door will have patch lock, pti pivot, 100 Kg floor spring & 25mm dia D shape 400 mm long handles both sides, (Ozone Make OGH-55P11-25X400), fixed with the glass by making necessary cutouts & holes. The glass edges shall bepolished on all sides. The entire door shall be erected in complete line & level. The door will have S.S brush finish Signage for pull & push. The patch fittings (Ozone make) shall be of aluminium with s,s, matt finish coating & signage shall be of kich make. The entire door complete in all respect should be installed in positions as required.				
12a	**PROVIDING AND FIXING 12 MM THICK TOUGHENED GLASS DIAPHRAGM FOR SEPARATING TWO M/C FOR e-LOBBY**	3.60	SQMT		
	P /F 12mm th Toughened glass Diapharm for Sepereting of between two M/C **with Frosted polyster films of 3M** complete as directed. Glass edges shall be round moulded and polish as per direction complete.Glass shall be fixed in wall and floor with necessary suitable patch fittings as directed. (Area based on outer diameters shall be measured and paid).				
13	**P/F BOTH SIDE LAMINATE SOLID/ PARTLY GLAZED FULL HEIGHT PARTITION WITH DOOR WITH DOOR CLOSURE**	32.00	SQMT		
	Providing and fixing both sides laminate full height partly glazed partition using 50mm x 25mm x 1.50mm thick Aluminium members in a maximum grid of 2'-0" x 2'-0" fixing 12 mm thick MDF Board exterior grade / 6 mm thick ply on both sides,1.0 mm laminate of approved make shall be fixed on MDF / plywood. Providing and fixing 5.0/8.0 mm thick float glass as directed in the partition. Providing and fixing door shutter using 32 mm thick flush shutter both side laminated and fixing 6 mm thick glass with beading patti, 5" Long 3 Nos stainless steel hinges, doorstop shall be provided as directed. Godrej Mortice lock shall be provided in door shutter.Providing and fixing "Dorma/Ozone/Godrej " or equivalent make door closure. All visible members if not laminated shall have lacquer polished as directed.				
	For purpose of payment partition height up to bottom of false ceilling only shall be measured and paid . No extra payment shall be made for members going up to slab/beam bottom.				
13a	**Providing and fixing Solid Bison Board Partiton with UPS door shutter with Aluminium Frame and one side Hilux sheet & Acp on other side.**	7.00	SQMT		
	Providing and fixing door shutter made out of 50x25x1.2mm thick aluminium framing at maximum 1'-6" C/C both way with 8 mm thick Hilux/Bison Board on one side painting & other Acp on other side. Steam beach beading of size 31x 12 mm should be placed around shutter edges, aluminium stoper patti on frame including 3 Nos 5" long SS hinges with countersunk SS screws, Aprroved make Dead Lock, S.S Handles,Door stoppers, doorstopper to be fixed as per drawing & instructions. All beadings should be polished. Rate includes providing ss jaali in door for ventilation of ups room.				

SN	Description	Quantity	Unit	Rate	Amount
	PANELLING WORK				
14	**P/F Wall panelling with laminate finishing for wall and Pillar etc**	25.00	SQMT		
	Providing and laying panelling on walls & pillars having 12 mm thick MDF Board exterior grade / 6 mm thick ply and 1.0 mm th laminate fixed on wall & pillars with Aluminium. framing of 25mmx50mmx1.20mm thick at maximum 2'-0" c/c bothways on wall and pillar etc complete as directed as per design and instruction of Architect. .				
15	**Plywood Box for Above Entrace Glass Door & Fixed Glass**	10.00	SQMT		
	Providing and fixing 18 mm.thk Ply with 1 mm laminate box as per shade and proper frame work for supporting and covering of above Entrance Glass Door, Fixed Glass Facade & Grills etc complete. Measurements shall be on actual site conditions and alignments of the door.				
16	Providing and fixing 8mm thick MDF Board exterior grade with jali work with high gloss PU coating over central column having 8mm thick MDF Board Exterior grade covered with 1 mm thick blue glossy laminate fixed on pillar with aluminium framing of 25mm x25mm x1.20 mm thick at maximum 2'-0" c/c bothway as per drawing and direction with all labour and material etc complete **(Rate shall be including CNC cutting jali work and 1 mm thick blue glossy laminate behind design jali work as directed)**	11.30	SQMT		
17	Providing and Fixing panelling on walls & pillars having using 25mmx50mmx1.20mm thick aluminum section in 2'-0" c/c bothways with 8mm th plywood to be finished with **Fluted Panel** and paint or polish complete as directed as per design and instruction of Architect. .	26.35	SQMT		
	Note: Sample of Panel must be got approved from Architect/Bank's Officials before using				
18	**Panelling for Digital wall with Blue / white high gloss PU Coating finishing**	4.00	SQMT		
	Providing and laying panelling on wall having 8mm th MDF Board exterior grade with PU coating fixed on wall with Aluminium framing of 25mm x 25mm x 1.20 mm thick at maximum 2'-0" c/c bothways etc. complete as directed. **Only front elevation surface area shall be measured for payment.**				
19	**P/A WALL PAPERS on Digital wall**	11.50	SQMT		
	Providing and applying **Wall paper** approved by Architect / Bank's Engineer having basic price of Rs 100=00 Per Sq.Ft				
20	**ALUMINUM COMPOSITE PANEL**	57.50	SQMT		

SN	Description	Quantity	Unit	Rate	Amount
	Providing and fixing 3 mm thick aluminium composite panel of Flexi Bond / Euro Bond / Timex with 0.25 mm foil with 50 mm x 25 mm x 1.20 mm thick aluminium hollow section tray system with minimum 20 mm bending with silicon Dow Coming of GE seal proof - ACP of approved indian make complete as per selection and direction of Architect for front facade for the building. This item will be carried out as per manufacturer's specifications. Rate also includes providing trap door shutter with hinges, stoppers etc complete as directed. **Design as per Bank standered Drawing and Architect's instructions etc complete. TIMEX - DIAMOND WHITE - 111, NAVY BLUE -**				
	FALSE CEILING WORK				
21	**P/F GYPSUM BOARD FALSE CEILLING**	68.00	SMT		
	Providing and fixing Gypsum board 12.50 mm thick false ceiling in steps and design using Original Indian Gypsum board with original GI sheet section **of Gypsteel ULTRA (Gypsteel Ultra shall be used)** supporting system in line and level. Finishing the surface and **applying 3 coats of Plastic emulsion paint** as directed complete. Entire work to be done as per standard specifications of Saint Gobin Gyproc India.				
	After completion of work, certificate from Saint Gobain Gyproc Company shall be submitted along with bill stating that work is satisfactorily completed as per their specification.				
	Note : (1) Rate includes making necessary cut-outs for lighting fixtures (2) Pattas if any shall be measured in SqM and not in RMt and paid in SqM (3) Only finished visible surface area shall be measured for payment.				
22	**Providing and Fixing of Armstrong/Knauf Mineral Fibre Accoustical Suspended ceilling system with FINE FISSURED (MICRO LOCK) EDGE TILES With Armstrong Silhouette Exposed Grid**	127.20	SMT		
	Using Silhouette Grid with Fine Fissured microlook Edge Tiles. With necessary Angles at junctions as per company specifications as directed complete. Rate includes necessary cut outs for A/C Grills, diffusers light fixtures complete as directed. **Cutout for light and Diffusers will be deducted from area. Only Tiles cost will be deducted for payment purpose**				
	After completion of work, certificate from Company to be obtained and submitted with bill that work is carried out as per their specifications				
23	**SOFT BOARD**	2.50	SQMT		
	Providing & fixing soft board for pin up using moulded Steam beach frame of 1" x 1/2" with 6 mm thick commercial plywood on back side and 12mm th soft board on front covered with cloth of selected design of Basic rate of Rs. 150 per Rmt. Steam beach member shall have lacquer polish as directed.				
24	Supplying and fixing **Roller Blind** Blackout of approved make with selected fabric of approved design and shade. (Basic Price of Rs 135=00 Per Sq.Ft Excluding GST)	11.50	SQMT		
25	Providing and Fixing **Frosted polyster film of 3M** (Scotchcal 7725 - 324) or equivalent make over glass surface as per drawing & direction with all labour & materials to the satisfaction of the Architect/Bank as per manufacturer's specification. No deduction will be made for any cutting in the film.	15.00	SQMT		

SN	Description	Quantity	Unit	Rate	Amount
26	**Supplying and installation 3'-0" x 1'-9"x 1'-3" height Center Tepoy as follows.**	1.00	NO		
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.				
27	**Supplying and installation 2'-0" x 2'-0"x 1'-3" height Center Tepoy as follows.**	2.00	NO		
	Providing and making open box structure type Tepoy made out of 36 mm (2X18) thick plywood with all over 1.0 mm thick laminate finish provided with bevelled & diamond polished edges 12mm thick glass top supported on 75 mm X 25 mm SS studs complete as directed.				
	TOTAL COST INTERIOR FURNISHING WORK "A"				
	SAY				

Tender Amount(In Words) Rupees:

(SIGNATURE OF TENDERER/FIRM)

NAME OF TENDERER

(SEAL OF FIRM)
PLACE:
DATE: